
### UNCONTROLLED DOCUMENT

PART NUMBER

REV.

## SML-LXR44USBC-TR



ELECTRO-OPTICAL CH	ARACTERIS	TKS TA=2	5°C	If= 20mA	
PARAMETER	MIN	ΤΥP	MAX	ZTINU	TEST COND
PEAK WAVELENGTH		470		nm	
FORWARD VOLTAGE		3.5	4.0	۷f	
REVERSE VOLTAGE	5.0			٧٢	I <sub>Γ</sub> = 1 🛮 Ο μΑ
AXIAL INTENSITY		170		mcd	I <sub>f</sub> = 20mA
VIEWING ANGLE		120		2x theta	
EMITTED COLOR:	BLUE				
EPOXY LENS FINISH:	WATER C	CLEAR			

#### LIMITS OF SAFE OPERATION AT 25'C

PARAMETER	MAX	UNITS
PEAK FORWARD CURRENT*	130	mA
STEADY CURRENT	<i>3</i> 0	mA
POWER DISSIPATION	105	mW
DERATE FROM 25°C	-1.2	mW/⁺C
OPERATING TEMP.	- 40 TO +85	<b>"</b> C
STORAGE TEMP.	- 40 TO +85	<b>"</b> C
<del></del>		

t<10µS

4.00 [0.157]	STO
<del>-</del>   <del>-</del> 2.00 [0.079]	* t.
Ø1.55 [Ø0.061]	RECOMMENDED SOLDER PAD LAYOUT
12.00 [0.472]	1.70 [0.067] (2 PLS.) 4.00 [0.157]
TOP TAPE / 8,00 [0,315] 2.50 [0	0.098]
TAPE FEED DIRECTION	

CAUTION: STATIC SENSITIVE DEVICE FOLLOW PROPER E.S.D. HANDLING PROCEDURES WHEN WORKING WITH THIS PART.

#### NOTES:

- 1. 500 PIECES PER REEL.
- 2. THE CATHODE IS ORIENTED TOWARDS THE TAPE SPROCKET HOLE.

\*UNLESS OTHERWISE SPECIFED TOLERANCES PER DECIMAL PRECISION ARE: X=±1 (±0.039), XX=±0.5 (±0.020), XXX=±0.25 (±0.010), XXXX=±0.127 (±0.005). LEAD SIZE=±0.05 (±0.002), LEAD LENGTH=±0.75 (±0.030). MN=+DECIMAL PRECISION MAX.=+0.001

PART NUMBER REV. SML-LXR44USBC-TR

> RIGHT ANGLE BOOMERANG SURFACE MOUNT LED, 470nm InGaN BLUE LED, WATER CLEAR LENS.

CONFIDENTIAL INFORMATION
THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE PROPERTY OF LUMEX INC. EXCEPT AS SPECIFICALLY AUTHORIZED IN WRITING BY LUMEX INC., THE HOLDER OF THIS DOCUMENT SHALL KEEP ALL INFORMATION CONTAINED HEREIN CONFIDENTIAL AND SHALL PROTECT SAME IN WHOLE OR IN PART FROM DISCLOSURE AND DISSEMINATION TO ALL THIRD PARTIES.

RELIABILITY NOTE OUR MANY YEARS OF EXPERIENCE DATA ACCUMULATION INDICATE THAT SOLDER HEAT IS A MAJOR CAUSE OF EARLY AND FUTURE FAILURE. PLEASE PAY ATTENTION TO YOUR SOLDERING PROCESS.



290 E. HELEN ROAD PALATINE, IL 60067-6976 PHONE: +1.847.359,2790 US WEB: www.lumex.com TW WEB: www.lumex.com.tw

DRAWN BY:

СТ

CHECKED BY:

APPROVED BY: DATE: PAGE:

1 OF 1 SCALE: N/A

2.5.03

# **Mouser Electronics**

**Authorized Distributor** 

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

Lumex:

SML-LXR44USBC-TR