

### Mixed Signal ISP Flash MCU Family

#### **Analog Peripherals**

- 10 or 12-Bit SAR ADC
  - 12-bit (C8051F040/1) or 10-bit (C8051F042/3/4/5/6/7) resolution
  - ± 1 LSB INL, guaranteed no missing codes
  - Programmable throughput up to 100 ksps
  - 13 External Inputs; single-ended or differential
  - SW programmable high voltage difference amplifier
  - Programmable amplifier gain: 16, 8, 4, 2, 1, 0.5
  - Data-dependent windowed interrupt generator
- Built-in temperature sensor

#### 8-bit SAR ADC (C8051F040/1/2/3 only)

- Programmable throughput up to 500 ksps
- 8 External Inputs, single-ended or differential
- Programmable amplifier gain: 4, 2, 1, 0.5

#### - Two 12-bit DACs (C8051F040/1/2/3 only)

 Can synchronize outputs to timers for jitter-free waveform generation

#### - Three Analog Comparators

- Programmable hysteresis/response time
- Voltage Reference
- Precision V<sub>DD</sub> Monitor/Brown-Out Detector On-Chip JTAG Debug & Boundary Scan
- On-chip debug circuitry facilitates full- speed, nonintrusive in-circuit/in-system debugging
- Provides breakpoints, single-stepping, watchpoints, stack monitor; inspect/modify memory and registers
- Superior performance to emulation systems using ICE-chips, target pods, and sockets
- IEEE1149.1 compliant boundary scan
- Complete development kit

#### High-Speed 8051 µC Core

- Pipelined instruction architecture; executes 70% of instruction set in 1 or 2 system clocks
- Up to 25 MIPS throughput with 25 MHz clock
- 20 vectored interrupt sources

#### Memory

- 4352 bytes internal data RAM (4 k + 256)
- 64 kB (C8051F040/1/2/3/4/5)
   or 32 kB (C8051F046/7) Flash; in-system programmable in 512-byte sectors
- External 64 kB data memory interface (programmable multiplexed or non-multiplexed modes)

#### **Digital Peripherals**

- 8 byte-wide port I/O (C8051F040/2/4/6); 5 V tolerant
- 4 byte-wide port I/O (C8051F041/3/5/7); 5 V tolerant
- Bosch Controller Area Network (CAN 2.0B), hardware SMBus<sup>™</sup> (I<sup>2</sup>C<sup>™</sup> Compatible), SPI<sup>™</sup>, and two UART serial ports available concurrently
- Programmable 16-bit counter/timer array with 6 capture/compare modules
- 5 general purpose 16-bit counter/timers
- Dedicated watch-dog timer; bi-directional reset pin

#### Clock Sources


- Internal calibrated programmable oscillator: 3 to 24.5 MHz
- External oscillator: crystal, RC, C, or clock
- Real-time clock mode using Timer 2, 3, 4, or PCA

#### Supply Voltage: 2.7 to 3.6 V

- Multiple power saving sleep and shutdown modes

### 100-Pin and 64-Pin TQFP Packages Available

- Temperature Range: -40 to +85 °C





2

### **Table of Contents**

1.	System Overview	19
	1.1. CIP-51™ Microcontroller Core	25
	1.1.1. Fully 8051 Compatible	25
	1.1.2. Improved Throughput	25
	1.1.3. Additional Features	
	1.2. On-Chip Memory	27
	1.3. JTAG Debug and Boundary Scan	28
	1.4. Programmable Digital I/O and Crossbar	
	1.5. Programmable Counter Array	
	1.6. Controller Area Network	
	1.7. Serial Ports	
	1.8. 12/10-Bit Analog to Digital Converter	32
	1.9. 8-Bit Analog to Digital Converter (C8051F040/1/2/3 Only)	33
	1.10.Comparators and DACs	34
2.	Absolute Maximum Ratings	
	Global DC Electrical Characteristic	
4.	Pinout and Package Definitions	37
	12-Bit ADC (ADC0, C8051F040/1 Only)	
	5.1. Analog Multiplexer and PGA	
	5.1.1. Analog Input Configuration	
	5.2. High-Voltage Difference Amplifier	
	5.3. ADC Modes of Operation	
	5.3.1. Starting a Conversion	
	5.3.2. Tracking Modes	
	5.3.3. Settling Time Requirements	
	5.4. ADC0 Programmable Window Detector	
6.	10-Bit ADC (ADC0, C8051F042/3/4/5/6/7 Only)	
-	6.1. Analog Multiplexer and PGA	
	6.1.1. Analog Input Configuration	
	6.2. High-Voltage Difference Amplifier	
	6.3. ADC Modes of Operation	
	6.3.1. Starting a Conversion	
	6.3.2. Tracking Modes	
	6.3.3. Settling Time Requirements	
	6.4. ADC0 Programmable Window Detector	
7.	8-Bit ADC (ADC2, C8051F040/1/2/3 Only)	
	7.1. Analog Multiplexer and PGA	
	7.2. ADC2 Modes of Operation	
	7.2.1. Starting a Conversion	
	7.2.2. Tracking Modes	
	7.2.3. Settling Time Requirements	
	7.3. ADC2 Programmable Window Detector	
	7.3.1. Window Detector in Single-Ended Mode	
	<b>5</b>	



	7.3.2. Window Detector in Differential Mode	1	ი2
8.	DACs, 12-Bit Voltage Mode (C8051F040/1/2/3 Only)		
•	8.1. DAC Output Scheduling		
	8.1.1. Update Output On-Demand	1	06
	8.1.2. Update Output Based on Timer Overflow		
	8.2. DAC Output Scaling/Justification		
9.	Voltage Reference (C8051F040/2/4/6)		
	.Voltage Reference (C8051F041/3/5/7)		
	.Comparators		
•	11.1.Comparator Inputs		
12	CIP-51 Microcontroller		
-	12.1.Instruction Set		
	12.1.1.Instruction and CPU Timing		
	12.1.2.MOVX Instruction and Program Memory		
	12.2.Memory Organization		
	12.2.1.Program Memory		
	12.2.2.Data Memory		
	12.2.3.General Purpose Registers		
	12.2.4.Bit Addressable Locations		
	12.2.5.Stack		
	12.2.6.Special Function Registers		
	12.2.7.Register Descriptions		
	12.3.Interrupt Handler		
	12.3.1.MCU Interrupt Sources and Vectors		
	12.3.2.External Interrupts		
	12.3.3.Interrupt Priorities		
	12.3.4.Interrupt Latency		
	12.3.5.Interrupt Register Descriptions		
	12.4.Power Management Modes		
	12.4.1.ldle Mode		
	12.4.2.Stop Mode		
13	Reset Sources	1	65
	13.1.Power-On Reset	1	66
	13.2.Power-Fail Reset	1	66
	13.3.External Reset	1	66
	13.4.Missing Clock Detector Reset	1	67
	13.5.Comparator0 Reset		
	13.6.External CNVSTR0 Pin Reset	1	67
	13.7.Watchdog Timer Reset	1	67
	13.7.1.Enable/Reset WDT	1	68
	13.7.2.Disable WDT		
	13.7.3.Disable WDT Lockout	1	68
	13.7.4.Setting WDT Interval		
14	.Oscillators	1	73
	14.1.Programmable Internal Oscillator	1	73



14.2.External Oscillator Drive Circuit	175
14.3.System Clock Selection	175
14.4.External Crystal Example	
14.5.External RC Example	
14.6.External Capacitor Example	178
15. Flash Memory	
15.1.Programming The Flash Memory	
15.2.Non-volatile Data Storage	
15.3.Security Options	
15.3.1.Summary of Flash Security Options	
16. External Data Memory Interface and On-Chip XRAM	
16.1.Accessing XRAM	187
16.1.1.16-Bit MOVX Example	187
16.1.2.8-Bit MOVX Example	
16.2.Configuring the External Memory Interface	
16.3.Port Selection and Configuration	
16.4.Multiplexed and Non-multiplexed Selection	191
16.4.1.Multiplexed Configuration	
16.4.2.Non-multiplexed Configuration	
16.5.Memory Mode Selection	
16.5.1.Internal XRAM Only	
16.5.2.Split Mode without Bank Select	
16.5.3.Split Mode with Bank Select	
16.5.4.External Only	
16.6.Timing	
16.6.1.Non-multiplexed Mode	
16.6.2.Multiplexed Mode	
17. Port Input/Output	
17.1.Ports 0 through 3 and the Priority Crossbar Decoder	
17.1.1.Crossbar Pin Assignment and Allocation	
17.1.2.Configuring the Output Modes of the Port Pins	
17.1.3.Configuring Port Pins as Digital Inputs	
17.1.4.Weak Pullups	
17.1.5.Configuring Port 1, 2, and 3 Pins as Analog Inputs	
17.1.6.External Memory Interface Pin Assignments	
17.1.7.Crossbar Pin Assignment Example	
17.2.Ports 4 through 7	
17.2.1.Configuring Ports Which are Not Pinned Out	
17.2.2.Configuring the Output Modes of the Port Pins	
17.2.3.Configuring Port Pins as Digital Inputs	
17.2.4.Weak Pullups	
17.2.5.External Memory Interface	
18. Controller Area Network (CAN0)	
18.1.Bosch CAN Controller Operation	228
18.1.1.CAN Controller Timing	



	18.1.2.Example Timing Calculation for 1 Mbit/Sec Communication	
	18.2.CAN Registers	
	18.2.1.CAN Controller Protocol Registers	
	18.2.2.Message Object Interface Registers	
	18.2.3.Message Handler Registers	
	18.2.4.CIP-51 MCU Special Function Registers	
	18.2.5.Using CAN0ADR, CAN0DATH, and CANDATL to Access CAN Regis	iters .
	18.2.6.CAN0ADR Autoincrement Feature	232
19	.System Management BUS/I <sup>2</sup> C BUS (SMBUS0)	239
	19.1.Supporting Documents	240
	19.2.SMBus Protocol	241
	19.2.1.Arbitration	241
	19.2.2.Clock Low Extension	242
	19.2.3.SCL Low Timeout	242
	19.2.4.SCL High (SMBus Free) Timeout	242
	19.3.SMBus Transfer Modes	242
	19.3.1.Master Transmitter Mode	242
	19.3.2.Master Receiver Mode	243
	19.3.3.Slave Transmitter Mode	243
	19.3.4.Slave Receiver Mode	244
	19.4.SMBus Special Function Registers	245
	19.4.1.Control Register	
	19.4.2.Clock Rate Register	248
	19.4.3.Data Register	
	19.4.4.Address Register	
	19.4.5.Status Register	
20	.Enhanced Serial Peripheral Interface (SPI0)	255
	20.1.Signal Descriptions	
	20.1.1.Master Out, Slave In (MOSI)	256
	20.1.2.Master In, Slave Out (MISO)	
	20.1.3.Serial Clock (SCK)	
	20.1.4.Slave Select (NSS)	
	20.2.SPI0 Master Mode Operation	
	20.3.SPI0 Slave Mode Operation	
	20.4.SPI0 Interrupt Sources	
	20.5.Serial Clock Timing	
	20.6.SPI Special Function Registers	
21	.UART0	265
	21.1.UART0 Operational Modes	
	21.1.1.Mode 0: Synchronous Mode	
	21.1.2.Mode 1: 8-Bit UART, Variable Baud Rate	
	21.1.3.Mode 2: 9-Bit UART, Fixed Baud Rate	
	21.1.4.Mode 3: 9-Bit UART, Variable Baud Rate	
	21.2.Multiprocessor Communications	270



21.3.Configuration of a Masked Address	271
21.4.Broadcast Addressing	
21.5.Frame and Transmission Error Detection	
22. UART1	
22.1.Enhanced Baud Rate Generation	278
22.2.Operational Modes	279
22.2.1.8-Bit UART	
22.2.2.9-Bit UART	280
22.3.Multiprocessor Communications	281
23. Timers	
23.1.Timer 0 and Timer 1	
23.1.1.Mode 0: 13-bit Counter/Timer	287
23.1.2.Mode 1: 16-bit Counter/Timer	
23.1.3.Mode 2: 8-bit Counter/Timer with Auto-Reload	289
23.1.4.Mode 3: Two 8-bit Counter/Timers (Timer 0 Only)	
23.2.Timer 2, Timer 3, and Timer 4	
23.2.1.Configuring Timer 2, 3, and 4 to Count Down	
23.2.2.Capture Mode	
23.2.3.Auto-Reload Mode	
23.2.4.Toggle Output Mode	
24. Programmable Counter Array	
24.1.PCA Counter/Timer	
24.2.Capture/Compare Modules	
24.2.1.Edge-triggered Capture Mode	
24.2.2.Software Timer (Compare) Mode	
24.2.3.High-Speed Output Mode	
24.2.4.Frequency Output Mode	
24.2.5.8-Bit Pulse Width Modulator Mode	
24.2.6.16-Bit Pulse Width Modulator Mode	311
24.3.Register Descriptions for PCA0	312
25. JTAG (IEEE 1149.1)	
25.1.Boundary Scan	318
25.1.1.EXTEST Instruction	319
25.1.2.SAMPLE Instruction	319
25.1.3.BYPASS Instruction	
25.1.4.IDCODE Instruction	319
25.2.Flash Programming Commands	
25.3.Debug Support	
Document Change List	
Contact Information	326



**Notes:** 



8

## **List of Figures**

1	System Overview	
••	Figure 1.1. C8051F040/2 Block Diagram	21
	Figure 1.2. C8051F041/3 Block Diagram	
	Figure 1.3. C8051F044/6 Block Diagram	
	Figure 1.4. C8051F045/7 Block Diagram	
	Figure 1.5. Comparison of Peak MCU Execution Speeds	
	Figure 1.6. On-Board Clock and Reset	
	Figure 1.7. On-Chip Memory Map	
	Figure 1.8. Development/In-System Debug Diagram	
	Figure 1.9. Digital Crossbar Diagram	
	Figure 1.10. PCA Block Diagram	
	Figure 1.11. CAN Controller Diagram	
	Figure 1.12. 10/12-Bit ADC Block Diagram	
	Figure 1.13. 8-Bit ADC Diagram	
	Figure 1.14. Comparator and DAC Diagram	
2.	Absolute Maximum Ratings	
3.	Global DC Electrical Characteristic	
4.	Pinout and Package Definitions	
	Figure 4.1. TQFP-100 Pinout Diagram	. 43
	Figure 4.2. TQFP-100 Package Drawing	. 44
	Figure 4.3. TQFP-64 Pinout Diagram	
	Figure 4.4. TQFP-64 Package Drawing	. 46
5.	12-Bit ADC (ADC0, C8051F040/1 Only)	
	Figure 5.1. 12-Bit ADC0 Functional Block Diagram	. 47
	Figure 5.2. Analog Input Diagram	
	Figure 5.3. High Voltage Difference Amplifier Functional Diagram	. 52
	Figure 5.4. 12-Bit ADC Track and Conversion Example Timing	. 55
	Figure 5.5. ADC0 Equivalent Input Circuits	. 56
	Figure 5.6. Temperature Sensor Transfer Function	. 57
	Figure 5.7. ADC0 Data Word Example	. 61
	Figure 5.8. 12-Bit ADC0 Window Interrupt Example:	
	Right Justified Single-Ended Data	. 63
	Figure 5.9. 12-Bit ADC0 Window Interrupt Example:	
	Right Justified Differential Data	. 64
	Figure 5.10. 12-Bit ADC0 Window Interrupt Example:	
	Left Justified Single-Ended Data	
	Figure 5.11. 12-Bit ADC0 Window Interrupt Example: Left Justified Differential Da 66	ta.
6.	10-Bit ADC (ADC0, C8051F042/3/4/5/6/7 Only)	
	Figure 6.1. 10-Bit ADC0 Functional Block Diagram	. 69
	Figure 6.2. Analog Input Diagram	
	Figure 6.3. High Voltage Difference Amplifier Functional Diagram	
	Figure 6.4. 10-Bit ADC Track and Conversion Example Timing	
	<u> </u>	-



	Figure 6.5. ADC0 Equivalent Input Circuits	 78
	Figure 6.6. Temperature Sensor Transfer Function	
	Figure 6.7. ADC0 Data Word Example	
	Figure 6.8. 10-Bit ADC0 Window Interrupt Example:	
	Right Justified Single-Ended Data	85
	Figure 6.9. 10-Bit ADC0 Window Interrupt Example:	
	Right Justified Differential Data	86
	Figure 6.10. 10-Bit ADC0 Window Interrupt Example:	
	Left Justified Single-Ended Data	87
	Figure 6.11. 10-Bit ADC0 Window Interrupt Example: Left Justified Differential D	
	88	
7.	8-Bit ADC (ADC2, C8051F040/1/2/3 Only)	
	Figure 7.1. ADC2 Functional Block Diagram	91
	Figure 7.2. ADC2 Track and Conversion Example Timing	
	Figure 7.3. ADC2 Equivalent Input Circuit	
	Figure 7.4. ADC2 Data Word Example	
	Figure 7.5. ADC Window Compare Examples, Single-Ended Mode	. 101
	Figure 7.6. ADC Window Compare Examples, Differential Mode	. 102
8.	DACs, 12-Bit Voltage Mode (C8051F040/1/2/3 Only)	
	Figure 8.1. DAC Functional Block Diagram	. 105
9.	Voltage Reference (C8051F040/2/4/6)	
	Figure 9.1. Voltage Reference Functional Block Diagram	. 113
10	. Voltage Reference (C8051F041/3/5/7)	
	Figure 10.1. Voltage Reference Functional Block Diagram	. 117
11	. Comparators	
	Figure 11.1. Comparator Functional Block Diagram	. 121
	Figure 11.2. Comparator Hysteresis Plot	. 122
12	. CIP-51 Microcontroller	
	Figure 12.1. CIP-51 Block Diagram	
	Figure 12.2. Memory Map	
	Figure 12.3. SFR Page Stack	
	Figure 12.4. SFR Page Stack While Using SFR Page 0x0F To Access Port 5	
	Figure 12.5. SFR Page Stack After ADC2 Window Comparator Interrupt Occurs	
	Figure 12.6. SFR Page Stack Upon PCA Interrupt Occurring During an ADC2 IS	R
	139	
	Figure 12.7. SFR Page Stack Upon Return From PCA Interrupt	
	Figure 12.8. SFR Page Stack Upon Return From ADC2 Window Interrupt	. 141
13	Reset Sources	405
	Figure 13.1. Reset Sources	
	Figure 13.2. Reset Timing	. 166
14	Oscillators	470
	Figure 14.1. Oscillator Diagram	. 1/3
4-	Figure 14.2. 32.768 kHz External Crystal Example	. 1//
15	Flash Memory	404
	Figure 15.1. Flash Program Memory Map and Security Bytes	. 181



16. External Data Memory Interface and On-Chip XRAM	
Figure 16.1. Multiplexed Configuration Example	191
Figure 16.2. Non-multiplexed Configuration Example	192
Figure 16.3. EMIF Operating Modes	193
Figure 16.4. Non-multiplexed 16-bit MOVX Timing	196
Figure 16.5. Non-multiplexed 8-bit MOVX without Bank Select Timing.	197
Figure 16.6. Non-multiplexed 8-bit MOVX with Bank Select Timing	198
Figure 16.7. Multiplexed 16-bit MOVX Timing	199
Figure 16.8. Multiplexed 8-bit MOVX without Bank Select Timing	200
Figure 16.9. Multiplexed 8-bit MOVX with Bank Select Timing	201
17. Port Input/Output	
Figure 17.1. Port I/O Cell Block Diagram	203
Figure 17.2. Port I/O Functional Block Diagram	204
Figure 17.3. Priority Crossbar Decode Table	
Figure 17.4. Priority Crossbar Decode Table	
Figure 17.5. Priority Crossbar Decode Table	
Figure 17.6. Crossbar Example:	211
18. Controller Area Network (CAN0)	
Figure 18.1. Typical CAN Bus Configuration	227
Figure 18.2. CAN Controller Diagram	228
Figure 18.3. Four Segments of a CAN Bit Time	229
Figure 18.4. CAN0DATH: CAN Data Access Register High Byte	234
19. System Management BUS/I <sup>2</sup> C BUS (SMBUS0)	
Figure 19.1. SMBus0 Block Diagram	239
Figure 19.2. Typical SMBus Configuration	240
Figure 19.3. SMBus Transaction	
Figure 19.4. Typical Master Transmitter Sequence	
Figure 19.5. Typical Master Receiver Sequence	243
Figure 19.6. Typical Slave Transmitter Sequence	
Figure 19.7. Typical Slave Receiver Sequence	244
20. Enhanced Serial Peripheral Interface (SPI0)	
Figure 20.1. SPI Block Diagram	
Figure 20.2. Multiple-Master Mode Connection Diagram	
Figure 20.3. 3-Wire Single Master and Slave Mode Connection Diagra	
Figure 20.4. 4-Wire Single Master and Slave Mode Connection Diagra	
Figure 20.5. Data/Clock Timing Diagram	260
21. UART0	
Figure 21.1. UART0 Block Diagram	
Figure 21.2. UART0 Mode 0 Timing Diagram	
Figure 21.3. UART0 Mode 0 Interconnect	
Figure 21.4. UART0 Mode 1 Timing Diagram	
Figure 21.5. UART0 Modes 2 and 3 Timing Diagram	
Figure 21.6. UART0 Modes 1, 2, and 3 Interconnect Diagram	
Figure 21.7. UART Multi-Processor Mode Interconnect Diagram	272



22.UART1Figure 22.1. UART1 Block Diagram277Figure 22.2. UART1 Baud Rate Logic278Figure 22.3. UART Interconnect Diagram279
Figure 22.2. UART1 Baud Rate Logic278
rigure 22.5. OART interconnect Diagram
Figure 22.4. 8-Bit UART Timing Diagram279
Figure 22.5. 9-Bit UART Timing Diagram
Figure 22.6. UART Multi-Processor Mode Interconnect Diagram
23. Timers
Figure 23.1. T0 Mode 0 Block Diagram288
Figure 23.2. T0 Mode 2 Block Diagram289
Figure 23.3. T0 Mode 3 Block Diagram
Figure 23.4. Tn Capture Mode Block Diagram
Figure 23.5. Tn Auto-reload Mode and Toggle Mode Block Diagram
24. Programmable Counter Array
Figure 24.1. PCA Block Diagram 303
Figure 24.2. PCA Counter/Timer Block Diagram
Figure 24.3. PCA Interrupt Block Diagram
Figure 24.4. PCA Capture Mode Diagram
Figure 24.5. PCA Software Timer Mode Diagram
Figure 24.6. PCA High-Speed Output Mode Diagram
Figure 24.7. PCA Frequency Output Mode
Figure 24.8. PCA 8-Bit PWM Mode Diagram
Figure 24.9. PCA 16-Bit PWM Mode 311
25. JTAG (IEEE 1149.1)



### **List of Tables** 1. System Overview 2. Absolute Maximum Ratings 3. Global DC Electrical Characteristic 4. Pinout and Package Definitions 5. 12-Bit ADC (ADC0, C8051F040/1 Only) Table 5.1. AMUX Selection Chart (AMX0AD3-0 and AMX0CF3-0 bits) ...... 50 Table 5.2. 12-Bit ADC0 Electrical Characteristics .......67 6. 10-Bit ADC (ADC0, C8051F042/3/4/5/6/7 Only) 7. 8-Bit ADC (ADC2, C8051F040/1/2/3 Only) 8. DACs, 12-Bit Voltage Mode (C8051F040/1/2/3 Only) 9. Voltage Reference (C8051F040/2/4/6) 10. Voltage Reference (C8051F041/3/5/7) 11. Comparators 12. CIP-51 Microcontroller 13. Reset Sources 14. Oscillators 15. Flash Memory 16. External Data Memory Interface and On-Chip XRAM 17. Port Input/Output



18. Controller Area Network (CAN0)	
Table 18.1. Background System Information	29
Table 18.2. CAN Register Index and Reset Values	33
19. System Management BUS/I <sup>2</sup> C BUS (SMBUS0)	
Table 19.1. SMB0STA Status Codes and States	52
20. Enhanced Serial Peripheral Interface (SPI0)	
21.UART0	
Table 21.1. UART0 Modes 26	66
Table 21.2. Oscillator Frequencies for Standard Baud Rates	73
22. UART1	
Table 22.1. Timer Settings for Standard Baud Rates Using the Internal 24.5 MHz O	s-
cillator28	
Table 22.2. Timer Settings for Standard Baud Rates Using an External 25.0 MHz O	IS-
cillator28	84
Table 22.3. Timer Settings for Standard Baud Rates Using an External 22.1184 MH	Ιz
Oscillator28	85
Table 22.4. Timer Settings for Standard Baud Rates Using an External 18.432 MHz	Z
Oscillator28	
Table 22.5. Timer Settings for Standard Baud Rates Using an External 11.0592 MH	
Oscillator28	
Table 22.6. Timer Settings for Standard Baud Rates Using an External 3.6864 MHz	
Oscillator28	36
23. Timers	
24. Programmable Counter Array	
Table 24.1. PCA Timebase Input Options	
Table 24.2. PCA0CPM Register Settings for PCA Capture/Compare Modules 30	ე5
25. JTAG (IEEE 1149.1)	
Table 25.1. Boundary Data Register Bit Definitions	18



### **List of Registers** SFR Definition 5.4. HVA0CN: High Voltage Difference Amplifier Control . . . . . . . . . . . 53 SFR Definition 5.12. ADC0LTL: ADC0 Less-Than Data Low Byte . . . . . . . . . . . . . . . . . 63 SFR Definition 6.5. ADC0CF: ADC0 Configuration ......80 SFR Definition 6.8. ADC0L: ADC0 Data Word LSB ......82



SFR Definition 12.3. SFR Next Register: SFRNEXT	143
SFR Definition 12.4. SFR Last Register: SFRLAST	143
SFR Definition 12.5. SP: Stack Pointer	
SFR Definition 12.6. DPL: Data Pointer Low Byte	
SFR Definition 12.7. DPH: Data Pointer High Byte	
SFR Definition 12.8. PSW: Program Status Word	
SFR Definition 12.9. ACC: Accumulator	
SFR Definition 12.10. B: B Register	
SFR Definition 12.11. IE: Interrupt Enable	
SFR Definition 12.12. IP: Interrupt Priority	158
SFR Definition 12.13. EIE1: Extended Interrupt Enable 1	
SFR Definition 12.14. EIE2: Extended Interrupt Enable 2	
SFR Definition 12.15. EIP1: Extended Interrupt Priority 1	
SFR Definition 12.16. EIP2: Extended Interrupt Priority 2	162
SFR Definition 12.18. PCON: Power Control	
SFR Definition 13.1. WDTCN: Watchdog Timer Control	
SFR Definition 13.2. RSTSRC: Reset Source	
SFR Definition 14.1. OSCICL: Internal Oscillator Calibration	174
SFR Definition 14.2. OSCICN: Internal Oscillator Control	174
SFR Definition 14.3. CLKSEL: Oscillator Clock Selection	175
SFR Definition 14.4. OSCXCN: External Oscillator Control	176
SFR Definition 15.1. FLACL: Flash Access Limit	
SFR Definition 15.2. FLSCL: Flash Memory Control	184
SFR Definition 15.3. PSCTL: Program Store Read/Write Control	
SFR Definition 16.1. EMIOCN: External Memory Interface Control	
SFR Definition 16.2. EMIOCF: External Memory Configuration	190
SFR Definition 16.3. EMIOTC: External Memory Timing Control	
SFR Definition 17.1. XBR0: Port I/O Crossbar Register 0	
SFR Definition 17.2. XBR1: Port I/O Crossbar Register 1	
SFR Definition 17.3. XBR2: Port I/O Crossbar Register 2	
SFR Definition 17.4. XBR3: Port I/O Crossbar Register 3	215
SFR Definition 17.5. P0: Port0 Data	
SFR Definition 17.6. P0MDOUT: Port0 Output Mode	216
SFR Definition 17.7. P1: Port1 Data	
SFR Definition 17.8. P1MDIN: Port1 Input Mode	217
SFR Definition 17.9. P1MDOUT: Port1 Output Mode	
SFR Definition 17.10. P2: Port2 Data	
SFR Definition 17.11. P2MDIN: Port2 Input Mode	218
SFR Definition 17.12. P2MDOUT: Port2 Output Mode	
SFR Definition 17.13. P3: Port3 Data	
SFR Definition 17.14. P3MDIN: Port3 Input Mode	220
SFR Definition 17.15. P3MDOUT: Port3 Output Mode	
SFR Definition 17.16. P4: Port4 Data	
SFR Definition 17.17. P4MDOUT: Port4 Output Mode	
SFR Definition 17.18. P5: Port5 Data	



SFR Definition 17.19. P5MDOUT: Port5 Output Mode	223
SFR Definition 17.20. P6: Port6 Data	
SFR Definition 17.21. P6MDOUT: Port6 Output Mode	224
SFR Definition 17.22. P7: Port7 Data	
SFR Definition 17.23. P7MDOUT: Port7 Output Mode	
SFR Definition 18.1. CANODATL: CAN Data Access Register Low Byte	235
SFR Definition 18.2. CANOADR: CAN Address Index	235
SFR Definition 18.3. CANOCN: CAN Control	
SFR Definition 18.4. CAN0TST: CAN Test	
SFR Definition 18.5. CANOSTA: CAN Status	
SFR Definition 19.1. SMB0CN: SMBus0 Control	
SFR Definition 19.2. SMB0CR: SMBus0 Clock Rate	
SFR Definition 19.3. SMB0DAT: SMBus0 Data	
SFR Definition 19.4. SMB0ADR: SMBus0 Address	
SFR Definition 19.5. SMB0STA: SMBus0 Status	
SFR Definition 20.1. SPI0CFG: SPI0 Configuration	
SFR Definition 20.2. SPI0CN: SPI0 Control	
SFR Definition 20.3. SPI0CKR: SPI0 Clock Rate	
SFR Definition 20.4. SPI0DAT: SPI0 Data	
SFR Definition 21.1. SCON0: UART0 Control	
SFR Definition 21.2. SSTA0: UART0 Status and Clock Selection	
SFR Definition 21.3. SBUF0: UART0 Data Buffer	
SFR Definition 21.4. SADDR0: UART0 Slave Address	
SFR Definition 21.5. SADEN0: UARTO Slave Address Enable	
SFR Definition 22.1. SCON1: Serial Port 1 Control	
SFR Definition 22.2. SBUF1: Serial (UART1) Port Data Buffer	283
SFR Definition 23.1. TCON: Timer Control	
SFR Definition 23.2. TMOD: Timer Mode	
SFR Definition 23.3. CKCON: Clock Control	
SFR Definition 23.4. TL0: Timer 0 Low Byte	
SFR Definition 23.5. TL1: Timer 1 Low Byte	
SFR Definition 23.6. TH0: Timer 0 High Byte	
SFR Definition 23.7. TH1: Timer 1 High Byte	
SFR Definition 23.8. TMRnCN: Timer n Control	
SFR Definition 23.9. TMRnCF: Timer n Configuration	
SFR Definition 23.10. RCAPnL: Timer n Capture Register Low Byte	
SFR Definition 23.11. RCAPnH: Timer n Capture Register High Byte	
SFR Definition 23.12. TMRnL: Timer n Low Byte	
SFR Definition 23.13. TMRnH Timer n High Byte	
SFR Definition 24.1. PCA0CN: PCA Control	
SFR Definition 24.2. PCA0MD: PCA0 Mode	
SFR Definition 24.3. PCA0CPMn: PCA0 Capture/Compare Mode	
SFR Definition 24.4. PCA0L: PCA0 Counter/Timer Low Byte	
SFR Definition 24.5. PCA0H: PCA0 Counter/Timer High Byte	
SFR Definition 24.6. PCA0CPLn: PCA0 Capture Module Low Byte	316



SFR Definition 24.7. PCA0CPHn: PCA0 Capture Module High Byte	316
JTAG Register Definition 25.1. IR: JTAG Instruction Register	317
JTAG Register Definition 25.2. DEVICEID: JTAG Device ID Register	320
JTAG Register Definition 25.3. FLASHCON: JTAG Flash Control Register	322
JTAG Register Definition 25.4. FLASHDAT: JTAG Flash Data	323
JTAG Register Definition 25.5. FLASHADR: JTAG Flash Address	323



### 1. System Overview

The C8051F04x family of devices are fully integrated mixed-signal System-on-a-Chip MCUs with 64 digital I/O pins (C8051F040/2/4/6) or 32 digital I/O pins (C8051F041/3/5/7), and an integrated CAN 2.0B controller. Highlighted features are listed below; refer to Table 1.1 for specific product feature selection.

- High-Speed pipelined 8051-compatible CIP-51 microcontroller core (up to 25 MIPS)
- Controller Area Network (CAN 2.0B) Controller with 32 message objects, each with its own indentifier mask.
- In-system, full-speed, non-intrusive debug interface (on-chip)
- True 12-bit (C8051F040/1) or 10-bit (C8051F042/3/4/5/6/7) 100 ksps 8-channel ADC with PGA and analog multiplexer
- High Voltage Difference Amplifier input to the 12/10-bit ADC (60 V Peak-to-Peak) with programmable gain.
- True 8-bit 500 ksps 8-channel ADC with PGA and analog multiplexer (C8051F040/1/2/3)
- Two 12-bit DACs with programmable update scheduling (C8051F040/1/2/3)
- 64 kB (C8051F040/1/2/3/4/5) or 32 kB (C8051F046/7) of in-system programmable Flash memory
- 4352 (4096 + 256) bytes of on-chip RAM
- External Data Memory Interface with 64 kB address space
- SPI, SMBus/I<sup>2</sup>C, and (2) UART serial interfaces implemented in hardware
- Five general purpose 16-bit Timers
- Programmable Counter/Timer Array with six capture/compare modules
- On-chip Watchdog Timer, V<sub>DD</sub> Monitor, and Temperature Sensor

With on-chip  $V_{DD}$  monitor, Watchdog Timer, and clock oscillator, the C8051F04x family of devices are truly stand-alone System-on-a-Chip solutions. All analog and digital peripherals are enabled/disabled and configured by user firmware. The Flash memory can be reprogrammed even in-circuit, providing non-volatile data storage, and also allowing field upgrades of the 8051 firmware.

On-board JTAG debug circuitry allows non-intrusive (uses no on-chip resources), full speed, in-circuit programming and debugging using the production MCU installed in the final application. This debug system supports inspection and modification of memory and registers, setting breakpoints, watchpoints, single stepping, Run, and Halt commands. All analog and digital peripherals are fully functional while debugging using JTAG.

Each MCU is specified for 2.7 V to 3.6 V operation over the industrial temperature range (–45 to +85 °C). The Port I/Os, /RST, and JTAG pins are tolerant for input signals up to 5 V. The C8051F040/2/4/6 are available in a 100-pin TQFP and the C8051F041/3/5/7 are available in a 64-pin TQFP.



**Table 1.1. Product Selection Guide** 

Ordering Part Number	MIPS (Peak)	Flash Memory	RAM	External Memory Interface	SMBus/I <sup>2</sup> C and SPI	CAN	UARTS	Timers (16-bit)	Programmable Counter Array	Digital Port I/O's	12-bit 100ksps ADC	10-bit 100ksps ADC	8-bit 500 ksps ADC Inputs	High Voltage Diff Amp	Voltage Reference	Temperature Sensor	DAC Resolution (bits)	DAC Outputs	Analog Comparators	Lead-free (RoHS Compliant)	Package
C8051F040	25	64 kB	4352	<b>V</b>	<b>V</b>	<b>V</b>	2	5	<b>√</b>	64	<b>V</b>	-	8	<b>V</b>	<b>V</b>	<b>V</b>	12	2	3	-	100TQFP
C8051F040-GQ	25	64 kB	4352	<b>V</b>	<b>V</b>	<b>V</b>	2	5	<b>√</b>	64	<b>V</b>	-	8	<b>V</b>	<b>V</b>	<b>V</b>	12	2	3	<b>V</b>	100TQFP
C8051F041	25	64 kB	4352	~	/	<b>√</b>	2	5	<b>V</b>	32	~	-	8	~	<b>V</b>	<b>√</b>	12	2	3	-	64TQFP
C8051F041-GQ	25	64 kB	4352	/	<b>V</b>	<b>√</b>	2	5	<b>√</b>	32	<b>V</b>	-	8	/	<b>√</b>	<b>V</b>	12	2	3	<b>√</b>	64TQFP
C8051F042	25	64 kB	4352	/	<b>V</b>	<b>√</b>	2	5	<b>√</b>	64	-	<b>V</b>	8	/	<b>√</b>	<b>V</b>	12	2	3	-	100TQFP
C8051F042-GQ	25	64 kB	4352	<b>V</b>	<b>V</b>	<b>V</b>	2	5	<b>√</b>	64	-	<b>√</b>	8	<b>V</b>	<b>V</b>	<b>√</b>	12	2	3	<b>√</b>	100TQFP
C8051F043	25	64 kB	4352	/	<b>V</b>	<b>√</b>	2	5	<b>√</b>	32	-	<b>√</b>	8	/	<b>√</b>	<b>V</b>	12	2	3	-	64TQFP
C8051F043-GQ	25	64 kB	4352	<b>✓</b>	<b>V</b>	<b>V</b>	2	5	<b>√</b>	32	-	<b>V</b>	8	<b>V</b>	<b>V</b>	<b>V</b>	12	2	3	<b>V</b>	64TQFP
C8051F044	25	64 kB	4352	<b>✓</b>	<b>V</b>	<b>√</b>	2	5	<b>√</b>	64	-	<b>V</b>		~	<b>V</b>	<b>√</b>			3	-	100TQFP
C8051F044-GQ	25	64 kB	4352	/	<b>V</b>	<b>V</b>	2	5	<b>√</b>	64	-	<b>V</b>		<b>V</b>	<b>V</b>	<b>V</b>			3	<b>V</b>	100TQFP
C8051F045	25	64 kB	4352	/	<b>V</b>	<b>V</b>	2	5	<b>√</b>	32	-	<b>V</b>		<b>V</b>	<b>V</b>	<b>V</b>			3	-	64TQFP
C8051F045-GQ	25	64 kB	4352	<b>✓</b>	<b>V</b>	<b>√</b>	2	5	<b>√</b>	32	-	<b>√</b>		/	<b>√</b>	/			3	<b>V</b>	64TQFP
C8051F046	25	32 kB	4352	<b>✓</b>	<b>√</b>	<b>√</b>	2	5	<b>√</b>	64	-	<b>√</b>		/	<b>√</b>	<b>√</b>			3	-	100TQFP
C8051F046-GQ	25	32 kB	4352	<b>V</b>	<b>V</b>	<b>V</b>	2	5	<b>√</b>	64	-	<b>√</b>		<b>V</b>	<b>V</b>	<b>V</b>			3	<b>V</b>	100TQFP
C8051F047	25	32 kB	4352	<b>√</b>	<b>√</b>	<b>√</b>	2	5	<b>✓</b>	32	-	<b>√</b>		/	<b>V</b>	/			3	-	64TQFP
C8051F047-GQ	25	32 kB	4352	/	/	/	2	5	<b>V</b>	32	-	<b>V</b>		/	<b>√</b>	/			3	<b>V</b>	64TQFP




Figure 1.1. C8051F040/2 Block Diagram






Figure 1.2. C8051F041/3 Block Diagram






Figure 1.3. C8051F044/6 Block Diagram






Figure 1.4. C8051F045/7 Block Diagram



### 1.1. CIP-51™ Microcontroller Core

### 1.1.1. Fully 8051 Compatible

The C8051F04x family of devices utilizes Silicon Labs' proprietary CIP-51 microcontroller core. The CIP-51 is fully compatible with the MCS-51™ instruction set; standard 803x/805x assemblers and compilers can be used to develop software. The core has all the peripherals included with a standard 8052, including five 16-bit counter/timers, two full-duplex UARTs, 256 bytes of internal RAM, 128 byte Special Function Register (SFR) address space, and up to 8 byte-wide I/O Ports.

#### 1.1.2. Improved Throughput

The CIP-51 employs a pipelined architecture that greatly increases its instruction throughput over the standard 8051 architecture. In a standard 8051, all instructions except for MUL and DIV take 12 or 24 system clock cycles to execute with a maximum system clock of 12-to-24 MHz. By contrast, the CIP-51 core executes 70% of its instructions in one or two system clock cycles, with only four instructions taking more than four system clock cycles.

The CIP-51 has a total of 109 instructions. The table below shows the total number of instructions that require each execution time.

Clocks to Execute	1	2	2/3	3	3/4	4	4/5	5	8
Number of Instructions	26	50	5	14	7	3	1	2	1

With the CIP-51's maximum system clock at 25 MHz, it has a peak throughput of 25 MIPS. Figure 1.5 shows a comparison of peak throughputs of various 8-bit microcontroller cores with their maximum system clocks.




Figure 1.5. Comparison of Peak MCU Execution Speeds



#### 1.1.3. Additional Features

The C8051F04x MCU family includes several key enhancements to the CIP-51 core and peripherals to improve overall performance and ease of use in end applications.

The extended interrupt handler provides 20 interrupt sources into the CIP-51 (as opposed to 7 for the standard 8051), allowing the numerous analog and digital peripherals to interrupt the controller. An interrupt driven system requires less intervention by the MCU, giving it more effective throughput. The extra interrupt sources are very useful when building multi-tasking, real-time systems.

There are up to seven reset sources for the MCU: an on-board  $V_{DD}$  monitor, a Watchdog Timer, a missing clock detector, a voltage level detection from Comparator0, a forced software reset, the CNVSTR0 input pin, and the /RST pin. The /RST pin is bi-directional, accommodating an external reset, or allowing the internally generated POR to be output on the /RST pin. Each reset source except for the  $V_{DD}$  monitor and Reset Input pin may be disabled by the user in software; the  $V_{DD}$  monitor is enabled/disabled via the MONEN pin. The Watchdog Timer may be permanently enabled in software after a power-on reset during MCU initialization.

The MCU has an internal, stand alone clock generator which is used by default as the system clock after any reset. If desired, the clock source may be switched on the fly to the external oscillator, which can use a crystal, ceramic resonator, capacitor, RC, or external clock source to generate the system clock. This can be extremely useful in low power applications, allowing the MCU to run from a slow (power saving) external crystal source, while periodically switching to the fast (up to 25 MHz) internal oscillator as needed.




Figure 1.6. On-Board Clock and Reset



### 1.2. On-Chip Memory

The CIP-51 has a standard 8051 program and data address configuration. It includes 256 bytes of data RAM, with the upper 128 bytes dual-mapped. Indirect addressing accesses the upper 128 bytes of general purpose RAM, and direct addressing accesses the 128 byte SFR address space. The CIP-51 SFR address space contains up to 256 SFR Pages. In this way, the CIP-51 MCU can accommodate the many SFRs required to control and configure the various peripherals featured on the device. The lower 128 bytes of RAM are accessible via direct and indirect addressing. The first 32 bytes are addressable as four banks of general purpose registers, and the next 16 bytes can be byte addressable or bit addressable.

The CIP-51 in the C8051F04x MCUs additionally has an on-chip 4 kB RAM block and an external memory interface (EMIF) for accessing off-chip data memory or memory-mapped peripherals. The on-chip 4 byte block can be addressed over the entire 64 kB external data memory address range (overlapping 4 kB boundaries). External data memory address space can be mapped to on-chip memory only, off-chip memory only, or a combination of the two (addresses up to 4 kB directed to on-chip, above 4 kB directed to EMIF). The EMIF is also configurable for multiplexed or non-multiplexed address/data lines.

The MCU's program memory consists of 64 kB (C8051F040/1/2/3/4/5) or 32 kB (C8051F046/7) of Flash. This memory may be reprogrammed in-system in 512 byte sectors, and requires no special off-chip programming voltage. The 512 bytes from addresses 0xFE00 to 0xFFFF are reserved for the 64 kB devices. There is also a single 128 byte sector at address 0x10000 to 0x1007F, which may be useful as a small table for software constants. See Figure 1.7 for the MCU system memory map.




Figure 1.7. On-Chip Memory Map



### 1.3. JTAG Debug and Boundary Scan

The C8051F04x family has on-chip JTAG boundary scan and debug circuitry that provides *non-intrusive*, *full speed*, *in-circuit debugging using the production part installed in the end application*, via the four-pin JTAG interface. The JTAG port is fully compliant to IEEE 1149.1, providing full boundary scan for test and manufacturing purposes.

Silicon Labs' debugging system supports inspection and modification of memory and registers, breakpoints, watchpoints, a stack monitor, and single stepping. No additional target RAM, program memory, timers, or communications channels are required. All the digital and analog peripherals are functional and work correctly while debugging. All the peripherals (except for the ADC and SMBus) are stalled when the MCU is halted, during single stepping, or at a breakpoint in order to keep them synchronized with instruction execution.

The C8051F040DK development kit provides all the hardware and software necessary to develop application code and perform in-circuit debugging with the C8051F04x MCUs. The development kit includes two target boards and a cable to facilitate evaluating a simple CAN communication network. The kit also includes software with a developer's studio and debugger, a target application board with the associated MCU installed, and the required cables and wall-mount power supply. The Serial Adapter takes its power from the application board; it requires roughly 20 mA at 2.7-3.6 V. For applications where there is not sufficient power available from the target system, the provided power supply can be connected directly to the Serial Adapter.

Silicon Labs' debug environment is a vastly superior configuration for developing and debugging embedded applications compared to standard MCU emulators, which use on-board "ICE Chips" and target cables and require the MCU in the application board to be socketed. Silicon Labs' debug environment both increases ease of use and preserves the performance of the precision, on-chip analog peripherals.




Figure 1.8. Development/In-System Debug Diagram

### 1.4. Programmable Digital I/O and Crossbar

The standard 8051 Ports (0, 1, 2, and 3) are available on the MCUs. The C8051F040/2/4/6 have 4 additional 8-bit ports (4, 5, 6, and 7) for a total of 64 general-purpose I/O Ports. The Ports behave like the standard 8051 with a few enhancements.

Each port pin can be configured as either a push-pull or open-drain output. Also, the "weak pullups" which are normally fixed on an 8051 can be globally disabled, providing additional power saving capabilities for low-power applications.

Perhaps the most unique enhancement is the Digital Crossbar. This is essentially a large digital switching network that allows mapping of internal digital system resources to Port I/O pins on P0, P1, P2, and P3 (See Figure 1.9). Unlike microcontrollers with standard multiplexed digital I/O ports, all combinations of functions are supported with all package options offered.

The on-chip counter/timers, serial buses, HW interrupts, ADC Start of Conversion input, comparator outputs, and other digital signals in the controller can be configured to appear on the Port I/O pins specified in the Crossbar Control registers. This allows the user to select the exact mix of general purpose Port I/O and digital resources needed for the particular application.




Figure 1.9. Digital Crossbar Diagram



### 1.5. Programmable Counter Array

The C8051F04x MCU family includes an on-board Programmable Counter/Timer Array (PCA) in addition to the five 16-bit general purpose counter/timers. The PCA consists of a dedicated 16-bit counter/timer time base with six programmable capture/compare modules. The timebase is clocked from one of six sources: the system clock divided by 12, the system clock divided by 4, Timer 0 overflow, an External Clock Input (ECI pin), the system clock, or the external oscillator source divided by 8.

Each capture/compare module can be configured to operate in one of six modes: Edge-Triggered Capture, Software Timer, High Speed Output, Frequency Output, 8-Bit Pulse Width Modulator, or 16-Bit Pulse Width Modulator. The PCA Capture/Compare Module I/O and External Clock Input are routed to the MCU Port I/O via the Digital Crossbar.




Figure 1.10. PCA Block Diagram



### 1.6. Controller Area Network

The C8051F04x family of devices feature a Controller Area Network (CAN) controller that implements serial communication using the CAN protocol. The CAN controller facilitates communication on a CAN network in accordance with the Bosch specification 2.0A (basic CAN) and 2.0B (full CAN). The CAN controller consists of a CAN Core, Message RAM (separate from the C8051 RAM), a message handler state machine, and control registers.

The CAN controller can operate at bit rates up to 1 Mbit/second. Silicon Labs CAN has 32 message objects each having its own identifier mask used for acceptance filtering of received messages. Incoming data, message objects and identifier masks are stored in the CAN message RAM. All protocol functions for transmission of data and acceptance filtering is performed by the CAN controller and not by the C8051 MCU. In this way, minimal CPU bandwidth is used for CAN communication. The C8051 configures the CAN controller, accesses received data, and passes data for transmission via Special Function Registers (SFR) in the C8051.




Figure 1.11. CAN Controller Diagram

#### 1.7. Serial Ports

The C8051F04x MCU Family includes two Enhanced Full-Duplex UARTs, an enhanced SPI Bus, and SMBus/I<sup>2</sup>C. Each of the serial buses is fully implemented in hardware and makes extensive use of the CIP-51's interrupts, thus requiring very little intervention by the CPU. The serial buses do not "share" resources such as timers, interrupts, or Port I/O, so any or all of the serial buses may be used together with any other.



### 1.8. 12/10-Bit Analog to Digital Converter

The C8051F040/1 devices have an on-chip 12-bit SAR ADC (ADC0) with a 9-channel input multiplexer and programmable gain amplifier. With a maximum throughput of 100 ksps, the ADC offers true 12-bit performance with an INL of ±1LSB. C8051F042/3/4/5/6/7 devices include a 10-bit SAR ADC with similar specifications and configuration options. The ADC0 voltage reference is selected between the DAC0 output and an external VREF pin. On C8051F040/2/4/6 devices, ADC0 has its own dedicated VREF0 input pin; on C8051F041/3/5/7 devices, the ADC0 uses the VREFA input pin and, on the C8051F041/3, shares it with the 8-bit ADC2. The on-chip 15 ppm/°C voltage reference may generate the voltage reference for the on-chip ADCs or other system components via the VREF output pin.

The ADC is under full control of the CIP-51 microcontroller via its associated Special Function Registers. One input channel is tied to an internal temperature sensor, while the other eight channels are available externally. Each pair of the eight external input channels can be configured as either two single-ended inputs or a single differential input. The system controller can also put the ADC into shutdown mode to save power.

A programmable gain amplifier follows the analog multiplexer. The gain can be set to 0.5, 1, 2, 4, 8, or 16 and is software programmable. The gain stage can be especially useful when different ADC input channels have widely varied input voltage signals, or when it is necessary to "zoom in" on a signal with a large dc offset (in differential mode, a DAC could be used to provide the dc offset).

Conversions can be started in four ways; a software command, an overflow of Timer 2, an overflow of Timer 3, or an external signal input. This flexibility allows the start of conversion to be triggered by software events, external HW signals, or a periodic timer overflow signal. Conversion completions are indicated by a status bit and an interrupt (if enabled). The resulting 10- or 12-bit data word is latched into two SFRs upon completion of a conversion. The data can be right or left justified in these registers under software control.

Window Compare registers for the ADC data can be configured to interrupt the controller when ADC data is within or outside of a specified range. The ADC can monitor a key voltage continuously in background mode, but not interrupt the controller unless the converted data is within the specified window.




Figure 1.12. 10/12-Bit ADC Block Diagram



### 1.9. 8-Bit Analog to Digital Converter (C8051F040/1/2/3 Only)

The C8051F040/1/2/3 devices have an on-board 8-bit SAR ADC (ADC2) with an 8-channel input multiplexer and programmable gain amplifier. This ADC features a 500 ksps maximum throughput and true 8-bit performance with an INL of ±1LSB. Eight input pins are available for measurement and can be programmed as single-ended or differential inputs. The ADC is under full control of the CIP-51 microcontroller via the Special Function Registers. The ADC2 voltage reference is selected between the analog power supply (AV+) and an external VREF pin. On C8051F040/2 devices, ADC2 has its own dedicated VREF2 input pin; on C8051F041/3 devices, ADC2 shares the VREFA input pin with the 12/10-bit ADC0. User software may put ADC2 into shutdown mode to save power.

A programmable gain amplifier follows the analog multiplexer. The gain stage can be especially useful when different ADC input channels have widely varied input voltage signals, or when it is necessary to "zoom in" on a signal with a large dc offset (in differential mode, a DAC could be used to provide the dc offset). The PGA gain can be set in software to 0.5, 1, 2, or 4.

A flexible conversion scheduling system allows ADC2 conversions to be initiated by software commands, timer overflows, or an external input signal. ADC2 conversions may also be synchronized with ADC0 software-commanded conversions. Conversion completions are indicated by a status bit and an interrupt (if enabled), and the resulting 8-bit data word is latched into an SFR upon completion.




Figure 1.13. 8-Bit ADC Diagram



### 1.10. Comparators and DACs

Each C8051F040/1/2/3 MCU has two 12-bit DACs, and all C8051F04x devices have three comparators on chip. The MCU data and control interface to each comparator and DAC is via the Special Function Registers. The MCU can place any DAC or comparator in low power shutdown mode.

The comparators have software programmable hysteresis and response time. Each comparator can generate an interrupt on its rising edge, falling edge, or both; these interrupts are capable of waking up the MCU from sleep mode. The comparators' output state can also be polled in software. The comparator outputs can be programmed to appear on the Port I/O pins via the Crossbar.

The DACs are voltage output mode and include a flexible output scheduling mechanism. This scheduling mechanism allows DAC output updates to be forced by a software write or a Timer 2, 3, or 4 overflow. The DAC voltage reference is supplied via the dedicated VREFD input pin on C8051F040/2 devices or via the internal voltage reference on C8051F041/3 devices. The DACs are especially useful as references for the comparators or offsets for the differential inputs of the ADC.




Figure 1.14. Comparator and DAC Diagram



### 2. Absolute Maximum Ratings

Table 2.1. Absolute Maximum Ratings\*

Parameter	Conditions	Min	Тур	Max	Units
Ambient temperature under bias		-55	—	125	°C
Storage Temperature		-65	_	150	°C
Voltage on any Pin (except V <sub>DD</sub> , Port I/O, and JTAG pins) with respect to DGND		-0.3	_	V <sub>DD</sub> + 0.3	V
Voltage on any Port I/O Pin, /RST, and JTAG pins with respect to DGND		-0.3	_	5.8	V
Voltage on V <sub>DD</sub> with respect to DGND		-0.3	_	4.2	V
Maximum Total current through V <sub>DD</sub> , AV+, DGND, and AGND		_	_	800	mA
Maximum output current sunk by any Port pin		_		100	mA
Maximum output current sunk by any other I/O pin		_	_	50	mA
Maximum output current sourced by any Port pin		_	_	100	mA
Maximum output current sourced by any other I/O pin		_	_	50	mA

\*Note: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device.

This is a stress rating only and functional operation of the devices at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

Due to special I/O design requirements of the High Voltage Difference Amplifier, undue electrical over-voltage stress (i.e., ESD) experienced by these pads may result in impedance degradation of these inputs (HVAIN+ and HVAIN-). For this reason, care should be taken to ensure proper handling and use as typically required to prevent ESD damage to electrostatically sensitive CMOS devices (e.g., static-free workstations, use of grounding straps, over-voltage protection in end-applications, etc.)



#### **Global DC Electrical Characteristic** 3.

**Table 3.1. Global DC Electrical Characteristics** 

-40 to +85 °C, 25 MHz System Clock unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Analog Supply Voltage <sup>1</sup>		2.7	3.0	3.6	V
Analog Supply Current	Internal REF, ADC, DAC, Comparators all active	_	1.7	_	mA
Analog Supply Current with analog sub-systems inactive	Internal REF, ADC, DAC, Comparators all disabled, oscillator disabled	_	0.2	_	μА
Analog-to-Digital Supply Delta ( V <sub>DD</sub> - AV+ )		_	_	0.5	V
Digital Supply Voltage		2.7	3.0	3.6	V
Digital Supply Current with CPU active (Normal Mode)	$V_{DD} = 2.7 \text{ V, Clock} = 25 \text{ MHz}$ $V_{DD} = 2.7 \text{ V, Clock} = 1 \text{ MHz}$ $V_{DD} = 2.7 \text{ V, Clock} = 32 \text{ kHz}$	_ _ _	10 0.5 20	_ _ _	mA mA μA
Digital Supply Current with CPU inactive (not accessing Flash) (Idle Mode)	V <sub>DD</sub> = 2.7 V, Clock = 25 MHz V <sub>DD</sub> = 2.7 V, Clock = 1 MHz V <sub>DD</sub> = 2.7 V, Clock = 32 kHz	_ _ _	5 0.2 10	_ _ _	mA mA μA
Digital Supply Current (shutdown) (Stop Mode)	Oscillator not running	_	0.2	_	μΑ
Digital Supply RAM Data Retention Voltage		_	1.5	_	V
Specified Operating Temperature Range		-40	_	+85	°C
SYSCLK (system clock frequency) <sup>2</sup>		0	_	25	MHz
Tsysl (SYSCLK low time)		18	_	_	ns
Tsysh (SYSCLK high time)		18	_	_	ns

#### Notes:

- Analog Supply AV+ must be greater than 1 V for V<sub>DD</sub> monitor to operate.
   SYSCLK must be at least 32 kHz to enable debugging.



# 4. Pinout and Package Definitions

**Table 4.1. Pin Definitions** 

Nama	Pin Nu	ımbers	Tuna	Description		
Name	F040/2/4/6	F041/3/5/7	Туре			
V <sub>DD</sub>	37, 64, 90	24, 41, 57		Digital Supply Voltage. Must be tied to +2.7 to +3.6 V.		
DGND	38, 63, 89	25, 40, 56		Digital Ground. Must be tied to Ground.		
AV+	8, 11, 14	3, 6		Analog Supply Voltage. Must be tied to +2.7 to +3.6 V.		
AGND	9, 10, 13	4, 5		Analog Ground. Must be tied to Ground.		
TMS	1	58	D In	JTAG Test Mode Select with internal pullup.		
TCK	2	59	D In	JTAG Test Clock with internal pullup.		
TDI	3	60	D In	JTAG Test Data Input with internal pullup. TDI is latched on the rising edge of TCK.		
TDO	4	61	D Out	JTAG Test Data Output with internal pullup. Data is shifted out on TDO on the falling edge of TCK. TDO output is a tri-state driver.		
/RST	5	62	D I/O	Device Reset. Open-drain output of internal $V_{DD}$ monitor. Is driven low when $V_{DD}$ is < 2.7 V and MONEN is high. An external source can initiate a system reset by driving this pin low.		
XTAL1	26	17	A In	Crystal Input. This pin is the return for the internal oscillator circuit for a crystal or ceramic resonator. For a precision internal clock, connect a crystal or ceramic resonator from XTAL1 to XTAL2. If overdriven by an external CMOS clock, this becomes the system clock.		
XTAL2	27	18	A Out	Crystal Output. This pin is the excitation driver for a crystal or ceramic resonator.		
MONEN	28	19	D In	$V_{DD}$ Monitor Enable. When tied high, this pin enables the internal $V_{DD}$ monitor, which forces a system reset when $V_{DD}$ is < 2.7 V. When tied low, the internal $V_{DD}$ monitor is disabled. In most applications, MONEN should be connected directly to $V_{DD}$ .		
VREF	12	7	A I/O	Bandgap Voltage Reference Output (all devices). DAC Voltage Reference Input (C8051F041/3 only).		
VREFA		8	A In	ADC0 (C8051F041/3/5/7) and ADC2 (C8051F041/3 only) Voltage Reference Input.		
VREF0	16		A In	ADC0 Voltage Reference Input.		
VREF2	17		A In	ADC2 Voltage Reference Input (C8051F040/2 only).		
VREF	15		A In	DAC Voltage Reference Input (C8051F040/2 only).		
AIN0.0	18	9	A In	ADC0 Input Channel 0 (See ADC0 Specification for complete description).		



**Table 4.1. Pin Definitions (Continued)** 

	Pin Nu	ımbers	_				
Name	F040/2/4/6	F041/3/5/7	Туре	Description			
AIN0.1	19	10	A In	ADC0 Input Channel 1 (See ADC0 Specification for complete description).			
AIN0.2	20	11	A In	ADC0 Input Channel 2 (See ADC0 Specification for complete description).			
AIN0.3	21	12	A In	ADC0 Input Channel 3 (See ADC0 Specification for complete description).			
HVCAP	22	13	A I/O	High Voltage Difference Amplifier Capacitor.			
HVREF	23	14	A In	High Voltage Difference Amplifier Bias Reference.			
HVAIN+	24	15	A In	High Voltage Difference Amplifier Positive Signal Input.			
HVAIN-	25	16	A In	High Voltage Difference Amplifier Negative Signal Input.			
CANTX	7	2	D Out	Controller Area Network Transmit Output.			
CANRX	6	1	D In	Controller Area Network Receive Input.			
DAC0	100	64	A Out	Digital to Analog Converter 0 Voltage Output. (See DAC Specification for complete description). (C8051F040/1/2/3 only)			
DAC1	99	63	A Out	Digital to Analog Converter 1 Voltage Output. (See DAC Specification for complete description). (C8051F040/1/2/3 only)			
P0.0	62	55	D I/O	Port 0.0. See Port Input/Output section for complete description.			
P0.1	61	54	D I/O	Port 0.1. See Port Input/Output section for complete description.			
P0.2	60	53	D I/O	Port 0.2. See Port Input/Output section for complete description.			
P0.3	59	52	D I/O	Port 0.3. See Port Input/Output section for complete description.			
P0.4	58	51	D I/O	Port 0.4. See Port Input/Output section for complete description.			
P0.5/ALE	57	50	D I/O	ALE Strobe for External Memory Address bus (multi- plexed mode) Port 0.5 See Port Input/Output section for complete description.			
P0.6/RD	56	49	D I/O	/RD Strobe for External Memory Address bus Port 0.6 See Port Input/Output section for complete description.			
P0.7/WR	55	48	D I/O	/WR Strobe for External Memory Address bus Port 0.7 See Port Input/Output section for complete description.			



**Table 4.1. Pin Definitions (Continued)** 

	Pin Nu	ımbers	_	Description			
Name	F040/2/4/6	F041/3/5/7	Type				
P1.0/AIN2.0/A8	36	29	A In D I/O	ADC1 Input Channel 0 (See ADC1 Specification for complete description). Bit 8 External Memory Address bus (Non-multiplexed mode) Port 1.0 See Port Input/Output section for complete description.			
P1.1/AIN2.1/A9	35	28	A In D I/O	Port 1.1. See Port Input/Output section for complete description.			
P1.2/AIN2.2/ A10	34	27	A In D I/O	Port 1.2. See Port Input/Output section for complete description.			
P1.3/AIN2.3/ A11	33	26	A In D I/O	Port 1.3. See Port Input/Output section for complete description.			
P1.4/AIN2.4/ A12	32	23	A In D I/O	Port 1.4. See Port Input/Output section for complete description.			
P1.5/AIN2.5/ A13	31	22	A In D I/O	Port 1.5. See Port Input/Output section for complete description.			
P1.6/AIN2.6/ A14	30	21	A In D I/O	Port 1.6. See Port Input/Output section for complete description.			
P1.7/AIN2.7/ A15	29	20	A In D I/O	Port 1.7. See Port Input/Output section for complete description.			
P2.0/A8m/A0	46	37	D I/O	Bit 8 External Memory Address bus (Multiplexed mode) Bit 0 External Memory Address bus (Non-multiplexed mode) Port 2.0 See Port Input/Output section for complete description.			
P2.1/A9m/A1	45	36	D I/O	Port 2.1. See Port Input/Output section for complete description.			
P2.2/A10m/A2	44	35	D I/O	Port 2.2. See Port Input/Output section for complete description.			
P2.3/A11m/A3	43	34	D I/O	Port 2.3. See Port Input/Output section for complete description.			
P2.4/A12m/A4	42	33	D I/O	Port 2.4. See Port Input/Output section for complete description.			
P2.5/A13m/A5	41	32	D I/O	Port 2.5. See Port Input/Output section for complete description.			
P2.6/A14m/A6	40	31	D I/O	Port 2.6. See Port Input/Output section for complete description.			
P2.7/A15m/A7	39	30	D I/O	Port 2.7. See Port Input/Output section for complete description.			



**Table 4.1. Pin Definitions (Continued)** 

Name	Pin Nu	ımbers	T	Description
Name	F040/2/4/6	F041/3/5/7	Туре	Description
P3.0/AD0/D0	54	47	A In D I/O	Bit 0 External Memory Address/Data bus (Multiplexed mode) Bit 0 External Memory Data bus (Non-multiplexed mode) Port 3.0 See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P3.1/AD1/D1	53	46	A In D I/O	Port 3.1. See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P3.2/AD2/D2	52	45	A In D I/O	Port 3.2. See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P3.3/AD3/D3	51	44	A In D I/O	Port 3.3. See Port Input/Output section for complete description.  ADC0 Input. (See ADC0 Specification for complete description.)
P3.4/AD4/D4	50	43	A In D I/O	Port 3.4. See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P3.5/AD5/D5	49	42	A In D I/O	Port 3.5. See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P3.6/AD6/D6	48	39	A In D I/O	Port 3.6. See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P3.7/AD7/D7	47	38	A In D I/O	Port 3.7. See Port Input/Output section for complete description. ADC0 Input. (See ADC0 Specification for complete description.)
P4.0	98		D I/O	Port 4.0. See Port Input/Output section for complete description.
P4.1	97		D I/O	Port 4.1. See Port Input/Output section for complete description.
P4.2	96		D I/O	Port 4.2. See Port Input/Output section for complete description.
P4.3	95		D I/O	Port 4.3. See Port Input/Output section for complete description.



**Table 4.1. Pin Definitions (Continued)** 

	<b>.</b>					
Name		ımbers	Туре	Description		
	F040/2/4/6	F041/3/5/7		P. C.		
P4.4	94		D I/O	Port 4.4. See Port Input/Output section for complete description.		
P4.5/ALE	93		D I/O	ALE Strobe for External Memory Address bus (multiplexed mode) Port 4.5 See Port Input/Output section for complete description.		
P4.6/RD	92		D I/O	/RD Strobe for External Memory Address bus Port 4.6 See Port Input/Output section for complete description.		
P4.7/WR	91		D I/O	/WR Strobe for External Memory Address bus Port 4.7 See Port Input/Output section for complete description.		
P5.0/A8	88		D I/O	Bit 8 External Memory Address bus (Non-multiplexed mode) Port 5.0 See Port Input/Output section for complete description.		
P5.1/A9	87		D I/O	Port 5.1. See Port Input/Output section for complete description.		
P5.2/A10	86		D I/O	Port 5.2. See Port Input/Output section for complete description.		
P5.3/A11	85		D I/O	Port 5.3. See Port Input/Output section for complete description.		
P5.4/A12	84		D I/O	Port 5.4. See Port Input/Output section for complete description.		
P5.5/A13	83		D I/O	Port 5.5. See Port Input/Output section for complete description.		
P5.6/A14	82		D I/O	Port 5.6. See Port Input/Output section for complete description.		
P5.7/A15	81		D I/O	Port 5.7. See Port Input/Output section for complete description.		
P6.0/A8m/A0	80		D I/O	Bit 8 External Memory Address bus (Multiplexed mode) Bit 0 External Memory Address bus (Non-multiplexed mode) mode) Port 6.0 See Port Input/Output section for complete description.		
P6.1/A9m/A1	79		D I/O	Port 6.1. See Port Input/Output section for complete description.		
P6.2/A10m/A2	78		D I/O	Port 6.2. See Port Input/Output section for complete description.		
P6.3/A11m/A3	77		D I/O	Port 6.3. See Port Input/Output section for complete description.		



**Table 4.1. Pin Definitions (Continued)** 

Name	Pin Numbers		Turna	Description		
Name	F040/2/4/6	F041/3/5/7	Туре	Description		
P6.4/A12m/A4	76		D I/O	Port 6.4. See Port Input/Output section for complete description.		
P6.5/A13m/A5	75		D I/O	Port 6.5. See Port Input/Output section for complete description.		
P6.6/A14m/A6	74		D I/O	Port 6.6. See Port Input/Output section for complete description.		
P6.7/A15m/A7	73		D I/O	Port 6.7. See Port Input/Output section for complete description.		
P7.0/AD0/D0	72		D I/O	Bit 0 External Memory Address/Data bus (Multiplexed mode) Bit 0 External Memory Data bus (Non-multiplexed mode) Port 7.0 See Port Input/Output section for complete description.		
P7.1/AD1/D1	71		D I/O	Port 7.1. See Port Input/Output section for complete description.		
P7.2/AD2/D2	70		D I/O	Port 7.2. See Port Input/Output section for complete description.		
P7.3/AD3/D3	69		D I/O	Port 7.3. See Port Input/Output section for complete description.		
P7.4/AD4/D4	68		D I/O	Port 7.4. See Port Input/Output section for complete description.		
P7.5/AD5/D5	67		D I/O	Port 7.5. See Port Input/Output section for complete description.		
P7.6/AD6/D6	66		D I/O	Port 7.6. See Port Input/Output section for complete description.		
P7.7/AD7/D7	65		D I/O	Port 7.7. See Port Input/Output section for complete description.		






Figure 4.1. TQFP-100 Pinout Diagram






Figure 4.2. TQFP-100 Package Drawing






Figure 4.3. TQFP-64 Pinout Diagram






Figure 4.4. TQFP-64 Package Drawing

## 5. 12-Bit ADC (ADC0, C8051F040/1 Only)

The ADC0 subsystem for the C8051F040/1 consists of a 9-channel, configurable analog multiplexer (AMUX0), a programmable gain amplifier (PGA0), and a 100 ksps, 12-bit successive-approximation-register ADC with integrated track-and-hold and Programmable Window Detector (see block diagram in Figure 5.1). The AMUX0, PGA0, Data Conversion Modes, and Window Detector are all configurable under software control via the Special Function Registers shown in Figure 5.1. The voltage reference used by ADC0 is selected as described in **Section "9. Voltage Reference (C8051F040/2/4/6)" on page 113** for C8051F040 devices, or **Section "10. Voltage Reference (C8051F041/3/5/7)" on page 117** for C8051F041 devices. The ADC0 subsystem (ADC0, track-and-hold and PGA0) is enabled only when the AD0EN bit in the ADC0 Control register (ADC0CN) is set to logic 1. The ADC0 subsystem is in low power shutdown when this bit is logic 0.




Figure 5.1. 12-Bit ADC0 Functional Block Diagram

## 5.1. Analog Multiplexer and PGA

The analog multiplexer can input analog signals to the ADC from four external analog input pins (AIN0.0 - AIN0.3), Port 3 port pins (optionally configured as analog input pins), High Voltage Difference Amplifier, or an internally connected on-chip temperature sensor (temperature transfer function is shown in Figure 5.6). AMUX input pairs can be programmed to operate in either differential or single-ended mode. This allows the user to select the best measurement technique for each input channel, and even accommodates mode changes "on-the-fly". The AMUX defaults to all single-ended inputs upon reset. There are three registers associated with the AMUX: the Channel Selection register AMX0SL (SFR Definition 5.2), the Configuration register AMX0CF (SFR Definition 5.1), and the Port Pin Selection register AMX0PRT (SFR Definition 5.3). Table 5.1 shows AMUX functionality by channel for each possible configuration. The PGA amplifies the AMUX output signal by an amount determined by the states of the AMP0GN2-0 bits in the ADC0 Configuration register, ADC0CF (SFR Definition 5.5). The PGA can be software-programmed for gains of 0.5, 2, 4, 8 or 16. Gain defaults to unity on reset.



#### 5.1.1. Analog Input Configuration

The analog multiplexer routes signals from external analog input pins, Port 3 I/O pins (See Section "17.1.5. Configuring Port 1, 2, and 3 Pins as Analog Inputs" on page 207), a High Voltage Difference Amplifier, and an on-chip temperature sensor as shown in Figure 5.2.




Figure 5.2. Analog Input Diagram

Analog signals may be input from four external analog input pins (AIN0.0 through AIN0.3) as differential or single-ended measurements. Additionally, Port 3 I/O Port Pins may be configured to input analog signals. Port 3 pins configured as analog inputs are selected using the Port Pin Selection register (AMX0PRT). Any number of Port 3 pins may be selected simultaneously as inputs to the AMUX. Even numbered Port 3 pins and odd numbered Port 3 pins are routed to separate AMUX inputs. (**Note:** Even port pins and odd port pins that are simultaneously selected will be shorted together as "wired-OR".) In this way, differential measurements may be made when using the Port 3 pins (voltage difference between selected even and odd Port 3 pins) as shown in Figure 5.2.

The High Voltage Difference Amplifier (HVDA) will accept analog input signals and reject up to 60 volts common-mode for differential measurement of up to the reference voltage to the ADC (0 to VREF volts). The output of the HVDA can be selected as an input to the ADC using the AMUX as any other channel is selected for input. (See Section "5.2. High-Voltage Difference Amplifier" on page 52).

## SFR Definition 5.1. AMX0CF: AMUX0 Configuration

R	R	R	R	R/W	R/W	R/W	R/W	Reset Value
-	-	-	-	PORT3IC	HVDA2C	AIN23IC	AIN01IC	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:

SFR Address: 0xBA SFR Page: 0

Bits7-4: UNUSED. Read = 0000b; Write = don't care

Bit3: PORT3IC: Port 3 even/odd Pin Input Pair Configuration Bit

0: Port 3 even and odd input channels are independent single-ended inputs1: Port 3 even and odd input channels are (respectively) +, - difference input pair

Bit2: HVDA2C: HVDA 2's Compliment Bit

0: HVDA output measured as an independent single-ended input

1: HVDA result for 2's compliment value

Bit1: AIN23IC: AIN0.2, AIN0.3 Input Pair Configuration Bit

0: AIN0.2 and AIN0.3 are independent single-ended inputs 1: AIN0.2, AIN0.3 are (respectively) +, - difference input pair

Bit0: AIN01IC: AIN0.0, AIN0.1 Input Pair Configuration Bit

0: AIN0.0 and AIN0.1 are independent single-ended inputs 1: AIN0.0, AIN0.1 are (respectively) +, - difference input pair

NOTE: The ADC0 Data Word is in 2's complement format for channels configured as difference.

#### SFR Definition 5.2. AMX0SL: AMUX0 Channel Select

R	R	R	R	R/W	R/W	R/W	R/W	Reset Value
-	-	-	-	AMX0AD3	AMX0AD2	AMX0AD1	AMX0AD0	00000000
 Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xBB SFR Page: 0

Bits7-4: UNUSED. Read = 0000b; Write = don't care

Bits3-0: AMX0AD3-0: AMX0 Address Bits

0000-1111b: ADC Inputs selected per Table 5.1.



Table 5.1. AMUX Selection Chart (AMX0AD3-0 and AMX0CF3-0 bits)

					Δ	MX0AD3-	0			
		0000	0001	0010	0011	0100	0101	0110	0111	1xxx
	0000	AIN0.0	AIN0.1	AIN0.2	AIN0.3	HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0001	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0010	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0011	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0100	AIN0.0	AIN0.1	AIN0.2	AIN0.3	+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
	0101	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
3-0	0110	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
Bits	0111	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
AMX0CF	1000	AIN0.0	AIN0.1	AIN0.2	AIN0.3	HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
AM	1001	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
	1010	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
	1011	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
	1100	AIN0.0	AIN0.1	AIN0.2	AIN0.3	+(HVDA) -(HVREF)		+P3EVEN -P3ODD)		TEMP SENSOR
	1101	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	+(HVDA) -(HVREF)		+P3EVEN -P3ODD		TEMP SENSOR
	1110	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		+P3EVEN -P3ODD		TEMP SENSOR
	1111	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		+P3EVEN -P3ODD		TEMP SENSOR

**Note:** "P3EVEN" denotes even numbered and "P3ODD" odd numbered Port 3 pins selected in the AMX0PRT register.



### SFR Definition 5.3. AMX0PRT: Port 3 Pin Selection

R/W R/W R/W R/W R/W R/W R/W R/W Reset Value PAIN7EN PAIN6EN PAIN5EN PAIN4EN PAIN3EN PAIN2EN PAIN1EN PAIN0EN 00000000 Bit6 Bit5 Bit3 Bit2 Bit1 Bit7 Bit4 Bit0

> SFR Address: 0xBD SFR Page: 0

Bit7: PAIN7EN: Pin 7 Analog Input Enable Bit

0: P3.7 is not selected as an analog input to the AMUX.1: P3.7 is selected as an analog input to the AMUX.

Bit6: PAIN6EN: Pin 6 Analog Input Enable Bit

0: P3.6 is not selected as an analog input to the AMUX.1: P3.6 is selected as an analog input to the AMUX.

Bit5: PAIN5EN: Pin 5 Analog Input Enable Bit

0: P3.5 is not selected as an analog input to the AMUX.1: P3.5 is selected as an analog input to the AMUX.

Bit4: PAIN4EN: Pin 4 Analog Input Enable Bit

0: P3.4 is not selected as an analog input to the AMUX.1: P3.4 is selected as an analog input to the AMUX.

Bit3: PAIN3EN: Pin 3 Analog Input Enable Bit

0: P3.3 is not selected as an analog input to the AMUX.

1: P3.3 is enabled as an analog input to the AMUX.

Bit2: PAIN2EN: Pin 2 Analog Input Enable Bit

0: P3.2 is not selected as an analog input to the AMUX.

1: P3.2 is enabled as an analog input to the AMUX.

Bit1: PAIN1EN: Pin 1 Analog Input Enable Bit

0: P3.1 is not selected as an analog input to the AMUX.

1: P3.1 is enabled as an analog input to the AMUX.

Bit0: PAIN0EN: Pin 0 Analog Input Enable Bit

0: P3.0 is not selected as an analog input to the AMUX.

1: P3.0 is enabled as an analog input to the AMUX.

**Note:**Any number of Port 3 pins may be selected simultaneously inputs to the AMUX. Odd numbered and even numbered pins that are selected simultaneously are shorted together as "wired-OR".



## 5.2. High-Voltage Difference Amplifier

The High Voltage Difference Amplifier (HVDA) can be used to measure high differential voltages up to 60 V peak-to-peak, reject high common-mode voltages up to ±60 V, and condition the signal voltage range to be suitable for input to ADC0. The input signal to the HVDA may be below AGND to –60 volts, and as high as +60 volts, making the device suitable for both single and dual supply applications. The HVDA provides a common-mode signal for the ADC via the High Voltage Reference Input (HVREF), allowing measurement of signals outside the specified ADC input range using on-chip circuitry. The HVDA has a gain of 0.05 V/V to 14 V/V. The first stage 20:1 difference amplifier has a gain of 0.05 V/V when the output amplifier is used as a unity gain buffer. When the output amplifier is set to a gain of 280 (selected using the HVGAIN bits in the High Voltage Control Register), an overall gain of 14 can be attained.

The HVDA uses four available external pins: +HVAIN, -HVAIN, HVCAP, and HVREF. HVAIN+ and HVAIN-serve as the differential inputs to the HVDA. HVREF should be used to provide a common mode reference for input to ADC0, and to prevent the output of the HVDA circuit from saturating. The output from the HVDA circuit as calculated by Equation 5.1 must remain within the "Output Voltage Range" specification listed in Table 5.3. The ideal value for HVREF in most applications is equal to 1/2 the supply voltage for the device. When the ADC is configured for differential measurement, the HVREF signal is applied to the AIN-input of the ADC, thereby removing HVREF from the measurement. HVCAP facilitates the use of a capacitor for noise filtering in conjunction with R7 (see Figure 5.3 for R7 and other approximate resistor values). Alternatively, the HVCAP could also be used to access amplification of the first stage of the HVDA at an external pin. (See Table 5.3 on page 68 for electrical specifications of the HVDA.)

$$V_{OUT} = [(HVAIN+) - (HVAIN-)] \cdot Gain + HVREF$$

**Note:** The output voltage of the HVDA is selected as an input to the AIN+ input of ADC0 via its analog multiplexer (AMUX0). HVDA output voltages outside the ADC's input range will result in saturation of the ADC input. Allow for adequate settle/tracking time for proper voltage measurements.

# HVAIN- $\frac{100 \text{k}\Omega}{100 \text{k}\Omega}$ $\frac{5 \text{k}\Omega}$ $\frac{5 \text{k}\Omega}{100 \text{k}\Omega}$ $\frac{5 \text{k}\Omega}{100 \text{k}\Omega}$ $\frac{5 \text{$

Equation 5.1. Calculating HVDA Output Voltage to AIN+

Figure 5.3. High Voltage Difference Amplifier Functional Diagram

## SFR Definition 5.4. HVA0CN: High Voltage Difference Amplifier Control

Reset Value R/W R R R/W R/W R/W R/W HVGAIN3 HVGAIN2 HVGAIN1 HVGAIN0 00000000 HVDAEN Bit7 Bit3 Bit2 Bit1 Bit6 Bit5 Bit4 Bit0

> SFR Address: 0xD6 SFR Page: 0

Bit7: HVDAEN: High Voltage Difference Amplifier (HVDA) Enable Bit.

0: The HVDA is disabled.1: The HVDA is enabled.

Bits6-3: Reserved.

Bits2-0: HVGAIN3-HVGAIN0: HVDA Gain Control Bits.

HVDA Gain Control Bits set the amplification gain if the difference signal input to the HVDA as defined in the table below:

HVGAIN3:HVGAIN0	HVDA Gain
0000	0.05
0001	0.1
0010	0.125
0011	0.2
0100	0.25
0101	0.4
0110	0.5
0111	0.8
1000	1.0
1001	1.6
1010	2.0
1011	3.2
1100	4.0
1101	6.2
1110	7.6
1111	14



### 5.3. ADC Modes of Operation

ADC0 has a maximum conversion speed of 100 ksps. The ADC0 conversion clock is derived from the system clock divided by the value held in the ADC0SC bits of register ADC0CF.

#### 5.3.1. Starting a Conversion

A conversion can be initiated in one of four ways, depending on the programmed states of the ADC0 Start of Conversion Mode bits (AD0CM1, AD0CM0) in ADC0CN. Conversions may be initiated by the following:

- Writing a '1' to the AD0BUSY bit of ADC0CN:
- A Timer 3 overflow (i.e., timed continuous conversions);
- A rising edge detected on the external ADC convert start signal, CNVSTR0;
- A Timer 2 overflow (i.e., timed continuous conversions).

The AD0BUSY bit is set to logic 1 during conversion and restored to logic 0 when conversion is complete. The falling edge of AD0BUSY triggers an interrupt (when enabled) and sets the AD0INT interrupt flag (ADC0CN.5). Converted data is available in the ADC0 data word MSB and LSB registers, ADC0H, ADC0L. Converted data can be either left or right justified in the ADC0H:ADC0L register pair (see example in Figure 5.7) depending on the programmed state of the AD0LJST bit in the ADC0CN register.

When initiating conversions by writing a '1' to AD0BUSY, the AD0INT bit should be polled to determine when a conversion has completed (ADC0 interrupts may also be used). The recommended polling procedure is shown below.


- Step 1. Write a '0' to AD0INT;
- Step 2. Write a '1' to AD0BUSY:
- Step 3. Poll AD0INT for '1';
- Step 4. Process ADC0 data.

#### 5.3.2. Tracking Modes

According to Table 5.2, each ADC0 conversion must be preceded by a minimum tracking time for the converted result to be accurate. The AD0TM bit in register ADC0CN controls the ADC0 track-and-hold mode. In its default state, the ADC0 input is continuously tracked when a conversion is not in progress. When the AD0TM bit is logic 1, ADC0 operates in low-power tracking mode. In this mode, each conversion is preceded by a tracking period of 3 SAR clocks after the start-of-conversion signal. When the CNVSTR0 signal is used to initiate conversions in low-power tracking mode, ADC0 tracks only when CNVSTR0 is low; conversion begins on the rising edge of CNVSTR0 (see Figure 5.4). Tracking can also be disabled when the entire chip is in low power standby or sleep modes. Low-power tracking mode is also useful when AMUX or PGA settings are frequently changed, to ensure that settling time requirements are met (see Section "5.3.3. Settling Time Requirements" on page 56).



## A. ADC Timing for External Trigger Source



### **B. ADC Timing for Internal Trigger Sources**




Figure 5.4. 12-Bit ADC Track and Conversion Example Timing



#### 5.3.3. Settling Time Requirements

A minimum tracking time is required before an accurate conversion can be performed. This tracking time is determined by the ADC0 MUX resistance, the ADC0 sampling capacitance, any external source resistance, and the accuracy required for the conversion. Figure 5.5 shows the equivalent ADC0 input circuits for both differential and Single-ended modes. Notice that the equivalent time constant for both input circuits is the same. The required settling time for a given settling accuracy (SA) may be approximated by Equation 5.2. When measuring the Temperature Sensor output,  $R_{TOTAL}$  reduces to  $R_{MUX}$ . Note that in Low-Power tracking mode, three SAR clocks are used for tracking at the start of every conversion. For most applications, these three SAR clocks will meet the tracking requirements. See Table 5.2 for absolute minimum settling/tracking time requirements.

$$t = \ln\left(\frac{2^n}{SA}\right) \times R_{TOTAL} C_{SAMPLE}$$

## **Equation 5.2. ADC0 Settling Time Requirements**

Where:

SA is the settling accuracy, given as a fraction of an LSB (for example, 0.25 to settle within 1/4 LSB) *t* is the required settling time in seconds

 $R_{TOTAL}$  is the sum of the ADC0 MUX resistance and any external source resistance. n is the ADC resolution in bits (12).

## **Differential Mode**

## **Single-Ended Mode**




Figure 5.5. ADC0 Equivalent Input Circuits






Figure 5.6. Temperature Sensor Transfer Function



## SFR Definition 5.5. ADC0CF: ADC0 Configuration Register

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
AD0SC4	AD0SC3	AD0SC2	AD0SC1	AD0SC0	AMP0GN2	AMP0GN1	AMP0GN0	11111000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xBC SFR Page: 0

Bits7-3: AD0SC4-0: ADC0 SAR Conversion Clock Period Bits

SAR Conversion clock is derived from system clock by the following equation, where *ADOSC* refers to the 5-bit value held in ADOSC4-0, and *CLK*<sub>SAR0</sub> refers to the desired ADC0 SAR clock. See Table 5.2 for SAR clock configuration requirements.

$$AD0SC \ge \frac{SYSCLK}{CLK_{SAR0}} - 1 *$$
 or  $CLK_{SAR0} = \frac{SYSCLK}{AD0SC + 1}$ 

\*Note: AD0SC is the rounded-up result.

Bits2-0: AMP0GN2-0: ADC0 Internal Amplifier Gain (PGA)

000: Gain = 1 001: Gain = 2 010: Gain = 4 011: Gain = 8 10x: Gain = 16 11x: Gain = 0.5

#### SFR Definition 5.6. ADC0CN: ADC0 Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
AD0EN	AD0TM	AD0INT	AD0BUSY	AD0CM1	AD0CM0	AD0WINT	AD0LJST	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xE8 SFR Page: 0

Bit7: AD0EN: ADC0 Enable Bit.

0: ADC0 Disabled. ADC0 is in low-power shutdown.

1: ADC0 Enabled. ADC0 is active and ready for data conversions.

Bit6: AD0TM: ADC Track Mode Bit

0: When the ADC is enabled, tracking is continuous unless a conversion is in process

1: Tracking Defined by AD0CM1-0 bits

Bit5: AD0INT: ADC0 Conversion Complete Interrupt Flag.

This flag must be cleared by software.

0: ADC0 has not completed a data conversion since the last time this flag was cleared.

1: ADC0 has completed a data conversion.

Bit4: AD0BUSY: ADC0 Busy Bit.

Read:

0: ADC0 Conversion is complete or a conversion is not currently in progress. AD0INT is set to logic 1 on the falling edge of AD0BUSY.

1: ADC0 Conversion is in progress.

Write:

0: No Effect.

1: Initiates ADC0 Conversion if AD0CM1-0 = 00b

Bit3-2: AD0CM1-0: ADC0 Start of Conversion Mode Select.

If AD0TM = 0:

00: ADC0 conversion initiated on every write of '1' to AD0BUSY.

01: ADC0 conversion initiated on overflow of Timer 3.

10: ADC0 conversion initiated on rising edge of external CNVSTR0.

11: ADC0 conversion initiated on overflow of Timer 2.

If AD0TM = 1:

00: Tracking starts with the write of '1' to AD0BUSY and lasts for 3 SAR clocks, followed by conversion.

01: Tracking started by the overflow of Timer 3 and last for 3 SAR clocks, followed by conversion

10: ADC0 tracks only when CNVSTR0 input is logic low; conversion starts on rising CNVSTR0 edge.

11: Tracking started by the overflow of Timer 2 and last for 3 SAR clocks, followed by conversion.

Bit1: AD0WINT: ADC0 Window Compare Interrupt Flag.

This bit must be cleared by software.

0: ADC0 Window Comparison Data match has not occurred since this flag was last cleared.

1: ADC0 Window Comparison Data match has occurred.

Bit0: AD0LJST: ADC0 Left Justify Select.

0: Data in ADC0H:ADC0L registers are right-justified.

1: Data in ADC0H:ADC0L registers are left-justified.



### SFR Definition 5.7. ADC0H: ADC0 Data Word MSB

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:
							SFR Addres	s: 0xBF
							SFR Pag	e: 0

Bits7-0: ADC0 Data Word High-Order Bits.

For AD0LJST = 0: Bits 7-4 are the sign extension of Bit3. Bits 3-0 are the upper 4 bits of the

12-bit ADC0 Data Word.

For AD0LJST = 1: Bits 7-0 are the most-significant bits of the 12-bit ADC0 Data Word.

#### SFR Definition 5.8. ADC0L: ADC0 Data Word LSB

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:
							SFR Address	s: 0xBE
							SFR Page	e: 0

Bits7-0: ADC0 Data Word Low-Order Bits.

For AD0LJST = 0: Bits 7-0 are the lower 8 bits of the 12-bit ADC0 Data Word.

For AD0LJST = 1: Bits 7-4 are the lower 4 bits of the 12-bit ADC0 Data Word. Bits3-0 will

always read '0'.



## 12-bit ADC0 Data Word appears in the ADC0 Data Word Registers as follows:

ADC0H[3:0]:ADC0L[7:0], if AD0LJST = 0

(ADC0H[7:4] will be sign-extension of ADC0H.3 for a differential reading, otherwise = 0000b).

ADC0H[7:0]:ADC0L[7:4], if AD0LJST = 1 (ADC0L[3:0] = 0000b).

Example: ADC0 Data Word Conversion Map, AIN0 Input in Single-Ended Mode (AMX0CF = 0x00, AMX0SL = 0x00)

AIN0-AGND (Volts)	ADC0H:ADC0L (AD0LJST = 0)	ADC0H:ADC0L (AD0LJST = 1)
VREF * (4095/4096)	0x0FFF	0xFFF0
VREF / 2	0x0800	0x8000
VREF * (2047/4096)	0x07FF	0x7FF0
0	0x0000	0x0000

Example: ADC0 Data Word Conversion Map, AIN0-AIN1 Differential Input Pair (AMX0CF = 0x01, AMX0SL = 0x00)

AIN0-AGND (Volts)	ADC0H:ADC0L (AD0LJST = 0)	ADC0H:ADC0L (AD0LJST = 1)
VREF * (2047/2048)	0x07FF	0x7FF0
VREF / 2	0x0400	0x4000
VREF * (1/2048)	0x0001	0x0010
0	0x0000	0x0000
-VREF * (1/2048)	0xFFFF (-1d)	0xFFF0
-VREF / 2	0xFC00 (-1024d)	0xC000
-VREF	0xF800 (-2048d)	0x8000

For AD0LJST = 0:

$$Code = Vin \times \frac{Gain}{VREF} \times 2^n$$
; 'n' = 12 for Single-Ended; 'n'=11 for Differential.


Figure 5.7. ADC0 Data Word Example




## 5.4. ADC0 Programmable Window Detector

The ADC0 Programmable Window Detector continuously compares the ADC0 output to user-programmed limits, and notifies the system when an out-of-bound condition is detected. This is especially effective in an interrupt-driven system, saving code space and CPU bandwidth while delivering faster system response times. The window detector interrupt flag (AD0WINT in ADC0CN) can also be used in polled mode. The high and low bytes of the reference words are loaded into the ADC0 Greater-Than and ADC0 Less-Than registers (ADC0GTH, ADC0GTL, ADC0LTH, and ADC0LTL). Reference comparisons are shown starting on page 63. Notice that the window detector flag can be asserted when the measured data is inside or outside the user-programmed limits, depending on the programming of the ADC0GTx and ADC0LTx registers.

#### SFR Definition 5.9. ADC0GTH: ADC0 Greater-Than Data High Byte



#### SFR Definition 5.10. ADC0GTL: ADC0 Greater-Than Data Low Byte




## SFR Definition 5.11. ADC0LTH: ADC0 Less-Than Data High Byte

	R/W	Reset Value								
	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0 SFR Address SFR Page		
Bits7-0: High byte of ADC0 Less-Than Data Word.										



#### SFR Definition 5.12. ADC0LTL: ADC0 Less-Than Data Low Byte






Figure 5.8. 12-Bit ADC0 Window Interrupt Example: Right Justified Single-Ended Data






Figure 5.9. 12-Bit ADC0 Window Interrupt Example: Right Justified Differential Data






Figure 5.10. 12-Bit ADC0 Window Interrupt Example: Left Justified Single-Ended Data






Figure 5.11. 12-Bit ADC0 Window Interrupt Example: Left Justified Differential Data



**Table 5.2. 12-Bit ADC0 Electrical Characteristics** 

 $V_{DD}$  = 3.0 V, AV+ = 3.0 V, VREF = 2.40 V (REFBE = 0), PGA Gain = 1, -40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
DC Accuracy			I.		
Resolution			12		bits
Integral Nonlinearity		_	_	±1	LSB
Differential Nonlinearity	Guaranteed Monotonic	_	_	±1	LSB
Offset Error	Note 1	_	0.5±3	_	LSB
Full Scale Error	Differential mode; See Note 1	_	0.4±3	_	LSB
Offset Temperature Coefficient		_	±0.25	_	ppm/°C
Dynamic Performance (10 kHz s	sine-wave input, 0 to 1 dB belo	w Full S	cale, 10	0 ksps)	
Signal-to-Noise Plus Distortion		66	_	_	dB
Total Harmonic Distortion	Up to the 5 <sup>th</sup> harmonic	_	-75	_	dB
Spurious-Free Dynamic Range		_	80	_	dB
Conversion Rate			l		
Maximum SAR Clock Frequency		_	_	2.5	MHz
Conversion Time in SAR Clocks		16	_	_	clocks
Track/Hold Acquisition Time		1.5	_	_	μs
Throughput Rate		_		100	ksps
Analog Inputs		1	•		
Input Voltage Range	Single-ended operation	0		VREF	V
Common-mode Voltage Range	Differential operation	AGND		AV+	V
Input Capacitance		_	10	_	pF
Temperature Sensor		1	•		
Nonlinearity	Notes 1, 2	_	±1	_	°C
Absolute Accuracy	Notes 1, 2	_	±3	_	°C
Gain	Notes 1, 2	_	2.86 ±0.034	_	mV/°C
Offset	Notes 1, 2 (Temp = 0 °C)	_	0.776 ±0.009		V
Power Specifications	•				
Power Supply Current (AV+ supplied to ADC)	Operating Mode, 100 ksps	_	450	900	μΑ
Power Supply Rejection		_	±0.3	_	mV/V
Notes:	1	1	1		

#### Notes:

- 1. Represents one standard deviation from the mean.
- 2. Includes ADC offset, gain, and linearity variations.



# Table 5.3. High-Voltage Difference Amplifier Electrical Characteristics $V_{DD}$ = 3.0 V, AV+ = 3.0 V, $V_{REF}$ = 3.0 V, -40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Analog Inputs					
Differential range	peak-to-peak	_	_	60	V
Common Mode Range	(HVAIN+) - (HVAIN-) = 0 V	-60	_	+60	V
Analog Output					
Output Voltage Range		0.1	_	2.9	V
DC Performance					
Common Mode Rejection Ratio	Vcm= -10 V to +10 V, Rs=0	44	52	_	dB
Offset Voltage		_	±3	_	mV
Noise	HVCAP floating	_	500	_	nV/rtHz
Nonlinearity	G = 1	_	72	_	dB
Dynamic Performance					
Small Signal Bandwidth	G = 0.05	_	3	_	MHz
Small Signal Bandwidth	G = 1	_	150	_	kHz
Slew Rate		_	2	_	V/µs
Settling Time	0.01%, G = 0.05, 10 V step	_	10	_	μs
Input/Output Impedance					
Differential (HVAIN+) input			105	_	kΩ
Differential (HVAIN-) input		_	98	_	kΩ
Common Mode input			51	_	kΩ
HVCAP		_	5	_	kΩ
Power Specification		•			
Quiescent Current			450	1000	μΑ



## 6. 10-Bit ADC (ADC0, C8051F042/3/4/5/6/7 Only)

The ADC0 subsystem for the C8051F042/3/4/5/6/7 consists of a 9-channel, configurable analog multiplexer (AMUX0), a programmable gain amplifier (PGA0), and a 100 ksps, 10-bit successive-approximation-register ADC with integrated track-and-hold and Programmable Window Detector (see block diagram in Figure 6.1). The AMUX0, PGA0, Data Conversion Modes, and Window Detector are all configurable under software control via the Special Function Registers shown in Figure 6.1. The voltage reference used by ADC0 is selected as described in Section "9. Voltage Reference (C8051F040/2/4/6)" on page 113 for C8051F042/4/6 devices, or Section "10. Voltage Reference (C8051F041/3/5/7)" on page 117 for C8051F043/5/7 devices. The ADC0 subsystem (ADC0, track-and-hold and PGA0) is enabled only when the AD0EN bit in the ADC0 Control register (ADC0CN) is set to logic 1. The ADC0 subsystem is in low power shutdown when this bit is logic 0.




Figure 6.1. 10-Bit ADC0 Functional Block Diagram

## 6.1. Analog Multiplexer and PGA

The analog multiplexer can input analog signals to the ADC from four external analog input pins, Port 3 port pins (optionally configured as analog input pins), High Voltage Difference Amplifier, and an internally connected on-chip temperature sensor (temperature transfer function is shown in Figure 6.6). AMUX input pairs can be programmed to operate in either differential or single-ended mode. This allows the user to select the best measurement technique for each input channel, and even accommodates mode changes "on-the-fly". The AMUX defaults to all single-ended inputs upon reset. There are three registers associated with the AMUX: the Channel Selection register AMX0SL (SFR Definition 6.2), the Configuration register AMX0CF (SFR Definition 6.1), and the Port Pin Selection register AMX0PRT (SFR Definition 6.3). Table 6.1 shows AMUX functionality by channel for each possible configuration. The PGA amplifies the AMUX output signal by an amount determined by the states of the AMP0GN2-0 bits in the ADC0 Configuration register, ADC0CF (SFR Definition 6.5). The PGA can be software-programmed for gains of 0.5, 2, 4, 8 or 16. Gain defaults to unity on reset.



### 6.1.1. Analog Input Configuration

The analog multiplexer routes signals from external analog input pins, Port 3 I/O pins (programmed to be analog inputs), a High Voltage Difference Amplifier, and an on-chip temperature sensor as shown in Figure 6.2.




Figure 6.2. Analog Input Diagram

Analog signals may be input from four external analog input pins (AIN0.0 through AIN0.3) as differential or single-ended measurements. Additionally, Port 3 I/O Port Pins may be configured to input analog signals. Port 3 pins configured as analog inputs are selected using the Port Pin Selection register (AMX0PRT). Any number of Port 3 pins may be selected simultaneously as inputs to the AMUX. Even numbered Port 3 pins and odd numbered Port 3 pins are routed to separate AMUX inputs. (**Note:** Even port pins and odd port pins that are simultaneously selected will be shorted together as "wired-OR".) In this way, differential measurements may be made when using the Port 3 pins (voltage difference between selected even and odd Port 3 pins) as shown in Figure 6.2.

The High-Voltage Difference Amplifier (HVDA) will accept analog input signals and reject up to 60 volts common-mode for differential measurement of up to the reference voltage to the ADC (0 to VREF volts). The output of the HVDA can be selected as an input to the ADC using the AMUX as any other channel is selected for measurement.



## SFR Definition 6.1. AMX0CF: AMUX0 Configuration

	R	R	R	R	R/W	R/W	R/W	R/W	Reset Value
	-	-	-	-	PORT3IC	HVDA2C	AIN23IC	AIN01IC	00000000
_	Rit7	Bit6	Bit5	Rit4	Bit3	Rit2	Rit1	Rit0	SFR Address:

SFR Address: 0xBA SFR Page: 0

Bits7-4: UNUSED. Read = 0000b; Write = don't care

Bit3: PORT3IC: Port 3 even/odd Pin Input Pair Configuration Bit

0: Port 3 even and odd input channels are independent single-ended inputs

1: Port 3 even and odd input channels are (respectively) +, - differential input pair

Bit2: HVDA2C: HVDA 2's Compliment Bit

0: HVDA output measured as an independent single-ended input

1: 2's compliment value Result from HVDA

Bit1: AIN23IC: AIN2, AIN3 Input Pair Configuration Bit

0: AIN2 and AIN3 are independent single-ended inputs
1: AIN2, AIN3 are (respectively) +, - differential input pair

Bit0: AIN01IC: AIN0, AIN1 Input Pair Configuration Bit

0: AIN0 and AIN1 are independent single-ended inputs 1: AIN0, AIN1 are (respectively) +, - differential input pair

NOTE: The ADC0 Data Word is in 2's complement format for channels configured as differential.

#### SFR Definition 6.2. AMX0SL: AMUX0 Channel Select

R	R	R	R	R/W	R/W	R/W	R/W	Reset Value
-	-	-	-	AMX0AD3	AMX0AD2	AMX0AD1	AMX0AD0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	•

SFR Address: 0xBB SFR Page: 0

Bits7-4: UNUSED. Read = 0000b; Write = don't care

Bits3-0: AMX0AD3-0: AMX0 Address Bits

0000-1111b: ADC Inputs selected per Table 6.1.



Table 6.1. AMUX Selection Chart (AMX0AD3-0 and AMX0CF3-0 bits)

					A	MX0AD3-	0			
		0000	0001	0010	0011	0100	0101	0110	0111	1xxx
	0000	AIN0.0	AIN0.1	AIN0.2	AIN0.3	HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0001	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0010	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0011	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		HVDA	AGND	P3EVEN	P3ODD	TEMP SENSOR
	0100	AIN0.0	AIN0.1	AIN0.2	AIN0.3	+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
	0101	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
3-0	0110	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
Bits	0111	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		P3EVEN	P3ODD	TEMP SENSOR
AMX0CF	1000	AIN0.0	AIN0.1	AIN0.2	AIN0.3	HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
AM	1001	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
	1010	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
	1011	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		HVDA	AGND	+P3EVEN -P3ODD		TEMP SENSOR
	1100	AIN0.0	AIN0.1	AIN0.2	AIN0.3	+(HVDA) -(HVREF)		+P3EVEN -P3ODD)		TEMP SENSOR
	1101	+(AIN0.0) -(AIN0.1)		AIN0.2	AIN0.3	+(HVDA) -(HVREF)		+P3EVEN -P3ODD		TEMP SENSOR
	1110	AIN0.0	AIN0.1	+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		+P3EVEN -P3ODD		TEMP SENSOR
	1111	+(AIN0.0) -(AIN0.1)		+(AIN0.2) -(AIN0.3)		+(HVDA) -(HVREF)		+P3EVEN -P3ODD		TEMP SENSOR

**Note:** "P3EVEN" denotes even numbered and "P3ODD" odd numbered Port 3 pins selected in the AMX0PRT register.



### SFR Definition 6.3. AMX0PRT: Port 3 Pin Selection

R/W R/W R/W R/W R/W Reset Value R/W R/W R/W PAIN6EN PAIN5EN PAIN4EN PAIN3EN PAIN2EN PAIN1EN PAIN0EN 00000000 PAIN7EN Bit7 Bit6 Bit5 Bit4 Bit3 Bit2 Bit1 Bit0

> SFR Address: 0xBA SFR Page: 0

Bit7: PAIN7EN: Pin 7 Analog Input Enable Bit

0: P3.7 is not selected as an analog input to the AMUX.1: P3.7 is selected as an analog input to the AMUX.

Bit6: PAIN6EN: Pin 6 Analog Input Enable Bit

0: P3.6 is not selected as an analog input to the AMUX.1: P3.6 is selected as an analog input to the AMUX.

Bit5: PAIN5EN: Pin 5 Analog Input Enable Bit

0: P3.5 is not selected as an analog input to the AMUX.1: P3.5 is selected as an analog input to the AMUX.

Bit4: PAIN4EN: Pin 4 Analog Input Enable Bit

0: P3.4 is not selected as an analog input to the AMUX.1: P3.4 is selected as an analog input to the AMUX.

Bit3: PAIN3EN: Pin 3 Analog Input Enable Bit

0: P3.3 is not selected as an analog input to the AMUX.

1: P3.3 is enabled as an analog input to the AMUX.

Bit2: PAIN2EN: Pin 2 Analog Input Enable Bit

 $0:\mbox{\sc P3.2}$  is not selected as an analog input to the AMUX.

1: P3.2 is enabled as an analog input to the AMUX.

Bit1: PAIN1EN: Pin 1 Analog Input Enable Bit

0: P3.1 is not selected as an analog input to the AMUX.

1: P3.1 is enabled as an analog input to the AMUX.

Bit0: PAIN0EN: Pin 0 Analog Input Enable Bit

0: P3.0 is not selected as an analog input to the AMUX.

1: P3.0 is enabled as an analog input to the AMUX.

**NOTE:** Any number of Port 3 pins may be selected simultaneously inputs to the AMUX. Odd numbered and even numbered pins that are selected simultaneously are shorted together as "wired-OR".



### 6.2. High-Voltage Difference Amplifier

The High-Voltage Difference Amplifier (HVDA) can be used to measure high differential voltages up to 60 V peak-to-peak, reject high common-mode voltages up to ±60 V, and condition the signal voltage range to be suitable for input to ADC0. The input signal to the HVDA may be below AGND to –60 volts, and as high as +60 volts, making the device suitable for both single and dual supply applications. The HVDA provides a common-mode signal for the ADC via the High Voltage Reference Input (HVREF), allowing measurement of signals outside the specified ADC input range using on-chip circuitry. The HVDA has a gain of 0.05 V/V to 14 V/V. The first stage 20:1 difference amplifier has a gain of 0.05 V/V when the output amplifier is used as a unity gain buffer. When the output amplifier is set to a gain of 280 (selected using the HVGAIN bits in the High Voltage Control Register), an overall gain of 14 can be attained.

The HVDA uses four available external pins: +HVAIN, -HVAIN, HVCAP, and HVREF. HVAIN+ and HVAIN-serve as the differential inputs to the HVDA. HVREF should be used to provide a common mode reference for input to ADC0, and to prevent the output of the HVDA circuit from saturating. The output from the HVDA circuit as calculated by Equation 6.1 must remain within the "Output Voltage Range" specification listed in Table 6.3. The ideal value for HVREF in most applications is equal to 1/2 the supply voltage for the device. When the ADC is configured for differential measurement, the HVREF signal is applied to the AIN-input of the ADC, thereby removing HVREF from the measurement. HVCAP facilitates the use of a capacitor for noise filtering in conjunction with R7 (see Figure 6.3 for R7 and other approximate resistor values). Alternatively, the HVCAP could also be used to access amplification of the first stage of the HVDA at an external pin. (See Table 6.3 on page 90 for electrical specifications of the HVDA.)

$$V_{OUT} = [(HVAIN+) - (HVAIN-)] \cdot Gain + HVREF$$

**Note:** The output voltage of the HVDA is selected as an input to the AIN+ input of ADC0 via its analog multiplexer (AMUX0). HVDA output voltages outside the ADC's input range will result in saturation of the ADC input. Allow for adequate settle/tracking time for proper voltage measurements.

# HVAIN- HVAIN- HVAOCN HVAINH HVAOCN (To AMUX0) Resistor values are approximate HVREF

Equation 6.1. Calculating HVDA Output Voltage to AIN+

Figure 6.3. High Voltage Difference Amplifier Functional Diagram



### SFR Definition 6.4. HVA0CN: High Voltage Difference Amplifier Control

Reset Value R/W R R R/W R/W R/W R/W HVGAIN3 HVGAIN2 HVGAIN1 HVGAIN0 00000000 HVDAEN Bit7 Bit3 Bit2 Bit1 Bit6 Bit5 Bit4 Bit0

> SFR Address: 0xD6 SFR Page: 0

Bit7: HVDAEN: High Voltage Difference Amplifier (HVDA) Enable Bit.

0: The HVDA is disabled.1: The HVDA is enabled.

Bits6-3: Reserved.

Bits2-0: HVGAIN3-HVGAIN0: HVDA Gain Control Bits.

HVDA Gain Control Bits set the amplification gain if the difference signal input to the HVDA

as defined in the table below:

HVGAIN3:HVGAIN0	HVDA Gain
0000	0.05
0001	0.1
0010	0.125
0011	0.2
0100	0.25
0101	0.4
0110	0.5
0111	0.8
1000	1.0
1001	1.6
1010	2.0
1011	3.2
1100	4.0
1101	6.2
1110	7.6
1111	14



### 6.3. ADC Modes of Operation

ADC0 has a maximum conversion speed of 100 ksps. The ADC0 conversion clock is derived from the system clock divided by the value held in the ADC0SC bits of register ADC0CF.

### 6.3.1. Starting a Conversion

A conversion can be initiated in one of four ways, depending on the programmed states of the ADCO Start of Conversion Mode bits (ADOCM1, ADOCM0) in ADCOCN. Conversions may be initiated by the following:

- Writing a '1' to the AD0BUSY bit of ADC0CN;
- A Timer 3 overflow (i.e., timed continuous conversions);
- A rising edge detected on the external ADC convert start signal, CNVSTR0;
- A Timer 2 overflow (i.e., timed continuous conversions).

The AD0BUSY bit is set to logic 1 during conversion and restored to logic 0 when conversion is complete. The falling edge of AD0BUSY triggers an interrupt (when enabled) and sets the AD0INT interrupt flag (ADC0CN.5). Converted data is available in the ADC0 data word MSB and LSB registers, ADC0H, ADC0L. Converted data can be either left or right justified in the ADC0H:ADC0L register pair (see example in Figure 6.7) depending on the programmed state of the AD0LJST bit in the ADC0CN register.

When initiating conversions by writing a '1' to AD0BUSY, the AD0INT bit should be polled to determine when a conversion has completed (ADC0 interrupts may also be used). The recommended polling procedure is shown below.


- Step 1. Write a '0' to AD0INT;
- Step 2. Write a '1' to AD0BUSY:
- Step 3. Poll AD0INT for '1';
- Step 4. Process ADC0 data.

### 6.3.2. Tracking Modes

According to Table 6.2, each ADC0 conversion must be preceded by a minimum tracking time for the converted result to be accurate. The AD0TM bit in register ADC0CN controls the ADC0 track-and-hold mode. In its default state, the ADC0 input is continuously tracked when a conversion is not in progress. When the AD0TM bit is logic 1, ADC0 operates in low-power tracking mode. In this mode, each conversion is preceded by a tracking period of 3 SAR clocks after the start-of-conversion signal. When the CNVSTR0 signal is used to initiate conversions in low-power tracking mode, ADC0 tracks only when CNVSTR0 is low; conversion begins on the rising edge of CNVSTR0 (see Figure 6.4). Tracking can also be disabled when the entire chip is in low power standby or sleep modes. Low-power tracking mode is also useful when AMUX or PGA settings are frequently changed, to ensure that settling time requirements are met (see Section "6.3.3. Settling Time Requirements" on page 78).



### A. ADC Timing for External Trigger Source



### **B. ADC Timing for Internal Trigger Sources**




Figure 6.4. 10-Bit ADC Track and Conversion Example Timing



### 6.3.3. Settling Time Requirements

A minimum tracking time is required before an accurate conversion can be performed. This tracking time is determined by the ADC0 MUX resistance, the ADC0 sampling capacitance, any external source resistance, and the accuracy required for the conversion. Figure 6.5 shows the equivalent ADC0 input circuits for both Differential and Single-ended modes. Notice that the equivalent time constant for both input circuits is the same. The required settling time for a given settling accuracy (SA) may be approximated by Equation 6.2. When measuring the Temperature Sensor output,  $R_{TOTAL}$  reduces to  $R_{MUX}$ . Note that in low-power tracking mode, three SAR clocks are used for tracking at the start of every conversion. For most applications, these three SAR clocks will meet the tracking requirements. See Table 6.2 for absolute minimum settling/tracking time requirements.

$$t = \ln\left(\frac{2^n}{SA}\right) \times R_{TOTAL} C_{SAMPLE}$$

### **Equation 6.2. ADC0 Settling Time Requirements**

### Where:

SA is the settling accuracy, given as a fraction of an LSB (for example, 0.25 to settle within 1/4 LSB) *t* is the required settling time in seconds

 $R_{TOTAL}$  is the sum of the ADC0 MUX resistance and any external source resistance. n is the ADC resolution in bits (10).

### **Differential Mode**

# **Single-Ended Mode**





Figure 6.5. ADC0 Equivalent Input Circuits





**Figure 6.6. Temperature Sensor Transfer Function** 



### SFR Definition 6.5. ADC0CF: ADC0 Configuration

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
AD0SC4	AD0SC3	AD0SC2	AD0SC1	AD0SC0	AMP0GN2	AMP0GN1	AMP0GN0	11111000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	•

SFR Address: 0xBC SFR Page: 0

Bits7-3: AD0SC4-0: ADC0 SAR Conversion Clock Period Bits

SAR Conversion clock is derived from system clock by the following equation, where ADOSC refers to the 5-bit value held in ADOSC4-0, and  $CLK_{SAR0}$  refers to the desired ADC0 SAR clock. See Table 6.2 on page 89 for SAR clock setting requirements.

$$AD0SC \ge \frac{SYSCLK}{CLK_{SAR0}} - 1 *$$
 or  $CLK_{SAR0} = \frac{SYSCLK}{AD0SC + 1}$ 

\*Note: AD0SC is the rounded-up result.

Bits2-0: AMP0GN2-0: ADC0 Internal Amplifier Gain (PGA)

000: Gain = 1 001: Gain = 2 010: Gain = 4 011: Gain = 8 10x: Gain = 16 11x: Gain = 0.5



### SFR Definition 6.6. ADC0CN: ADC0 Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
AD0EN	AD0TM	AD0INT	AD0BUSY	AD0CM1	AD0CM0	AD0WINT	AD0LJST	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xE8 SFR Page: 0

Bit7: AD0EN: ADC0 Enable Bit.

0: ADC0 Disabled. ADC0 is in low-power shutdown.

1: ADC0 Enabled. ADC0 is active and ready for data conversions.

Bit6: AD0TM: ADC Track Mode Bit

0: When the ADC is enabled, tracking is continuous unless a conversion is in process

1: Tracking Defined by AD0CM1-0 bits

Bit5: AD0INT: ADC0 Conversion Complete Interrupt Flag.

This flag must be cleared by software.

0: ADC0 has not completed a data conversion since the last time this flag was cleared.

1: ADC0 has completed a data conversion.

Bit4: AD0BUSY: ADC0 Busy Bit.

Read:

0: ADC0 Conversion is complete or a conversion is not currently in progress. AD0INT is set to logic 1 on the falling edge of AD0BUSY.

1: ADC0 Conversion is in progress.

Write:

0: No Effect.

1: Initiates ADC0 Conversion if AD0CM1-0 = 00b

Bit3-2: AD0CM1-0: ADC0 Start of Conversion Mode Select.

If AD0TM = 0:

00: ADC0 conversion initiated on every write of '1' to AD0BUSY.

01: ADC0 conversion initiated on overflow of Timer 3.

10: ADC0 conversion initiated on rising edge of external CNVSTR0.

11: ADC0 conversion initiated on overflow of Timer 2.

If AD0TM = 1:

00: Tracking starts with the write of '1' to AD0BUSY and lasts for 3 SAR clocks, followed by conversion.

01: Tracking started by the overflow of Timer 3 and last for 3 SAR clocks, followed by conversion.

10: ADC0 tracks only when CNVSTR0 input is logic low; conversion starts on rising CNVSTR0 edge.

11: Tracking started by the overflow of Timer 2 and last for 3 SAR clocks, followed by conversion.

Bit1: AD0WINT: ADC0 Window Compare Interrupt Flag.

This bit must be cleared by software.

0: ADC0 Window Comparison Data match has not occurred since this flag was last cleared.

1: ADC0 Window Comparison Data match has occurred.

Bit0: AD0LJST: ADC0 Left Justify Select.

0: Data in ADC0H:ADC0L registers are right-justified.

1: Data in ADC0H:ADC0L registers are left-justified.



### SFR Definition 6.7. ADC0H: ADC0 Data Word MSB

R/W	Reset Value							
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:

SFR Address: 0xBF SFR Page: 0

Bits7-0: ADC0 Data Word High-Order Bits.

For AD0LJST = 0: Bits 7-2 are the sign extension of Bit 1. Bits 0 and 1 are the upper 2 bits of

the 10-bit ADC0 Data Word.

For AD0LJST = 1: Bits 7-0 are the most-significant bits of the 10-bit ADC0 Data Word.

### SFR Definition 6.8. ADC0L: ADC0 Data Word LSB

Ī	R/W	Reset Value							
_	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:
								SFR Address SFR Page	

Bits7-0: ADC0 Data Word Low-Order Bits.

For AD0LJST = 0: Bits 7-0 are the lower 8 bits of the 10-bit ADC0 Data Word.

For AD0LJST = 1: Bits 6 and 7 are the lower 2 bits of the 10-bit ADC0 Data Word. Bits 5-0

### 10-bit ADC Data Word appears in the ADC Data Word Registers as follows:

ADC0H[1:0]:ADC0L[7:0], if ADLJST = 0

(ADC0H[7:2] will be sign-extension of ADC0H.1 for a differential reading, otherwise = 000000b).

ADC0H[7:0]:ADC0L[7:6], if ADLJST = 1 (ADC0L[5:0] = 000000b).

Example: ADC Data Word Conversion Map, AIN0 Input in Single-Ended Mode (AMX0CF = 0x00, AMX0SL = 0x00)

AIN0-AGND (Volts)	ADC0H:ADC0L (ADLJST = 0)	ADC0H:ADC0L (ADLJST = 1)
VREF * (1023/1024)	0x03FF	0xFFC0
VREF / 2	0x0200	0x8000
VREF * (511/1024)	0x01FF	0x7FC0
0	0x0000	0x0000

Example: ADC Data Word Conversion Map, AIN0-AIN1 Differential Input Pair (AMX0CF = 0x01, AMX0SL = 0x00)

AIN0-AGND (Volts)	ADC0H:ADC0L (ADLJST = 0)	ADC0H:ADC0L (ADLJST = 1)
VREF * (511/512)	0x01FF	0x7FC0
VREF / 2	0x0100	0x4000
VREF * (1/512)	0x0001	0x0040
0	0x0000	0x0000
-VREF * (1/512)	0xFFFF (-1)	0xFFC0
-VREF / 2	0xFF00 (-256)	0xC000
-VREF	0xFE00 (-512)	0x8000

ADLJST = 0:

$$Code = Vin \times \frac{Gain}{VREF} \times 2^n$$
; 'n' = 10 for Single-Ended; 'n'=9 for Differential.


Figure 6.7. ADC0 Data Word Example




### 6.4. ADC0 Programmable Window Detector

The ADC0 Programmable Window Detector continuously compares the ADC0 output to user-programmed limits, and notifies the system when an out-of-bound condition is detected. This is especially effective in an interrupt-driven system, saving code space and CPU bandwidth while delivering faster system response times. The window detector interrupt flag (AD0WINT in ADC0CN) can also be used in polled mode. The high and low bytes of the reference words are loaded into the ADC0 Greater-Than and ADC0 Less-Than registers (ADC0GTH, ADC0GTL, ADC0LTH, and ADC0LTL). Reference comparisons are shown starting on page 85. Notice that the window detector flag can be asserted when the measured data is inside or outside the user-programmed limits, depending on the programming of the ADC0GTx and ADC0LTx registers.


### SFR Definition 6.9. ADC0GTH: ADC0 Greater-Than Data High Byte



### SFR Definition 6.10. ADC0GTL: ADC0 Greater-Than Data Low Byte




### SFR Definition 6.11. ADC0LTH: ADC0 Less-Than Data High Byte





### SFR Definition 6.12. ADC0LTL: ADC0 Less-Than Data Low Byte






Figure 6.8. 10-Bit ADC0 Window Interrupt Example: Right Justified Single-Ended Data






Figure 6.9. 10-Bit ADC0 Window Interrupt Example: Right Justified Differential Data






Figure 6.10. 10-Bit ADC0 Window Interrupt Example: Left Justified Single-Ended Data



Input Voltage (AD0 - AD1)	ADC Data Word		Input Voltage (AD0 - AD1)	ADC Data Word	
REF x (511/512)	0x7FC0		REF x (511/512)	0x7FC0	
		AD0WINT not affected			> ADOWINT=1
	0x4040			0x4040	<u> </u>
REF x (256/512)	0x4000	ADC0LTH:ADC0LTL	REF x (256/512)	0x4000	ADC0GTH:ADC0GTL
	0x3FC0 0x0000	AD0WINT=1		0x3FC0 0x0000	AD0WINT not affected
REF x (-1/512)	0xFFC0	ADC0GTH:ADC0GTL	REF x (-1/512)	0x0000	ADC0LTH:ADC0LTL
***************************************	0xFF80			0xFF80	
		AD0WINT not affected			> ADOWINT=1
-REF	0x8000		-REF	0x8000	J

Given:

AMX0SL = 0x00, AMX0CF = 0x01, ADLJST = 1, ADC0LTH:ADC0LTL = 0x4000, ADC0GTH:ADC0GTL = 0xFFC0. An ADC End of Conversion will cause an ADC Window Compare Interrupt (ADWINT=1) if the resulting ADC Data Word is < 0x4000 and > 0xFFC0. (Two's-complement math.) Given:

AMX0SL = 0x00, AMX0CF = 0x01, ADLJST = 1, ADC0LTH:ADC0LTL = 0xFFC0, ADC0GTH:ADC0GTL = 0x4000. An ADC End of Conversion will cause an ADC Window Compare Interrupt (ADWINT=1) if the resulting ADC Data Word is < 0xFFC0 or > 0x4000. (Two's-complement math.)

Figure 6.11. 10-Bit ADC0 Window Interrupt Example: Left Justified Differential Data



**Table 6.2. 10-Bit ADC0 Electrical Characteristics** 

 $V_{DD}$  = 3.0 V, AV+ = 3.0 V,  $V_{REF}$  = 2.40 V (REFBE = 0), PGA Gain = 1, -40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units					
DC Accuracy				1						
Resolution			10		bits					
Integral Nonlinearity		_	_	±1	LSB					
Differential Nonlinearity	Guaranteed Monotonic	_	_	±1	LSB					
Offset Error		_	0.2±1	_	LSB					
Full Scale Error	Differential mode	_	0.1±1	_	LSB					
Offset Temperature Coefficient		_	±0.25	_	ppm/°C					
Dynamic Performance (10 kHz sine-wave input, 0 to 1 dB below Full Scale, 100 ksps)										
Signal-to-Noise Plus Distortion		59	_	_	dB					
Total Harmonic Distortion	Up to the 5 <sup>th</sup> harmonic	_	<del>-</del> 70	_	dB					
Spurious-Free Dynamic Range		_	80	_	dB					
Conversion Rate	1	•	•							
SAR Clock Frequency		_		2.5	MHz					
Conversion Time in SAR Clocks		16	_	_	clocks					
Track/Hold Acquisition Time		1.5	_	_	μs					
Throughput Rate		_	_	100	ksps					
Analog Inputs										
Input Voltage Range	Single-ended operation	0	_	VREF	V					
Common-mode Voltage Range	Differential operation	AGND	_	AV+	V					
Input Capacitance		_	10	_	pF					
Temperature Sensor										
Nonlinearity <sup>1,2</sup>		_	±1	_	°C					
Absolute Accuracy <sup>1,2</sup>		_	±3	_	°C					
Gain <sup>1,2</sup>		_	2.86 ±0.034	_	mV/°C					
Offset <sup>1,2</sup>	Temp = 0 °C	_	0.776 ±0.009		V					
Power Specifications	•	•	•							
Power Supply Current (AV+ supplied to ADC)	Operating Mode, 100 ksps	_	450	900	μΑ					
Power Supply Rejection		_	±0.3	_	mV/V					
Notes:	•	•	•							

### Notes:

- 1. Represents one standard deviation from the mean.
- 2. Includes ADC offset, gain, and linearity variations.



# Table 6.3. High-Voltage Difference Amplifier Electrical Characteristics $V_{DD}$ = 3.0 V, AV+ = 3.0 V, $V_{REF}$ = 3.0 V, -40 to +85 °C unless otherwise specified.

Parameter	Conditions Min Typ N		Max	Units	
Analog Inputs		•	•		
Differential range	peak-to-peak	_	_	60	V
Common Mode Range	$(HVAIN+) - (HVAIN-) = 0 V \qquad \qquad -60 \qquad - \qquad +60$		V		
Analog Output		•	•		
Output Voltage Range				2.9	V
DC Performance		•	•		
Common Mode Rejection Ratio	Vcm= -10 V to +10 V, Rs=0	44	52	_	dB
Offset Voltage		<u> </u>	±3	_	mV
Noise	HVCAP floating	HVCAP floating — 500 —		_	nV/rtHz
Nonlinearity	G = 1	— 72 —		dB	
Dynamic Performance	ynamic Performance				
Small Signal Bandwidth	G = 0.05	_	3		MHz
Small Signal Bandwidth	G = 1	_	150	_	kHz
Slew Rate		<u> </u>	2	_	V/µs
Settling Time	0.01%, G = 0.05, 10 V step	_	10	_	μs
Input/Output Impedance		1			
Differential (HVAIN+) input		_	105	_	kΩ
Differential (HVAIN-) input		_	98	_	kΩ
Common Mode input		<u> </u>		_	kΩ
HVCAP		<b> </b>	5	_	kΩ
Power Specification		1	ı		
Quiescent Current			450	1000	μΑ



### 7. 8-Bit ADC (ADC2, C8051F040/1/2/3 Only)

The ADC2 subsystem for the C8051F040/1/2/3 consists of an 8-channel, configurable analog multiplexer, a programmable gain amplifier, and a 500 ksps, 8-bit successive-approximation-register ADC with integrated track-and-hold (see block diagram in Figure 7.1). The AMUX2, PGA2, and Data Conversion Modes, are all configurable under software control via the Special Function Registers shown in Figure 7.1. The ADC2 subsystem (8-bit ADC, track-and-hold and PGA) is enabled only when the AD2EN bit in the ADC2 Control register (ADC2CN) is set to logic 1. The ADC2 subsystem is in low power shutdown when this bit is logic 0. The voltage reference used by ADC2 is selected as described in Section "9. Voltage Reference (C8051F040/2/4/6)" on page 113 for C8051F040/2 devices, or Section "10. Voltage Reference (C8051F041/3/5/7)" on page 117 for C8051F041/3 devices.




Figure 7.1. ADC2 Functional Block Diagram

### 7.1. Analog Multiplexer and PGA

Eight ADC2 channels are available for measurement, as selected by the AMX2SL register (see SFR Definition 7.2). The PGA amplifies the ADC2 output signal by an amount determined by the states of the AMP2GN2-0 bits in the ADC2 Configuration register, ADC2CF (SFR Definition 7.1). The PGA can be software-programmed for gains of 0.5, 1, 2, or 4. Gain defaults to 0.5 on reset.

**Important Note**: AIN2 pins also function as Port 1 I/O pins, and must be configured as analog inputs when used as ADC2 inputs. To configure an AIN2 pin for analog input, set to '0' the corresponding bit in register P1MDIN. Port 1 pins selected as analog inputs are skipped by the Digital I/O Crossbar. See **Section** "17.1.5. Configuring Port 1, 2, and 3 Pins as Analog Inputs" on page 207 for more information on configuring the AIN2 pins.



### 7.2. ADC2 Modes of Operation

ADC2 has a maximum conversion speed of 500 ksps. The ADC2 conversion clock (SAR2 clock) is a divided version of the system clock, determined by the AD2SC bits in the ADC2CF register (system clock divided by (AD2SC + 1) for  $0 \le AD2SC \le 31$ ). The maximum ADC2 conversion clock is 7.5 MHz.

### 7.2.1. Starting a Conversion

A conversion can be initiated in one of five ways, depending on the programmed states of the ADC2 Start of Conversion Mode bits (AD2CM2–0) in ADC2CN. Conversions may be initiated by the following:

- •Writing a '1' to the AD2BUSY bit of ADC2CN;
- •A Timer 3 overflow (i.e., timed continuous conversions);
- •A rising edge detected on the external ADC convert start signal, CNVSTR2 or CNVSTR0 (see important note below);
- •A Timer 2 overflow (i.e., timed continuous conversions);
- •Writing a '1' to the AD0BUSY of register ADC0CN (initiate conversion of ADC2 and ADC0 with a single software command).

An important note about external convert start (CNVSTR0 and CNVSTR2): If CNVSTR2 is enabled in the digital crossbar (Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204), CNVSTR2 will be the external convert start signal for ADC2. However, if only CNVSTR0 is enabled in the digital crossbar and CNVSTR2 is not enabled, then CNVSTR0 may serve as the start of conversion for both ADC0 and ADC2. This permits synchronous sampling of both ADC0 and ADC2.

During conversion, the AD2BUSY bit is set to logic 1 and restored to 0 when conversion is complete. The falling edge of AD2BUSY triggers an interrupt (when enabled) and sets the interrupt flag in ADC2CN. Converted data is available in the ADC2 data word, ADC2.

When a conversion is initiated by writing a '1' to AD2BUSY, it is recommended to poll AD2INT to determine when the conversion is complete. The recommended procedure is:

- Step 1. Write a '0' to AD2INT;
- Step 2. Write a '1' to AD2BUSY;
- Step 3. Poll AD2INT for '1';
- Step 4. Process ADC2 data.

### 7.2.2. Tracking Modes

According to Table 7.2, each ADC2 conversion must be preceded by a minimum tracking time for the converted result to be accurate. The AD2TM bit in register ADC2CN controls the ADC2 track-and-hold mode. In its default state, the ADC2 input is continuously tracked, except when a conversion is in progress. When the AD2TM bit is logic 1, ADC2 operates in low-power tracking mode. In this mode, each conversion is preceded by a tracking period of 3 SAR clocks (after the start-of-conversion signal). When the CNVSTR2 (or CNVSTR0, See Section 7.2.1 above) signal is used to initiate conversions in low-power tracking mode, ADC2 tracks only when CNVSTR2 is low; conversion begins on the rising edge of CNVSTR2 (see Figure 7.2). Tracking can also be disabled (shutdown) when the entire chip is in low power standby or sleep modes. Low-power Track-and-Hold mode is also useful when AMUX or PGA settings are frequently changed, due to the settling time requirements described in Section "7.2.3. Settling Time Requirements" on page 94.



# A. ADC Timing for External Trigger Source CNVSTR2/CNVSTR0 (AD2CM[2:0]=010) SAR2 Clocks AD2TM=1 Low Power or Convert Track Convert Low Power Mode AD2TM=0 Track or Convert Convert Track B. ADC Timing for Internal Trigger Source




Figure 7.2. ADC2 Track and Conversion Example Timing



### 7.2.3. Settling Time Requirements

A minimum tracking time is required before an accurate conversion can be performed. This tracking time is determined by the ADC2 MUX resistance, the ADC2 sampling capacitance, any external source resistance, and the accuracy required for the conversion. Figure 7.3 shows the equivalent ADC2 input circuit. The required ADC2 settling time for a given settling accuracy (SA) may be approximated by Equation 7.1. Note: An absolute minimum settling time of 0.8 µs required after any MUX selection. Note that in low-power tracking mode, three SAR2 clocks are used for tracking at the start of every conversion. For most applications, these three SAR2 clocks will meet the tracking requirements.

$$t = \ln\left(\frac{2^n}{SA}\right) \times R_{TOTAL}C_{SAMPLE}$$

### **Equation 7.1. ADC2 Settling Time Requirements**

Where:

SA is the settling accuracy, given as a fraction of an LSB (for example, 0.25 to settle within 1/4 LSB) *t* is the required settling time in seconds

 $R_{TOTAL}$  is the sum of the ADC2 MUX resistance and any external source resistance. n is the ADC resolution in bits (8).




Figure 7.3. ADC2 Equivalent Input Circuit



### SFR Definition 7.1. AMX2CF: AMUX2 Configuration

R	R	R	R	R/W	R/W	R/W	R/W	Reset Value
-	-	-	-	PIN67IC	PIN45IC	PIN23IC	PIN01IC	00000000
Rit7	Rit6	Rit5	Rit/I	Rit3	Rit2	Rit1	Rit∩	-

SFR Address: 0xBA SFR Page: 2

Bits7-4: UNUSED. Read = 0000b; Write = don't care
Bit3: PIN67IC: P1.6, P1.7 Input Pair Configuration Bit

0: P1.6 and P1.7 are independent single-ended inputs 1: P1.6, P1.7 are (respectively) +, - differential input pair

Bit2: PIN45IC: P1.4, P1.5 Input Pair Configuration Bit

0: P1.4 and P1.5 are independent single-ended inputs 1: P1.4, P1.5 are (respectively) +, - differential input pair

Bit1: PIN23IC: P1.2, P1.3 Input Pair Configuration Bit

0: P1.2 and P1.3 are independent single-ended inputs 1: P1.2, P1.3 are (respectively) +, - differential input pair

Bit0: PIN01IC: P1.0, P1.1 Input Pair Configuration Bit

0: P1.0 and P1.1 are independent single-ended inputs 1: P1.0, P1.1 are (respectively) +, - differential input pair

NOTE: The ADC2 Data Word is in 2's complement format for channels configured as differential.

### SFR Definition 7.2. AMX2SL: AMUX2 Channel Select

R	R	R	R	R	R/W	R/W	R/W	Reset Value
-	-	-	-	-	AMX2AD2	AMX2AD1	AMX2AD0	00000000
Di+7	Dit6	Dit5	Di+/	Di+2	Bi+2	Di+1	₽iŧ∩	

SFR Address: 0xBB SFR Page: 2

Bits7-3: UNUSED. Read = 00000b; Write = don't care

Bits2-0: AMX2AD2-0: AMX2 Address Bits

000-111b: ADC Inputs selected per Table 7.1.



Table 7.1. AMUX Selection Chart (AMX2AD2-0 and AMX2CF3-0 bits)

					AMX2	AD2-0			
		000	001	010	011	100	101	110	111
	0000	P1.0	P1.1	P1.2	P1.3	P1.4	P1.5	P1.6	P1.7
	0001	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	P1.2	P1.3	P1.4	P1.5	P1.6	P1.7
	0010	P1.0	P1.1	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	P1.4	P1.5	P1.6	P1.7
	0011	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	P1.4	P1.5	P1.6	P1.7
	0100	P1.0	P1.1	P1.2	P1.3	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	P1.6	P1.7
	0101	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	P1.2	P1.3	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	P1.6	P1.7
3-0	0110	P1.0	P1.1	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	P1.6	P1.7
Bits 3	0111	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	P1.6	P1.7
AMX2CF	1000	P1.0	P1.1	P1.2	P1.3	P1.4	P1.5	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
AMX	1001	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	P1.2	P1.3	P1.4	P1.5	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
	1010	P1.0	P1.1	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	P1.4	P1.5	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
	1011	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	P1.4	P1.5	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
	1100	P1.0	P1.1	P1.2	P1.3	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
	1101	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	P1.2	P1.3	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
	1110	P1.0	P1.1	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)
	1111	+(P1.0) -(P1.1)	-(P1.0) +(P1.1)	+(P1.2) -(P1.3)	-(P1.2) +(P1.3)	+(P1.4) -(P1.5)	-(P1.4) +(P1.5)	+(P1.6) -(P1.7)	-(P1.6) +(P1.7)

### SFR Definition 7.3. ADC2CF: ADC2 Configuration

	R/W	R/W	R/W	R/W	R/W	R	R/W	R/W	Reset Value
	AD2SC4	AD2SC3	AD2SC2	AD2SC1	AD2SC0	-	AMP2GN1	AMP2GN0	11111000
l	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xBC SFR Page: 2

Bits7-3: AD2SC4-0: ADC2 SAR Conversion Clock Period Bits

SAR Conversion clock is derived from system clock by the following equation, where *AD2SC* refers to the 5-bit value held in AD2SC4-0. SAR conversion clock requirements are given in Table 7.2.

$$AD2SC \ge \frac{SYSCLK}{CLK_{SAR2}} - 1 *$$
 or  $CLK_{SAR2} = \frac{SYSCLK}{AD2SC + 1} -$ 

\*Note: AD2SC is the rounded-up result.

Bit2: UNUSED. Read = 0b. Write = don't care.

Bits1-0: AMP2GN1-0: ADC2 Internal Amplifier Gain (PGA)

00: Gain = 0.5 01: Gain = 1 10: Gain = 2 11: Gain = 4



### SFR Definition 7.4. ADC2CN: ADC2 Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
AD2EN	AD2TM	AD2INT	AD2BUSY	AD2CM2	AD2CM1	AD2CM0	AD2WINT	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	•
							CED Addroso:	OvE0

SFR Address: 0xE8 SFR Page: 2

Bit7: AD2EN: ADC2 Enable Bit.

0: ADC2 Disabled. ADC2 is in low-power shutdown.

1: ADC2 Enabled. ADC2 is active and ready for data conversions.

Bit6: AD2TM: ADC2 Track Mode Bit.

0: Normal Track Mode: When ADC2 is enabled, tracking is continuous unless a conversion is in

1: Low-power Track Mode: Tracking defined by AD2CM2-0 bits (see below).

Bit5: AD2INT: ADC2 Conversion Complete Interrupt Flag.

This flag must be cleared by software.

0: ADC2 has not completed a data conversion since the last time this flag was cleared.

1: ADC2 has completed a data conversion.

Bit4: AD2BUSY: ADC2 Busy Bit.

Read

0: ADC2 Conversion is complete or a conversion is not currently in progress. AD2INT is set to logic 1 on the falling edge of AD2BUSY.

1: ADC2 Conversion is in progress.

Write:

0: No Effect.

1: Initiates ADC2 Conversion if AD2CM2-0 = 000b

Bits3-1: AD2CM2-0: ADC2 Start of Conversion Mode Select.

AD2TM = 0:

000: ADC2 conversion initiated on every write of '1' to AD2BUSY.

001: ADC2 conversion initiated on overflow of Timer 3.

010: ADC2 conversion initiated on rising edge of external CNVSTR2 or CNVSTR0.

011: ADC2 conversion initiated on overflow of Timer 2.

1xx: ADC2 conversion initiated on write of '1' to AD0BUSY (synchronized with ADC0 software-commanded conversions).

AD2TM = 1:

000: Tracking initiated on write of '1' to AD2BUSY and lasts 3 SAR2 clocks, followed by conversion

001: Tracking initiated on overflow of Timer 3 and lasts 3 SAR2 clocks, followed by conversion.

010: ADC2 tracks only when CNVSTR2 (or CNVSTR0, See Section 7.2.1) input is logic low; conversion starts on rising CNVSTR2 edge.

011: Tracking initiated on overflow of Timer 2 and lasts 3 SAR2 clocks, followed by conversion. 1xx: Tracking initiated on write of '1' to AD0BUSY and lasts 3 SAR2 clocks, followed by conversion.

Bit0: AD2WINT: ADC2 Window Compare Interrupt Flag.

0: ADC2 window comparison data match has not occurred since this flag was last cleared.

1: ADC2 window comparison data match has occurred. This flag must be cleared in software.

An important note about external convert start (CNVSTR0 and CNVSTR2): If CNVSTR2 is enabled in the digital crossbar (Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204), CNVSTR2 will be the external convert start signal for ADC2. However, if only CNVSTR0 is enabled in the digital crossbar and CNVSTR2 is not enabled, then CNVSTR0 may serve as the start of conversion for both ADC0 and ADC2.



### SFR Definition 7.5. ADC2: ADC2 Data Word

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xBE SFR Page: 2

Bits7-0: ADC2 Data Word.

### 8-bit ADC Data Word appears in the ADC2 Data Word Register as follows:

Example: ADC2 Data Word Conversion Map, AIN1.0 Input (AMX2SL = 0x00)

AIN1.0-AGND (Volts)	ADC2
VREF * (255/256)	0xFF
VREF / 2	0x80
VREF * (127/256)	0x7F
0	0x00

$$Code = Vin \times \frac{Gain}{VREF} \times 256$$


Figure 7.4. ADC2 Data Word Example




### 7.3. ADC2 Programmable Window Detector

The ADC2 Programmable Window Detector continuously compares the ADC2 output to user-programmed limits, and notifies the system when an out-of-bound condition is detected. This is especially effective in an interrupt-driven system, saving code space and CPU bandwidth while delivering faster system response times. The window detector interrupt flag (AD2WINT in ADC2CN) can also be used in polled mode. The reference words are loaded into the ADC2 Greater-Than and ADC2 Less-Than registers (ADC2GT and ADC2LT). Notice that the window detector flag can be asserted when the measured data is inside or outside the user-programmed limits, depending on the programming of the ADC2GT and ADC2LT registers.

### SFR Definition 7.6. ADC2GT: ADC2 Greater-Than Data



### SFR Definition 7.7. ADC2LT: ADC2 Less-Than Data



### 7.3.1. Window Detector in Single-Ended Mode

Figure 7.5 shows two example window comparisons for Single-ended mode, with ADC2LT = 0x20 and ADC2GT = 0x10. In Single-ended mode, the codes vary from 0 to VREF x (255/256) and are represented as 8-bit unsigned integers. In the left example, an AD2WINT interrupt will be generated if the ADC2 conversion word (ADC2) is within the range defined by ADC2GT and ADC2LT (if 0x10 < ADC2 < 0x20). In the right example, and AD2WINT interrupt will be generated if ADC2 is outside of the range defined by ADC2GT and ADC2LT (if ADC2 < 0x10 or ADC2 > 0x20).






Figure 7.5. ADC Window Compare Examples, Single-Ended Mode



### 7.3.2. Window Detector in Differential Mode

Figure 7.6 shows two example window comparisons for differential mode, with ADC2LT = 0x10 (+16d) and ADC2GT = 0xFF (-1d). Notice that in Differential mode, the codes vary from -VREF to VREF x (127/128) and are represented as 8-bit 2s complement signed integers. In the left example, an AD2WINT interrupt will be generated if the ADC2 conversion word (ADC2L) is within the range defined by ADC2GT and ADC2LT (if 0xFF (-1d) < ADC2 < 0x0F (16d)). In the right example, an AD2WINT interrupt will be generated if ADC2 is outside of the range defined by ADC2GT and ADC2LT (if ADC2 < 0xFF (-1d) or ADC2 > 0x10 (+16d)).




Figure 7.6. ADC Window Compare Examples, Differential Mode



### **Table 7.2. ADC2 Electrical Characteristics**

 $V_{DD}$  = 3.0 V, AV+ = 3.0 V,  $V_{REF2}$  = 2.40 V (REFBE = 0), PGA2 = 1, -40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
DC Accuracy		•	•		
Resolution			8		bits
Integral Nonlinearity		_	_	±1	LSB
Differential Nonlinearity	Guaranteed Monotonic	_	_	±1	LSB
Offset Error		_	0.5±0.3	_	LSB
Full Scale Error	Differential mode	_	-1±0.2	_	LSB
Dynamic Performance (10 kHz s	sine-wave input, 0 to 1 dB below	w Full S	cale, 500	ksps)	
Signal-to-Noise Plus Distortion		45	47	_	dB
Total Harmonic Distortion	Up to the 5 <sup>th</sup> harmonic	_	<del>-</del> 51	_	dB
Spurious-Free Dynamic Range		_	52	_	dB
Conversion Rate	'	l			
SAR Conversion Clock Frequency		_	_	6	MHz
Conversion Time in SAR Clocks		8	_	_	clocks
Track/Hold Acquisition Time		300	_	_	ns
Throughput Rate		_	_	500	ksps
Analog Inputs	'	l			
Input Voltage Range	Single-ended	0	_	VREF	V
Common Mode Range		0	_	AV+	V
Input Capacitance		_	5	_	pF
Power Specifications	•	1	ı		
Power Supply Current (AV+ supplied to ADC2)	Operating Mode, 500 ksps	_	420	900	μΑ
Power Supply Rejection		_	±0.3	_	mV/V





# 8. DACs, 12-Bit Voltage Mode (C8051F040/1/2/3 Only)

Each C8051F040/1/2/3 devices include two on-chip 12-bit voltage-mode Digital-to-Analog Converters (DACs). Each DAC has an output swing of 0 V to (VREF – 1 LSB) for a corresponding input code range of 0x000 to 0xFFF. The DACs may be enabled/disabled via their corresponding control registers, DAC0CN and DAC1CN. While disabled, the DAC output is maintained in a high-impedance state, and the DAC supply current falls to 1 μA or less. The voltage reference for each DAC is supplied at the VREFD pin (C8051F040/2 devices) or the VREF pin (C8051F041/3 devices). Note that the VREF pin on C8051F041/3 devices may be driven by the internal voltage reference or an external source. If the internal voltage reference is used it must be enabled in order for the DAC outputs to be valid. See Section "9. Voltage Reference (C8051F040/2/4/6)" on page 113 or Section "10. Voltage Reference (C8051F041/3/5/7)" on page 117 for more information on configuring the voltage reference for the DACs.




Figure 8.1. DAC Functional Block Diagram



### 8.1. DAC Output Scheduling

Each DAC features a flexible output update mechanism which allows for seamless full-scale changes and supports jitter-free updates for waveform generation. The following examples are written in terms of DAC0, but DAC1 operation is identical.

### 8.1.1. Update Output On-Demand

In its default mode (DACOCN.[4:3] = '00') the DACO output is updated "on-demand" on a write to the high-byte of the DACO data register (DACOH). It is important to note that writes to DACOL are held, and have no effect on the DACO output until a write to DACOH takes place. If writing a full 12-bit word to the DAC data registers, the 12-bit data word is written to the low byte (DACOL) and high byte (DACOH) data registers. Data is latched into DACO after a write to the corresponding DACOH register, **so the write sequence should be DACOL followed by DACOH** if the full 12-bit resolution is required. The DAC can be used in 8-bit mode by initializing DACOL to the desired value (typically 0x00), and writing data to only DACOH (also see **Section 8.2** for information on formatting the 12-bit DAC data word within the 16-bit SFR space).

### 8.1.2. Update Output Based on Timer Overflow

Similar to the ADC operation, in which an ADC conversion can be initiated by a timer overflow independently of the processor, the DAC outputs can use a Timer overflow to schedule an output update event. This feature is useful in systems where the DAC is used to generate a waveform of a defined sampling rate by eliminating the effects of variable interrupt latency and instruction execution on the timing of the DAC output. When the DACOMD bits (DACOCN.[4:3]) are set to '01', '10', or '11', writes to both DAC data registers (DACOL and DACOH) are held until an associated Timer overflow event (Timer 3, Timer 4, or Timer 2, respectively) occurs, at which time the DACOH:DACOL contents are copied to the DAC input latches allowing the DAC output to change to the new value.


### 8.2. DAC Output Scaling/Justification

In some instances, input data should be shifted prior to a DAC0 write operation to properly justify data within the DAC input registers. This action would typically require one or more load and shift operations, adding software overhead and slowing DAC throughput. To alleviate this problem, the data-formatting feature provides a means for the user to program the orientation of the DAC0 data word within data registers DAC0H and DAC0L. The three DAC0DF bits (DAC0CN.[2:0]) allow the user to specify one of five data word orientations as shown in the DAC0CN register definition.

DAC1 is functionally the same as DAC0 described above. The electrical specifications for both DAC0 and DAC1 are given in Table 8.1.



### SFR Definition 8.1. DAC0H: DAC0 High Byte



SFR Address: 0xD3 SFR Page: 0

Bits7-0: DAC0 Data Word Most Significant Byte.

# SFR Definition 8.2. DAC0L: DAC0 Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xD2 SFR Page: 0

Bits7-0: DAC0 Data Word Least Significant Byte.



### SFR Definition 8.3. DACOCN: DACO Control

R/W	R	R	R/W	R/W	R/W	R/W	R/W	Reset Value
DAC0EN	-	-	DAC0MD1	DAC0MD0	DAC0DF2	DAC0DF1	DAC0DF0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u>-</u> '

SFR Address: 0xD4 SFR Page: 0

Bit7: DAC0EN: DAC0 Enable Bit.

0: DAC0 Disabled. DAC0 Output pin is disabled; DAC0 is in low-power shutdown mode.

1: DAC0 Enabled. DAC0 Output pin is active; DAC0 is operational.

Bits6-5: UNUSED. Read = 00b; Write = don't care.

Bits4-3: DAC0MD1-0: DAC0 Mode Bits.

00: DAC output updates occur on a write to DAC0H.01: DAC output updates occur on Timer 3 overflow.10: DAC output updates occur on Timer 4 overflow.11: DAC output updates occur on Timer 2 overflow.

Bits2-0: DAC0DF2-0: DAC0 Data Format Bits:

000: The most significant nibble of the DAC0 Data Word is in DAC0H[3:0], while the least significant byte is in DAC0L.

DACOH								DAC0L							
MSB														LSB	

001: The most significant 5-bits of the DAC0 Data Word is in DAC0H[4:0], while the least significant 7-bits are in DAC0L[7:1].

DAC0H							DAC0L						
MSB											LSB		

010: The most significant 6-bits of the DAC0 Data Word is in DAC0H[5:0], while the least significant 6-bits are in DAC0L[7:2].

		-j·													
DAC0H								DAC0L							
MSB												LSB			

011: The most significant 7-bits of the DAC0 Data Word is in DAC0H[6:0], while the least significant 5-bits are in DAC0L[7:3].


DAC0H								DAC0L							
l	MSB											LSB			

1xx: The most significant 8-bits of the DAC0 Data Word is in DAC0H[7:0], while the least significant 4-bits are in DAC0L[7:4].

DAC0H								DACOL							
MSB											LSB				



### SFR Definition 8.4. DAC1H: DAC1 High Byte



SFR Address: 0xD3 SFR Page: 1

Bits7-0: DAC1 Data Word Most Significant Byte.

### SFR Definition 8.5. DAC1L: DAC1 Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	


SFR Address: 0xD2 SFR Page: 1

Bits7-0: DAC1 Data Word Least Significant Byte.



### SFR Definition 8.6. DAC1CN: DAC1 Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value			
DAC1E		-		DAC1MD0		DAC1DF1		00000000			
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0				
							SFR Address: SFR Page:	0XD4			
Bit7:	DAC1EN: D	)ΔC1 Enah	la Rit								
Dittr.				in is disable	d DAC1 is i	in low-pow	er shutdowi	n mode			
				in is active; D			or orrandom				
Bits6-5:			; Write = do								
Bits4-3:	DAC1MD1-										
	00: DAC ou	tput update	es occur on a	a write to DA	C1H.						
				Timer 3 over							
	10: DAC output updates occur on Timer 4 overflow.										
	11: DAC output updates occur on Timer 2 overflow.										
Bits2-0:	DAC1DF2:	DAC1 Data	a Format Bits	S:							
	sigr		ificant nibble e is in DAC1	e of the DAC	1 Data Word	d is in DAC		ile the leas			
		MSB			DACIL LS						
		MISD						LSD			
	sigr	<u>nificant 7-b</u>	its are in DA		Data word	d is in DAC	1H[4:0], wh	ile the leas			
		nificant 7-b			Data Word	DAC1		ile the leas			
					Data Word			LSB			
	010: The	DAC1H ISB       e most sign nificant 6-b	its are in DA	C1L[7:1].		DAC1	L   	LSB			
	010: The	DAC1H ISB	its are in DA	C1L[7:1].		DAC1	L       1H[5:0], wh	LSB			
	010: The	DAC1H ISB       e most sign nificant 6-b	its are in DA	C1L[7:1].		DAC1	L   	LSB			
	010: The sign	PAC1H  E most sign nificant 6-b  DAC1H  E most sign	its are in DA ificant 6-bits its are in DA	of the DAC1	Data Word	DACI	L 1H[5:0], wh L	LSB lile the leas			
	010: The sign MSB   011: The sign	PAC1H  E most sign nificant 6-b  DAC1H  E most sign	ificant 6-bits its are in DA	of the DAC1	Data Word	DACI	L 1H[5:0], wh L LSB 1H[6:0], wh	LSB lile the leas			



significant 4-bits are in DAC1L[7:4].

The most significant 8-bits of the DAC1 Data Word is in DAC1H[7:0], while the least



110 Rev. 1.5

1xx:

### **Table 8.1. DAC Electrical Characteristics**

 $V_{DD}$  = 3.0 V, AV+ = 3.0 V,  $V_{REF}$  = 2.40 V (REFBE = 0), No Output Load unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Static Performance		1	I.		
Resolution			12		bits
Integral Nonlinearity			<u>+2</u>	_	LSB
Differential Nonlinearity		_		±1	LSB
Output Noise	No Output Filter 100 kHz Output Filter 10 kHz Output Filter		250 128 41		μVrms
Offset Error	Data Word = 0x014	_	±3	±30	mV
Offset Tempco			6	_	ppm/°C
Full-Scale Error			±20	±60	mV
Full-Scale Error Tempco		_	10	_	ppm/°C
V <sub>DD</sub> Power Supply Rejection Ratio		_	-60	_	dB
Output Impedance in Shutdown Mode	DACnEN = 0	_	100	_	kΩ
Output Sink Current		_	300	_	μΑ
Output Short-Circuit Current	Data Word = 0xFFF		15	_	mA
Dynamic Performance		•			
Voltage Output Slew Rate	Load = 40 pF		0.44	_	V/µs
Output Settling Time to 1/2 LSB	Load = 40 pF, Output swing from code 0xFFF to 0x014	_	10	_	μs
Output Voltage Swing		0	_	VREF - LSB	V
Startup Time		_	10	_	μs
Analog Outputs					
Load Regulation	I <sub>L</sub> = 0.01 mA to 0.3 mA at code 0xFFF	_	60	_	ppm
Power Consumption (each DA	(C)			ı	
Power Supply Current (AV+ supplied to DAC)	Data Word = 0x7FF	_	110	400	μΑ





### 9. Voltage Reference (C8051F040/2/4/6)

The voltage reference circuit offers full flexibility in operating the ADC and DAC modules. Three voltage reference input pins allow each ADC and the two DACs (C8051F040/2 only) to reference an external voltage reference or the on-chip voltage reference output. ADC0 may also reference the DAC0 output internally, and ADC2 may reference the analog power supply voltage, via the VREF multiplexers shown in Figure 9.1.

The internal voltage reference circuit consists of a 1.2 V, temperature stable bandgap voltage reference generator and a gain-of-two output buffer amplifier. The internal reference may be routed via the VREF pin to external system components or to the voltage reference input pins shown in Figure 9.1. Bypass capacitors of 0.1  $\mu$ F and 4.7  $\mu$ F are recommended from the VREF pin to AGND, as shown in Figure 9.1. See Table 9.1 for voltage reference specifications.

The Reference Control Register, REF0CN (defined in SFR Definition 9.1) enables/disables the internal reference generator and selects the reference inputs for ADC0 and ADC2. The BIASE bit in REF0CN enables the on-board reference generator while the REFBE bit enables the gain-of-two buffer amplifier which drives the VREF pin. When disabled, the supply current drawn by the bandgap and buffer amplifier falls to less than 1 μA (typical) and the output of the buffer amplifier enters a high impedance state. If the internal bandgap is used as the reference voltage generator, BIASE and REFBE must both be set to logic 1. If the internal reference is not used, REFBE may be set to logic 0. Note that the BIASE bit must be set to logic 1 if either DAC or ADC is used, regardless of the voltage reference used. If neither the ADC nor the DAC are being used, both of these bits can be set to logic 0 to conserve power. Bits AD0VRS and AD2VRS select the ADC0 and ADC2 voltage reference sources, respectively. The electrical specifications for the Voltage Reference are given in Table 9.1.

The temperature sensor connects to the highest order input of the ADC0 input multiplexer (see Section "5.1. Analog Multiplexer and PGA" on page 47 for C8051F040 devices, or Section "6.1. Analog Multiplexer and PGA" on page 69 for C8051F042/4/6 devices). The TEMPE bit within REF0CN enables and disables the temperature sensor. While disabled, the temperature sensor defaults to a high impedance state and any A/D measurements performed on the sensor while disabled result in meaningless data.




Figure 9.1. Voltage Reference Functional Block Diagram



### SFR Definition 9.1. REF0CN: Reference Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
-	-	-	AD0VRS	AD2VRS	TEMPE	BIASE	REFBE	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>_</del>

SFR Address: 0xD1 SFR Page: 0

Bits7-5: UNUSED. Read = 000b; Write = don't care. Bit4: AD0VRS: ADC0 Voltage Reference Select

0: ADC0 voltage reference from VREF0 pin.

1: ADC0 voltage reference from DAC0 output (C8051F040/2 only). AD2VRS: ADC2 Voltage Reference Select (C8051F040/2 only).

0: ADC2 voltage reference from VREF2 pin.

1: ADC2 voltage reference from AV+.

Bit2: TEMPE: Temperature Sensor Enable Bit.

Bit3:

0: Internal Temperature Sensor Off.1: Internal Temperature Sensor On.

Bit1: BIASE: ADC/DAC Bias Generator Enable Bit. (Must be '1' if using ADC or DAC).

0: Internal Bias Generator Off.1: Internal Bias Generator On.

Bit0: REFBE: Internal Reference Buffer Enable Bit.

0: Internal Reference Buffer Off.

1: Internal Reference Buffer On. Internal voltage reference is driven on the VREF pin.

# Table 9.1. Voltage Reference Electrical Characteristics $V_{DD}$ = 3.0 V, AV+ = 3.0 V, -40 to +85°C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Internal Reference (REFBE =	1)	1	I		
Output Voltage	25 °C ambient	2.36	2.43	2.48	V
VREF Short-Circuit Current		_	_	30	mA
VREF Temperature Coefficient		_	15	_	ppm/°C
Load Regulation	Load = 0 to 200 µA to AGND	_	0.5	_	ppm/µA
VREF Turn-on Time 1	4.7 μF tantalum, 0.1 μF ceramic bypass	_	2	_	ms
VREF Turn-on Time 2	0.1 μF ceramic bypass	_	20	_	μs
VREF Turn-on Time 3	no bypass cap	_	10	_	μs
Reference Buffer Power Sup- ply Current		_	40	_	μΑ
Power Supply Rejection		_	140	_	ppm/V
External Reference (REFBE =	0)	•			
Input Voltage Range		1.00	_	(AV+) - 0.3	V
Input Current		_	0	1	μA





### 10. Voltage Reference (C8051F041/3/5/7)

The internal voltage reference circuit consists of a 1.2 V, temperature stable bandgap voltage reference generator and a gain-of-two output buffer amplifier. The internal reference may be routed via the VREF pin to external system components or to the VREFA input pin shown in Figure 10.1. Bypass capacitors of 0.1  $\mu$ F and 4.7  $\mu$ F are recommended from the VREF pin to AGND, as shown in Figure 10.1. See Table 10.1 for voltage reference specifications.

The VREFA pin provides a voltage reference input for ADC0 and ADC2 (C8051F041/3 only). ADC0 may also reference the DAC0 output internally (C8051F041/3 only), and ADC2 may reference the analog power supply voltage, via the VREF multiplexers shown in Figure 10.1.

The Reference Control Register, REF0CN (defined in SFR Definition 10.1) enables/disables the internal reference generator and selects the reference inputs for ADC0 and ADC2. The BIASE bit in REF0CN enables the on-board reference generator while the REFBE bit enables the gain-of-two buffer amplifier which drives the VREF pin. When disabled, the supply current drawn by the bandgap and buffer amplifier falls to less than 1  $\mu$ A (typical) and the output of the buffer amplifier enters a high impedance state. If the internal bandgap is used as the reference voltage generator, BIASE and REFBE must both be set to 1 (this includes any time a DAC is used). If the internal reference is not used, REFBE may be set to logic 0. Note that the BIASE bit must be set to logic 1 if either ADC is used, regardless of the voltage reference used. If neither the ADC nor the DAC are being used, both of these bits can be set to logic 0 to conserve power. Bits AD0VRS and AD2VRS select the ADC0 and ADC2 voltage reference sources, respectively. The electrical specifications for the Voltage Reference are given in Table 10.1.

The temperature sensor connects to the highest order input of the ADC0 input multiplexer (see Section "5.1. Analog Multiplexer and PGA" on page 47 for C8051F041 devices that feature a 12-bit ADC, or Section "6.1. Analog Multiplexer and PGA" on page 69 for C8051F043/5/7 devices that feature a 10-bit ADC). The TEMPE bit within REF0CN enables and disables the temperature sensor. While disabled, the temperature sensor defaults to a high impedance state and any A/D measurements performed on the sensor while disabled result in meaningless data.




Figure 10.1. Voltage Reference Functional Block Diagram



### SFR Definition 10.1. REF0CN: Reference Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
-	-	-	AD0VRS	AD1VRS	TEMPE	BIASE	REFBE	00000000
Rit7	Rit6	Rit5	Rit4	Rit3	Rit2	Rit1	Rit∩	_

SFR Address: 0xD1 SFR Page: 0

Bits7-5: UNUSED. Read = 000b; Write = don't care. Bit4: AD0VRS: ADC0 Voltage Reference Select

0: ADC0 voltage reference from VREFA pin.

1: ADC0 voltage reference from DAC0 output (C8051F041/3 only). AD2VRS: ADC2 Voltage Reference Select (C8051F041/3 only).

0: ADC2 voltage reference from VREFA pin.

1: ADC2 voltage reference from AV+.

Bit2: TEMPE: Temperature Sensor Enable Bit.

Bit3:

0: Internal Temperature Sensor Off.1: Internal Temperature Sensor On.

Bit1: BIASE: ADC/DAC Bias Generator Enable Bit. (Must be '1' if using ADC or DAC).

0: Internal Bias Generator Off.1: Internal Bias Generator On.

Bit0: REFBE: Internal Reference Buffer Enable Bit.

0: Internal Reference Buffer Off.

1: Internal Reference Buffer On. Internal voltage reference is driven on the VREF pin.



# Table 10.1. Voltage Reference Electrical Characteristics $V_{DD}$ = 3.0 V, AV+ = 3.0 V, -40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Internal Reference (REFBE =	1)			1	
Output Voltage	25 °C ambient	2.36	2.43	2.48	V
VREF Short-Circuit Current		_	_	30	mA
VREF Temperature Coefficient		_	15	_	ppm/°C
Load Regulation	Load = 0 to 200 µA to AGND	_	0.5	_	ppm/µA
VREF Turn-on Time 1	4.7 μF tantalum, 0.1 μF ceramic bypass	_	2	_	ms
VREF Turn-on Time 2	0.1 μF ceramic bypass	_	20	_	μs
VREF Turn-on Time 3	no bypass cap	_	10	_	μs
Reference Buffer Power Sup- ply Current		_	40	_	μA
Power Supply Rejection		_	140	_	ppm/V
External Reference (REFBE =	0)			1	
Input Voltage Range		1.00	_	(AV+) - 0.3	V
Input Current		_	0	1	μΑ





### 11. Comparators

C8051F04x family of devices include three on-chip programmable voltage comparators, shown in Figure 11.1. Each comparator offers programmable response time and hysteresis. When assigned to a Port pin, the Comparator output may be configured as open drain or push-pull, and Comparator inputs should be configured as analog inputs (see Section "17.1.5. Configuring Port 1, 2, and 3 Pins as Analog Inputs" on page 207). The Comparator may also be used as a reset source (see Section "13.5. Comparator Reset" on page 167).

The output of a Comparator can be polled by software, used as an interrupt source, used as a reset source, and/or routed to a Port pin. Each comparator can be individually enabled and disabled (shutdown). When disabled, the Comparator output (if assigned to a Port I/O pin via the Crossbar) defaults to the logic low state, and its supply current falls to less than 1  $\mu$ A. See **Section "17.1.1. Crossbar Pin Assignment and Allocation" on page 205** for details on configuring the Comparator output via the digital Crossbar. The Comparator inputs can be externally driven from -0.25 V to ( $V_{DD}$ ) + 0.25 V without damage or upset. The complete electrical specifications for the Comparator are given in Table 11.1.

The Comparator response time may be configured in software using the CPnMD1-0 bits in register CPT-nMD (see SFR Definition 11.2). Selecting a longer response time reduces the amount of power consumed by the comparator. See Table 11.1 for complete timing and current consumption specifications.




Figure 11.1. Comparator Functional Block Diagram






Figure 11.2. Comparator Hysteresis Plot

The hysteresis of the Comparator is software-programmable via its Comparator Control register (CPT-nCN). The user can program both the amount of hysteresis voltage (referred to the input voltage) and the positive and negative-going symmetry of this hysteresis around the threshold voltage.

The Comparator hysteresis is programmed using Bits3-0 in the Comparator Control Register CPTnCN (shown in SFR Definition 11.1). The amount of negative hysteresis voltage is determined by the settings of the CPnHYN bits. As shown in Table 11.1, settings of approximately 20, 10 or 5 mV of negative hysteresis can be programmed, or negative hysteresis can be disabled. In a similar way, the amount of positive hysteresis is determined by the setting the CPnHYP bits.

Comparator interrupts can be generated on either rising-edge and falling-edge output transitions. (For Interrupt enable and priority control, see Section "12.3. Interrupt Handler" on page 153). The rising and/ or falling -edge interrupts are enabled using the comparator's Rising/Falling Edge Interrupt Enable Bits (CPnRIE and CPnFIE) in their respective Comparator Mode Selection Register (CPTnMD), shown in SFR Definition 11.2. These bits allow the user to control which edge (or both) will cause a comparator interrupt. However, the comparator interrupt must also be enabled in the Extended Interrupt Enable Register (EIE1). The CPnFIF flag is set to logic 1 upon a Comparator falling-edge interrupt, and the CPnRIF flag is set to logic 1 upon the Comparator rising-edge interrupt. Once set, these bits remain set until cleared by software. The output state of a Comparator can be obtained at any time by reading the CPnOUT bit. A Comparator is enabled by setting its respective CPnEN bit to logic 1, and is disabled by clearing this bit to logic 0. Upon enabling a comparator, the output of the comparator is not immediately valid. Before using a comparator as an interrupt or reset source, software should wait for a minimum of the specified "Power-up time" as specified in Table 11.1, "Comparator Electrical Characteristics," on page 126.



### 11.1. Comparator Inputs

The Port pins selected as comparator inputs should be configured as analog inputs in the Port 2 Input Configuration Register (for details on Port configuration, see **Section "17.1.3. Configuring Port Pins as Digital Inputs" on page 206**). The inputs for Comparator are on Port 2 as follows:

Comparator Input	Port PIN
CP0+	P2.6
CP0-	P2.7
CP1+	P2.2
CP1-	P2.3
CP2+	P2.4
CP2-	P2.5



### SFR Definition 11.1. CPTnCN: Comparator 0, 1, and 2 Control

	R/W	R	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
	CPnEN	CPnOUT	CPnRIF	CPnFIF	CPnHYP1	CPnHYP0	CPnHYN1	CPnHYN0	00000000
•	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: CPT0CN: 0x88; CPT1CN: 0x88; CPT2CN: 0x88 SFR Pages: CPT0CN:page 1; CPT1CN:page 2; CPT2CN:page 3

Bit7: CPnEN: Comparator Enable Bit. (Please see note below.)

0: Comparator Disabled.

1: Comparator Enabled.

Bit6: CPnOUT: Comparator Output State Flag.

0: Voltage on CPn+ < CPn-.</li>1: Voltage on CPn+ > CPn-.

Bit5: CPnRIF: Comparator Rising-Edge Interrupt Flag.

0: No Comparator Rising Edge Interrupt has occurred since this flag was last cleared.

1: Comparator Rising Edge Interrupt has occurred. Must be cleared by software.

Bit4: CPnFIF: Comparator Falling-Edge Interrupt Flag.

0: No Comparator Falling-Edge Interrupt has occurred since this flag was last cleared.

1: Comparator Falling-Edge Interrupt has occurred. Must be cleared by software.

Bits3-2: CPnHYP1-0: Comparator Positive Hysteresis Control Bits.

00: Positive Hysteresis Disabled.

01: Positive Hysteresis = 5 mV.

10: Positive Hysteresis = 10 mV.

11: Positive Hysteresis = 20 mV.

Bits1-0: CPnHYN1-0: Comparator Negative Hysteresis Control Bits.

00: Negative Hysteresis Disabled.

01: Negative Hysteresis = 5 mV.

10: Negative Hysteresis = 10 mV.

11: Negative Hysteresis = 20 mV.

NOTE: Upon enabling a comparator, the output of the comparator is not immediately valid. Before using a comparator as an interrupt or reset source, software should wait for a minimum of the specified "Power-up time" as specified in Table 11.1, "Comparator Electrical Characteristics." on page 126.



### SFR Definition 11.2. CPTnMD: Comparator Mode Selection

R/W	R/W	R/W	R/W	R	R	R/W	R/W	Reset Value
-	-	CPnRIE	CPnFIE	-	-	CPnMD1	CPnMD0	00000010
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u>-</u>

SFR Address: CPT0MD: 0x89; CPT1MD: 0x89; CPT2MD: 0x89 SFR Page: CPT0MD:page 1; CPT1MD:page 2; CPT2MD:page 3

Bits7-6: UNUSED. Read = 00b, Write = don't care.

Bit 5: CPnRIE: Comparator Rising-Edge Interrupt Enable Bit.

0: Comparator rising-edge interrupt disabled.1: Comparator rising-edge interrupt enabled.

Bit 4: CPnFIE: Comparator Falling-Edge Interrupt Enable Bit.

0: Comparator falling-edge interrupt disabled.

1: Comparator falling-edge interrupt enabled. Bits3-2: UNUSED. Read = 00b, Write = don't care.

Bits1-0: CPnMD1-CPnMD0: Comparator Mode Select

These bits select the response time for the Comparator.

Mode	CPnMD1	CPnMD0	CPn Typical Response Time
0	0	0	Fastest Response Time
1	0	1	_
2	1	0	_
3	1	1	Lowest Power Consumption



**Table 11.1. Comparator Electrical Characteristics** 

 $V_{DD} = 3.0 \text{ V}, -40 \text{ to } +85 ^{\circ}\text{C}$  unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Response Time,	CPn+ - CPn- = 100 mV	_	100	_	ns
Mode 0	CPn+ - CPn- = 10 mV	_	250	_	ns
Response Time,	CPn+ - CPn- = 100 mV	_	175	_	ns
Mode 1	CPn+ - CPn- = 10 mV	_	500	_	ns
Response Time,	CPn+ - CPn- = 100 mV	_	320	_	ns
Mode 2	CPn+ - CPn- = 10 mV	_	1100	_	ns
Response Time,	CPn+ - CPn- = 100 mV	_	1050	_	ns
Mode 3	CPn+ - CPn- = 10 mV	_	5200	_	ns
Common-Mode Rejection Ratio		_	1.5	4	mV/V
Positive Hysteresis 1	CPnHYP1-0 = 00	_	0	1	mV
Positive Hysteresis 2	CPnHYP1-0 = 01	2	4.5	7	mV
Positive Hysteresis 3	CPnHYP1-0 = 10	4	9	13	mV
Positive Hysteresis 4	CPnHYP1-0 = 11	10	17	25	mV
Negative Hysteresis 1	CPnHYN1-0 = 00		0	1	mV
Negative Hysteresis 2	CPnHYN1-0 = 01	2	4.5	7	mV
Negative Hysteresis 3	CPnHYN1-0 = 10	4	9	13	mV
Negative Hysteresis 4	CPnHYN1-0 = 11	10	17	25	mV
Inverting or Non-Inverting Input Voltage Range		-0.25		V <sub>DD</sub> + 0.25	V
Input Capacitance		_	7	_	pF
Input Bias Current		-5	0.001	+5	nA
Input Offset Voltage		-5		+5	mV
Power Supply		•	•		
Power Supply Rejection		_	0.1	1	mV/V
Power-up Time		_	10	_	μs
	Mode 0	_	7.6	_	μΑ
Supply Current at DC	Mode 1	_	3.2	_	μΑ
Supply Sulfell at DO	Mode 2	_	1.3	_	μΑ
	Mode 3		0.4	_	μΑ



### 12. CIP-51 Microcontroller

The MCU system controller core is the CIP-51 microcontroller. The CIP-51 is fully compatible with the MCS-51™ instruction set; standard 803x/805x assemblers and compilers can be used to develop software. The MCU family has a superset of all the peripherals included with a standard 8051. Included are five 16-bit counter/timers (see description in **Section 23**), two full-duplex UARTs (see description in **Section 21** and **Section 22**), 256 bytes of internal RAM, 128 byte Special Function Register (SFR) address space (see **Section 12.2.6**), and 8/4 byte-wide I/O Ports (see description in **Section 17**). The CIP-51 also includes on-chip debug hardware (see description in **Section 25**), and interfaces directly with the MCUs' analog and digital subsystems providing a complete data acquisition or control-system solution in a single integrated circuit.

The CIP-51 Microcontroller core implements the standard 8051 organization and peripherals as well as additional custom peripherals and functions to extend its capability (see Figure 12.1 for a block diagram). The CIP-51 includes the following features:

- Fully Compatible with MCS-51 Instruction Set
- 25 MIPS Peak Throughput with 25 MHz Clock
- 0 to 25 MHz Clock Frequency
- 256 Bytes of Internal RAM
- 8/4 Byte-Wide I/O Ports

- Extended Interrupt Handler
- Reset Input
- Power Management Modes
- On-chip Debug Logic
- Program and Data Memory Security




Figure 12.1. CIP-51 Block Diagram



#### **Performance**

The CIP-51 employs a pipelined architecture that greatly increases its instruction throughput over the standard 8051 architecture. In a standard 8051, all instructions except for MUL and DIV take 12 or 24 system clock cycles to execute, and usually have a maximum system clock of 12 MHz. By contrast, the CIP-51 core executes 70% of its instructions in one or two system clock cycles, with no instructions taking more than eight system clock cycles.

With the CIP-51's maximum system clock at 25 MHz, it has a peak throughput of 25 MIPS. The CIP-51 has a total of 109 instructions. The table below shows the total number of instructions that require each execution time.

Clocks to Execute	1	2	2/3	3	3/4	4	4/5	5	8
Number of Instructions	26	50	5	14	7	3	1	2	1

#### **Programming and Debugging Support**

A JTAG-based serial interface is provided for in-system programming of the Flash program memory and communication with on-chip debug support logic. The re-programmable Flash can also be read and changed a single byte at a time by the application software using the MOVC and MOVX instructions. This feature allows program memory to be used for non-volatile data storage as well as updating program code under software control.

The on-chip debug support logic facilitates full speed in-circuit debugging, allowing the setting of hardware breakpoints and watch points, starting, stopping and single stepping through program execution (including interrupt service routines), examination of the program's call stack, and reading/writing the contents of registers and memory. This method of on-chip debug is completely non-intrusive and non-invasive, requiring no RAM, Stack, timers, or other on-chip resources.

The CIP-51 is supported by development tools from Silicon Labs and third party vendors. Silicon Labs provides an integrated development environment (IDE) including editor, macro assembler, debugger and programmer. The IDE's debugger and programmer interface to the CIP-51 via its JTAG interface to provide fast and efficient in-system device programming and debugging. Third party macro assemblers and C compilers are also available.



### 12.1. Instruction Set

The instruction set of the CIP-51 System Controller is fully compatible with the standard MCS-51™ instruction set; standard 8051 development tools can be used to develop software for the CIP-51. All CIP-51 instructions are the binary and functional equivalent of their MCS-51™ counterparts, including opcodes, addressing modes and effect on PSW flags. However, instruction timing is different than that of the standard 8051.

#### 12.1.1. Instruction and CPU Timing

In many 8051 implementations, a distinction is made between machine cycles and clock cycles, with machine cycles varying from 2 to 12 clock cycles in length. However, the CIP-51 implementation is based solely on clock cycle timing. All instruction timings are specified in terms of clock cycles.

Due to the pipelined architecture of the CIP-51, most instructions execute in the same number of clock cycles as there are program bytes in the instruction. Conditional branch instructions take one less clock cycle to complete when the branch is not taken as opposed to when the branch is taken. Table 12.1 is the CIP-51 Instruction Set Summary, which includes the mnemonic, number of bytes, and number of clock cycles for each instruction.

#### 12.1.2. MOVX Instruction and Program Memory

In the CIP-51, the MOVX instruction serves three purposes: accessing on-chip XRAM, accessing off-chip XRAM, and accessing on-chip program Flash memory. The Flash access feature provides a mechanism for user software to update program code and use the program memory space for non-volatile data storage (see Section "15. Flash Memory" on page 179). The External Memory Interface provides a fast access to off-chip XRAM (or memory-mapped peripherals) via the MOVX instruction. Refer to Section "16. External Data Memory Interface and On-Chip XRAM" on page 187 for details.

Table 12.1. CIP-51 Instruction Set Summary

Mnemonic	Description	Bytes	Clock Cycles
	Arithmetic Operations		•
ADD A, Rn	Add register to A	1	1
ADD A, direct	Add direct byte to A	2	2
ADD A, @Ri	Add indirect RAM to A	1	2
ADD A, #data	Add immediate to A	2	2
ADDC A, Rn	Add register to A with carry	1	1
ADDC A, direct	Add direct byte to A with carry	2	2
ADDC A, @Ri	Add indirect RAM to A with carry	1	2
ADDC A, #data	Add immediate to A with carry	2	2
SUBB A, Rn	Subtract register from A with borrow	1	1
SUBB A, direct	Subtract direct byte from A with borrow	2	2
SUBB A, @Ri	Subtract indirect RAM from A with borrow	1	2
SUBB A, #data	Subtract immediate from A with borrow	2	2
INC A	Increment A	1	1
INC Rn	Increment register	1	1
INC direct	Increment direct byte	2	2
INC @Ri	Increment indirect RAM	1	2
DEC A	Decrement A	1	1



Table 12.1. CIP-51 Instruction Set Summary (Continued)

Mnemonic	Description	Bytes	Clock Cycles
DEC Rn	Decrement register	1	1
DEC direct	Decrement direct byte	2	2
DEC @Ri	Decrement indirect RAM	1	2
INC DPTR	Increment Data Pointer	1	1
MUL AB	Multiply A and B	1	4
DIV AB	Divide A by B	1	8
DA A	Decimal adjust A	1	1
	Logical Operations	1	II.
ANL A, Rn	AND Register to A	1	1
ANL A, direct	AND direct byte to A	2	2
ANL A, @Ri	AND indirect RAM to A	1	2
ANL A, #data	AND immediate to A	2	2
ANL direct, A	AND A to direct byte	2	2
ANL direct, #data	AND immediate to direct byte	3	3
ORL A, Rn	OR Register to A	1	1
ORL A, direct	OR direct byte to A	2	2
ORL A, @Ri	OR indirect RAM to A	1	2
ORL A, #data	OR immediate to A	2	2
ORL direct, A	OR A to direct byte	2	2
ORL direct, #data	OR immediate to direct byte	3	3
XRL A, Rn	Exclusive-OR Register to A	1	1
XRL A, direct	Exclusive-OR direct byte to A	2	2
XRL A, @Ri	Exclusive-OR indirect RAM to A	1	2
XRL A, #data	Exclusive-OR immediate to A	2	2
XRL direct, A	Exclusive-OR A to direct byte	2	2
XRL direct, #data	Exclusive-OR immediate to direct byte	3	3
CLR A	Clear A	1	1
CPL A	Complement A	1	1
RL A	Rotate A left	1	1
RLC A	Rotate A left through Carry	1	1
RR A	Rotate A right	1	1
RRC A	Rotate A right through Carry	1	1
SWAP A	Swap nibbles of A	1	1
	Data Transfer		
MOV A, Rn	Move Register to A	1	1
MOV A, direct	Move direct byte to A	2	2
MOV A, @Ri	Move indirect RAM to A	1	2
MOV A, #data	Move immediate to A	2	2
MOV Rn, A	Move A to Register	1	1
MOV Rn, direct	Move direct byte to Register	2	2
MOV Rn, #data	Move immediate to Register	2	2
MOV direct, A	Move A to direct byte	2	2
MOV direct, Rn	Move Register to direct byte	2	2
MOV direct, direct	Move direct byte to direct byte	3	3
MOV direct, @Ri	Move indirect RAM to direct byte	2	2



Table 12.1. CIP-51 Instruction Set Summary (Continued)

Description	Bytes	Clock Cycles
Move immediate to direct byte	3	3
Move A to indirect RAM	1	2
Move direct byte to indirect RAM	2	2
Move immediate to indirect RAM	2	2
Load DPTR with 16-bit constant	3	3
Move code byte relative DPTR to A	1	3
Move code byte relative PC to A	1	3
Move external data (8-bit address) to A	1	3
Move A to external data (8-bit address)	1	3
Move external data (16-bit address) to A	1	3
Move A to external data (16-bit address)	1	3
Push direct byte onto stack	2	2
Pop direct byte from stack	2	2
Exchange Register with A	1	1
Exchange direct byte with A	2	2
Exchange indirect RAM with A	1	2
Exchange low nibble of indirect RAM with A	1	2
Boolean Manipulation		
Clear Carry	1	1
Clear direct bit	2	2
Set Carry	1	1
Set direct bit	2	2
Complement Carry	1	1
	2	2
	2	2
	2	2
·	2	2
	2	2
·	2	2
•	2	2
		2/3
	2	2/3
	3	3/4
		3/4
	3	3/4
	<u> </u>	1
	2	3
	3	4
=		5
		5
·		3
, .		4
		3
		3
Jump if A equals zero	2	2/3
	Move immediate to direct byte  Move A to indirect RAM  Move direct byte to indirect RAM  Move immediate to indirect RAM  Load DPTR with 16-bit constant  Move code byte relative DPTR to A  Move external data (8-bit address) to A  Move A to external data (8-bit address) to A  Move A to external data (16-bit address)  Move A to external data (16-bit address)  Push direct byte onto stack  Pop direct byte from stack  Exchange Register with A  Exchange indirect RAM with A  Exchange low nibble of indirect RAM with A  Boolean Manipulation  Clear Carry  Clear direct bit  Set Carry  Set direct bit  Complement Carry  Complement Carry  AND complement of direct bit to Carry  OR direct bit to Carry  Move direct bit to Carry  Move direct bit to Carry  Move Carry to direct bit  Jump if Carry is set  Jump if direct bit is set  Jump if direct bit is set  Jump if direct bit is set and clear bit  Program Branching  Absolute subroutine call  Long sump  Short jump (relative address)  Jump indirect relative to DPTR	Move immediate to direct byte  Move A to indirect RAM  Move direct byte to indirect RAM  Move immediate to indirect RAM  Load DPTR with 16-bit constant  Move code byte relative DPTR to A  Move external data (8-bit address) to A  Move external data (8-bit address) to A  Move external data (16-bit address) to A  Move external data (16-bit address) to A  Move A to external data (16-bit address) to A  Move A to external data (16-bit address) to A  Move A to external data (16-bit address) to A  Move A to external data (16-bit address) to A  Move A to external data (16-bit address) to A  Move A to external data (16-bit address) to A  Exchange direct byte onto stack  Pop direct byte from stack  Exchange Register with A  Exchange low nibble of indirect RAM with A  Exchange low nibble of indirect RAM with A  Boolean Manipulation  Clear Carry  Clear direct bit  Set direct bit  Complement Carry  Complement Carry  Complement direct bit  AND direct bit to Carry  AND complement of direct bit to Carry  OR direct bit to carry  OR complement of direct bit to Carry  OR complement of direct bit to Carry  Move direct bit to Carry  Move direct bit to Carry  Move Carry to direct bit  Jump if Carry is not set  Jump if direct bit is set and clear bit  Program Branching  Absolute subroutine call  Long subroutine call  Return from subroutine  Return from interrupt  Absolute jump  Short jump (relative address)  Jump indirect relative to DPTR



Table 12.1. CIP-51 Instruction Set Summary (Continued)

Mnemonic	Description	Bytes	Clock Cycles
JNZ rel	Jump if A does not equal zero	2	2/3
CJNE A, direct, rel	Compare direct byte to A and jump if not equal	3	3/4
CJNE A, #data, rel	Compare immediate to A and jump if not equal	3	3/4
CJNE Rn, #data, rel	Compare immediate to Register and jump if not equal	3	3/4
CJNE @Ri, #data, rel	Compare immediate to indirect and jump if not equal	3	4/5
DJNZ Rn, rel	Decrement Register and jump if not zero	2	2/3
DJNZ direct, rel	Decrement direct byte and jump if not zero	3	3/4
NOP	No operation	1	1

#### Notes on Registers, Operands and Addressing Modes:

Rn - Register R0-R7 of the currently selected register bank.

@Ri - Data RAM location addressed indirectly through R0 or R1.

**rel** - 8-bit, signed (two's complement) offset relative to the first byte of the following instruction. Used by SJMP and all conditional jumps.

**direct** - 8-bit internal data location's address. This could be a direct-access Data RAM location (0x00-0x7F) or an SFR (0x80-0xFF).

#data - 8-bit constant

#data16 - 16-bit constant

bit - Direct-accessed bit in Data RAM or SFR

**addr11** - 11-bit destination address used by ACALL and AJMP. The destination must be within the same 2K-byte page of program memory as the first byte of the following instruction.

**addr16** - 16-bit destination address used by LCALL and LJMP. The destination may be anywhere within the 64 kB program memory space.

There is one unused opcode (0xA5) that performs the same function as NOP. All mnemonics copyrighted © Intel Corporation 1980.



### 12.2. Memory Organization

The memory organization of the CIP-51 System Controller is similar to that of a standard 8051. There are two separate memory spaces: program memory and data memory. Program and data memory share the same address space but are accessed via different instruction types. There are 256 bytes of internal data memory and 64k bytes of internal program memory address space implemented within the CIP-51. The CIP-51 memory organization is shown in Figure 12.2.




Figure 12.2. Memory Map

#### 12.2.1. Program Memory

The CIP-51 has a 64 kB program memory space. The MCU implements 64 kB (C8051F040/1/2/3/4/5) and 32 kB (C8051F046/7) of this program memory space as in-system re-programmed Flash memory, organized in a contiguous block from addresses 0x0000 to 0xFFFF (C8051F040/1/2/3/4/5) and 0x0000 to 0x7FFF (C8051F046/7). Note: 512 bytes from 0xFE00 to 0xFFFF (C8051F040/1/2/3/4/5 only) of this memory are reserved for factory use and are not available for user program storage.

Program memory is normally assumed to be read-only. However, the CIP-51 can write to program memory by setting the Program Store Write Enable bit (PSCTL.0) and using the MOVX instruction. This feature provides a mechanism for the CIP-51 to update program code and use the program memory space for non-volatile data storage. Refer to **Section "15. Flash Memory" on page 179** for further details.



### 12.2.2. Data Memory

The CIP-51 implements 256 bytes of internal RAM mapped into the data memory space from 0x00 through 0xFF. The lower 128 bytes of data memory are used for general purpose registers and scratch pad memory. Either direct or indirect addressing may be used to access the lower 128 bytes of data memory. Locations 0x00 through 0x1F are addressable as four banks of general purpose registers, each bank consisting of eight byte-wide registers. The next 16 bytes, locations 0x20 through 0x2F, may either be addressed as bytes or as 128 bit locations accessible with the direct addressing mode.

The upper 128 bytes of data memory are accessible only by indirect addressing. This region occupies the same address space as the Special Function Registers (SFR) but is physically separate from the SFR space. The addressing mode used by an instruction when accessing locations above 0x7F determines whether the CPU accesses the upper 128 bytes of data memory space or the SFR's. Instructions that use direct addressing will access the SFR space. Instructions using indirect addressing above 0x7F access the upper 128 bytes of data memory. Figure 12.2 illustrates the data memory organization of the CIP-51.

### 12.2.3. General Purpose Registers

The lower 32 bytes of data memory, locations 0x00 through 0x1F, may be addressed as four banks of general-purpose registers. Each bank consists of eight byte-wide registers designated R0 through R7. Only one of these banks may be enabled at a time. Two bits in the program status word, RS0 (PSW.3) and RS1 (PSW.4), select the active register bank (see description of the PSW in SFR Definition 12.8). This allows fast context switching when entering subroutines and interrupt service routines. Indirect addressing modes use registers R0 and R1 as index registers.

#### 12.2.4. Bit Addressable Locations

In addition to direct access to data memory organized as bytes, the sixteen data memory locations at 0x20 through 0x2F are also accessible as 128 individually addressable bits. Each bit has a bit address from 0x00 to 0x7F. Bit 0 of the byte at 0x20 has bit address 0x00 while bit 7 of the byte at 0x20 has bit address 0x07. Bit 7 of the byte at 0x2F has bit address 0x7F. A bit access is distinguished from a full byte access by the type of instruction used (bit source or destination operands as opposed to a byte source or destination).

The MCS-51<sup>™</sup> assembly language allows an alternate notation for bit addressing of the form XX.B where XX is the byte address and B is the bit position within the byte. For example, the instruction:

MOV C, 22.3h

moves the Boolean value at 0x13 (bit 3 of the byte at location 0x22) into the Carry flag.

#### 12.2.5. Stack

A programmer's stack can be located anywhere in the 256 byte data memory. The stack area is designated using the Stack Pointer (SP, address 0x81) SFR. The SP will point to the last location used. The next value pushed on the stack is placed at SP+1 and then SP is incremented. A reset initializes the stack pointer to location 0x07; the first value pushed on the stack is placed at location 0x08, which is also the first register (R0) of register bank 1. Thus, if more than one register bank is to be used, the SP should be initialized to a location in the data memory not being used for data storage. The stack depth can extend up to 256 bytes.

The MCUs also have built-in hardware for a stack record which is accessed by the debug logic. The stack record is a 32-bit shift register, where each PUSH or increment SP pushes one record bit onto the register, and each CALL pushes two record bits onto the register. (A POP or decrement SP pops one record bit,

and a RET pops two record bits, also.) The stack record circuitry can also detect an overflow or underflow on the 32-bit shift register, and can notify the debug software even with the MCU running at speed.

#### 12.2.6. Special Function Registers

The direct-access data memory locations from 0x80 to 0xFF constitute the special function registers (SFR's). The SFR's provide control and data exchange with the CIP-51's resources and peripherals. The CIP-51 duplicates the SFR's found in a typical 8051 implementation as well as implementing additional SFR's used to configure and access the sub-systems unique to the MCU. This allows the addition of new functionality while retaining compatibility with the MCS-51™ instruction set. Table 12.2 lists the SFR's implemented in the CIP-51 System Controller.

The SFR registers are accessed whenever the direct addressing mode is used to access memory locations from 0x80 to 0xFF. SFR's with addresses ending in 0x0 or 0x8 (e.g. P0, TCON, P1, SCON, IE, etc.) are bit-addressable as well as byte-addressable. All other SFR's are byte-addressable only. Unoccupied addresses in the SFR space are reserved for future use. Accessing these areas will have an indeterminate effect and should be avoided. Refer to the corresponding pages of the datasheet, as indicated in Table 12.3, for a detailed description of each register.

#### 12.2.6.1. SFR Paging

The CIP-51 features *SFR paging*, allowing the device to map many SFR's into the 0x80 to 0xFF memory address space. The SFR memory space has 256 *pages*. In this way, each memory location from 0x80 to 0xFF can access up to 256 SFR's. The C8051F04x family of devices utilizes five SFR pages: 0, 1, 2, 3, and F. SFR pages are selected using the Special Function Register Page Selection register, SFRPAGE (see SFR Definition 12.2). The procedure for reading and writing an SFR is as follows:

- 1. Select the appropriate SFR page number using the SFRPAGE register.
- 2. Use direct accessing mode to read or write the special function register (MOV instruction).

#### 12.2.6.2. Interrupts and SFR Paging

When an interrupt occurs, the SFR Page Register will automatically switch to the SFR page containing the flag bit that caused the interrupt. The automatic SFR Page switch function conveniently removes the burden of switching SFR pages from the interrupt service routine. Upon execution of the RETI instruction, the SFR page is automatically restored to the SFR Page in use prior to the interrupt. This is accomplished via a three-byte SFR Page Stack. The top byte of the stack is SFRPAGE, the current SFR Page. The second byte of the SFR Page Stack is SFRNEXT. The third, or bottom byte of the SFR Page Stack is SFRLAST. On interrupt, the current SFRPAGE value is pushed to the SFRNEXT byte, and the value of SFRNEXT is pushed to SFRLAST. Hardware then loads SFRPAGE with the SFR Page containing the flag bit associated with the interrupt. On a return from interrupt, the SFR Page Stack is popped resulting in the value of SFRNEXT returning to the SFRPAGE register, thereby restoring the SFR page context without software intervention. The value in SFRLAST (0x00 if there is no SFR Page value in the bottom of the stack) of the stack is placed in SFRNEXT register. If desired, the values stored in SFRNEXT and SFRLAST may be modified during an interrupt, enabling the CPU to return to a different SFR Page upon execution of the RETI instruction (on interrupt exit). Modifying registers in the SFR Page Stack does not cause a push or pop of the stack. Only interrupt calls and returns will cause push/pop operations on the SFR Page Stack.






Figure 12.3. SFR Page Stack

Automatic hardware switching of the SFR Page on interrupts may be enabled or disabled as desired using the SFR Automatic Page Control Enable Bit located in the SFR Page Control Register (SFRPGCN). This function defaults to 'enabled' upon reset. In this way, the autoswitching function will be enabled unless disabled in software.

A summary of the SFR locations (address and SFR page) is provided in Table 12.2. in the form of an SFR memory map. Each memory location in the map has an SFR page row, denoting the page in which that SFR resides. Note that certain SFR's are accessible from ALL SFR pages, and are denoted by the "(ALL PAGES)" designation. For example, the Port I/O registers P0, P1, P2, and P3 all have the "(ALL PAGES)" designation, indicating these SFR's are accessible from all SFR pages regardless of the SFRPAGE register value.

#### 12.2.6.3. SFR Page Stack Example

The following is an example of a C8051F040 device that shows the operation of the SFR Page Stack during interrupts.

In this example, the SFR Page Control is left in the default enabled state (i.e., SFRPGEN = 1), and the CIP-51 is executing in-line code that is writing values to Port 5 (SFR "P5", located at address 0xD8 on SFR Page 0x0F). The device is also using the Programmable Counter Array (PCA) and the 8-bit ADC (ADC2) window comparator to monitor a voltage. The PCA is timing a critical control function in its interrupt service routine (ISR), so its interrupt is enabled and is set to *high* priority. The ADC2 is monitoring a voltage that is less important, but to minimize the software overhead its window comparator is being used with an associated ISR that is set to *low* priority. At this point, the SFR page is set to access the Port 5 SFR (SFRPAGE = 0x0F). See Figure 12.4 below.






Figure 12.4. SFR Page Stack While Using SFR Page 0x0F To Access Port 5

While CIP-51 executes in-line code (writing values to Port 5 in this example), an ADC2 Window Comparator Interrupt occurs. The CIP-51 vectors to the ADC2 Window Comparator ISR and pushes the current SFR Page value (SFR Page 0x0F) into SFRNEXT in the SFR Page Stack. The SFR page needed to access ADC2's SFR's is then automatically placed in the SFRPAGE register (SFR Page 0x02). SFRPAGE is considered the "top" of the SFR Page Stack. Software can now access the ADC2 SFR's. Software may switch to any SFR Page by writing a new value to the SFRPAGE register at any time during the ADC2 ISR to access SFR's that are not on SFR Page 0x02. See Figure 12.5.






Figure 12.5. SFR Page Stack After ADC2 Window Comparator Interrupt Occurs

While in the ADC2 ISR, a PCA interrupt occurs. Recall the PCA interrupt is configured as a *high* priority interrupt, while the ADC2 interrupt is configured as a *low* priority interrupt. Thus, the CIP-51 will now vector to the high priority PCA ISR. Upon doing so, the CIP-51 will automatically place the SFR page needed to access the PCA's special function registers into the SFRPAGE register, SFR Page 0x00. The value that was in the SFRPAGE register before the PCA interrupt (SFR Page 2 for ADC2) is pushed down the stack into SFRNEXT. Likewise, the value that was in the SFRNEXT register before the PCA interrupt (in this case SFR Page 0x0F for Port 5) is pushed down to the SFRLAST register, the "bottom" of the stack. Note that a value stored in SFRLAST (via a previous software write to the SFRLAST register) will be overwritten. See Figure 12.6 below.






Figure 12.6. SFR Page Stack Upon PCA Interrupt Occurring During an ADC2 ISR

On exit from the PCA interrupt service routine, the CIP-51 will return to the ADC2 Window Comparator ISR. On execution of the RETI instruction, SFR Page 0x00 used to access the PCA registers will be automatically popped off of the SFR Page Stack, and the contents of the SFRNEXT register will be moved to the SFRPAGE register. Software in the ADC2 ISR can continue to access SFR's as it did prior to the PCA interrupt. Likewise, the contents of SFRLAST are moved to the SFRNEXT register. Recall this was the SFR Page value 0x0F being used to access Port 5 before the ADC2 interrupt occurred. See Figure 12.7 below.






Figure 12.7. SFR Page Stack Upon Return From PCA Interrupt

On the execution of the RETI instruction in the ADC2 Window Comparator ISR, the value in SFRPAGE register is overwritten with the contents of SFRNEXT. The CIP-51 may now access the Port 5 SFR bits as it did prior to the interrupts occurring. See Figure 12.8 below.






Figure 12.8. SFR Page Stack Upon Return From ADC2 Window Interrupt

Note that in the above example, all three bytes in the SFR Page Stack are accessible via the SFRPAGE, SFRNEXT, and SFRLAST special function registers. If the stack is altered while servicing an interrupt, it is possible to return to a different SFR Page upon interrupt exit than selected prior to the interrupt call. Direct access to the SFR Page stack can be useful to enable real-time operating systems to control and manage context switching between multiple tasks.

Push operations on the SFR Page Stack only occur on interrupt service, and pop operations only occur on interrupt exit (execution on the RETI instruction). The automatic switching of the SFRPAGE and operation of the SFR Page Stack as described above can be disabled in software by clearing the SFR Automatic Page Enable Bit (SFRPGEN) in the SFR Page Control Register (SFRPGCN). See SFR Definition 12.1.



### SFR Definition 12.1. SFR Page Control Register: SFRPGCN

	R	R	R	R	R	R	R	R/W Reset Value
	-	-	-	-	-	-	-	SFRPGEN 00000001
_	Rit7	Bit6	Bit5	Rit4	Bit3	Rit2	Rit1	Bit0

SFR Address: 0x81 SFR Page: All Pages

Bits7-1: Reserved.

Bit0: SFRPGEN: SFR Automatic Page Control Enable.

Upon interrupt the C8051 Core will vector to the specified interrupt service routine and automatically switch the SFR page to the corresponding peripheral or function's SFR page. This bit is used to control this autopaging function.

0: SFR Automatic Paging disabled. C8051 core will not automatically change to the appropriate SFR page (i.e., the SFR page that contains the SFR's for the peripheral/function that was the source of the interrupt).

1: SFR Automatic Paging enabled. Upon interrupt, the CIP-51 will switch the SFR page to the page that contains the SFR's for the peripheral or function that is the source of the interrupt.

### SFR Definition 12.2. SFR Page Register: SFRPAGE

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
								00000000
 Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>
							SFR Addres	s: 0x84

SFR Page: All Pages

Bits7-0: SFRPAGE: SFR Page Register.

Byte represents the SFR page the CIP-51 uses when reading or modifying SFR's.

SFR page context is retained upon interrupts/return from interrupts in a 3 byte SFR Page Stack: SFRPAGE is the first entry, SFRNEXT is the second, and SFRLAST is third entry. The SFRPAGE, SFRSTACK, and SFRLAST bytes may be used alter the context in the SFR Page Stack. Only interrupts and returns from interrupt service routines push and pop the SFR Page Stack. (See Section 12.2.6.2 and Section 12.2.6.3 for further information.)

Write:

Sets the SFR Page

Read:

Byte is the SFR page the CIP-51 MCU is using.



### SFR Definition 12.3. SFR Next Register: SFRNEXT

	R/W	Reset Value							
									00000000
1	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0x85 SFR Page: All Pages

Bits7-0: SFR page context is retained upon interrupts/return from interrupts in a 3 byte SFR Page Stack: SFRPAGE is the first entry, SFRNEXT is the second, and SFRLAST is third entry. The SFRPAGE, SFRSTACK, and SFRLAST bytes may be used alter the context in the SFR Page Stack. Only interrupts and returns from interrupt service routines push and pop the SFR Page Stack. (See Section 12.2.6.2 and Section 12.2.6.3 for further information.)


#### Write:

Sets the SFR Page contained in the second byte of the SFR Stack. This will cause the SFRPAGE SFR to have this SFR page value upon a return from interrupt.

#### Read:

Returns the value of the SFR page contained in the second byte of the SFR stack. This is the value that will go to the SFR Page register upon a return from interrupt.

### SFR Definition 12.4. SFR Last Register: SFRLAST



SFR Address: 0x86 SFR Page: All Pages

Bits7-0: SFR page context is retained upon interrupts/return from interrupts in a 3 byte SFR Page Stack: SFRPAGE is the first entry, SFRNEXT is the second, and SFRLAST is the third entry. The SFR stack bytes may be used alter the context in the SFR Page Stack, and will not cause the stack to 'push' or 'pop'. Only interrupts and returns from the interrupt service routine push and pop the SFR Page Stack.

#### Write:

Sets the SFR Page in the last entry of the SFR Stack. This will cause the SFRNEXT SFR to have this SFR page value upon a return from interrupt.

#### Read:

Returns the value of the SFR page contained in the last entry of the SFR stack.



Table 12.2. Special Function Register (SFR) Memory Map

Note
F8 CANOCN P7  F0 (ALL PAGES)  ADCOCN PCAOCPL2 PCAOCPH2 PCAOCPH3 PCAOCPH4 PCAOCPH4 RSTSRC  E8 ADC2CN P6  P6  CANOCN PCAOCPL5 PCAOCPH5 XBR0 XBR1 XBR2 XBR3  PCAOCN CANODATL PAGES)  ACC CANODATL PCAOCPM0 PCAOCPM1 PCAOCPM1 PCAOCPM3 PCAOCPM4 PCAOCPM4 PCAOCPM5  CANODATL PAGES)
ADCOCN PCAOCPL2 PCAOCPH2 PCAOCPH3 PCAOCPH4 PCAOCPH4 RSTSRC  ADC2CN P6  P6  PCAOCPL5 PCAOCPH5  ACC (ALL PAGES)  XBR0 XBR1 XBR2 XBR3  PCAOCPM3 PCAOCPM3 PCAOCPM3 PCAOCPM3 PCAOCPM4 RSTSRC  (ALL PAGES)  (ALL PAGES)  (ALL PAGES)  (ALL PAGES)  (ALL PAGES)  (ALL PAGES)  PCAOCPM5 PCAOCPM5 PCAOCPM6 PCAOCPM1 PCAOCPM1 CANOADR PCAOCPM5 PCAOCPM5 PCAOCPM5 PCAOCPM5 PCAOCPM5 PCAOCPM6 PCAOCPM5 PCAOCPM6 PC
E8 ADC2CN P6 PCA0CPL5 PCA0CPH5  CANODATL P5 PCA0MD CANODATL P5
E0 ACC (ALL PAGES)  XBR0  XBR1  XBR2  XBR3  PCA0CN CANODATL CANODATH  CANODATL  P5
CANODATL CANODATH CANOADR CANOTST P5
DO (ALL PAGES)  DAC1L  DAC1H  DAC1CN
TMR2CN TMR2CF RCAP2L RCAP2H TMR2L TMR2H TMR3CN TMR3CF RCAP3L RCAP3H TMR3L TMR3H TMR4CN TMR4CF RCAP4L RCAP4H TMR4L TMR4H
SMB0CN SMB0STA SMB0DAT SMB0ADR ADC0GTL ADC0GTH ADC0LTL ADC0LTH ADC2LT ADC2LT
SADENO AMXOCF AMXOSL ADCOCF AMXOPRT ADCOL ADCOH
B8 (ALL PAGES)  AMX2CF AMX2SL ADC2CF ADC2

Table 12.2. Special Function Register (SFR) Memory Map (Continued)

A D D R E S S	0(8)	1(9)	2(A)	3(B)	4(C)	5(D)	6(E)	7(F)	SFR P A G E
ВО	P3 (ALL PAGES)							FLSCL FLACL	0 1 2 3 F
A8	IE (ALL PAGES)	SADDR0				P1MDIN	P2MDIN	P3MDIN	0 1 2 3 F
A0	P2 (ALL PAGES)	EMIOTC	EMI0CN	EMI0CF	POMDOUT	P1MDOUT	P2MDOUT	P3MDOUT	0 1 2 3 F
98	SCON0 SCON1	SBUF0 SBUF1	SPI0CFG	SPIODAT	P4MDOUT	SPI0CKR P5MDOUT	P6MDOUT	P7MDOUT	0 1 2 3 F
90	P1 (ALL PAGES)	SSTA0					SFRPGCN	CLKSEL	0 1 2 3 F
88	TCON CPT0CN CPT1CN CPT2CN	TMOD CPT0MD CPT1MD CPT2MD	TL0 OSCICN	TL1 OSCICL	TH0 OSCXCN	TH1	CKCON	PSCTL	0 1 2 3 F
80			DPL (ALL PAGES)				SFRLAST (ALL PAGES)		0 1 2 3 F
	0(8)	1(9)	2(A)	3(B)	4(C)	5(D)	6(E)	7(F)	



# **Table 12.3. Special Function Registers**

SFRs are listed in alphabetical order. All undefined SFR locations are reserved.

Register	Address	SFR Page	Description	Page No.
ACC	0xE0	All Pages	Accumulator	page 152
ADC0CF	0xBC	0	ADC0 Configuration	page 58 <sup>1</sup> , page 80 <sup>2</sup>
ADC0CN	0xE8	0	ADC0 Control	page 59 <sup>1</sup> , page 81 <sup>2</sup>
ADC0GTH	0xC5	0	ADC0 Greater-Than High	page 62 <sup>1</sup> , page 84 <sup>2</sup>
ADC0GTL	0xC4	0	ADC0 Greater-Than Low	page 62 <sup>1</sup> , page 84 <sup>2</sup>
ADC0H	0xBF	0	ADC0 Data Word High	page 60 <sup>1</sup> , page 82 <sup>2</sup>
ADC0L	0xBE	0	ADC0 Data Word Low	page 60 <sup>1</sup> , page 82 <sup>2</sup>
ADC0LTH	0xC7	0	ADC0 Less-Than High	page 62 <sup>1</sup> , page 84 <sup>2</sup>
ADC0LTL	0xC6	0	ADC0 Less-Than Low	page 63 <sup>1</sup> , page 85 <sup>2</sup>
ADC2 <sup>3</sup>	0xBE	2	ADC2 Data Word	page 99
ADC2CF <sup>3</sup>	0xBC	2	ADC2 Analog Multiplexer Configuration	page 95
ADC2CN <sup>3</sup>	0xE8	2	ADC2 Control	page 98
ADC2GT <sup>3</sup>	0xC4	2	ADC2 Window Comparator Greater-Than	page 100
ADC2LT <sup>3</sup>	0xC6	2	ADC2 Window Comparator Less-Than	page 100
AMX0CF	0xBA	0	ADC0 Multiplexer Configuration	page 49 <sup>1</sup> , page 71 <sup>2</sup>
AMX0PRT	0xBD	0	ADC0 Port 3 I/O Pin Select	page 51
AMX0SL	0xBB	0	ADC0 Multiplexer Channel Select	page 49 <sup>1</sup> , page 71 <sup>2</sup>
AMX2CF <sup>3</sup>	0xBA	2	ADC2 Multiplexer Configuration	page 97
AMX2SL <sup>3</sup>	0xBB	2	ADC2 Multiplexer Channel Select	page 95
В	0xF0	All Pages	B Register	page 152
CAN0ADR	0xDA	1	CAN0 Address	page 213
CAN0CN	0xF8	1	CAN0 Control	page 213
CAN0DATH	0xD9	1	CAN0 Data Register High	page 212
CAN0DATL	0xD8	1	CAN0 Data Register Low	page 212
CAN0STA	0xC0	1	CAN0 Status	page 214
CAN0TST	0xDB	1	CAN0 Test Register	page 214
CKCON	0x8E	0	Clock Control	page 293
CLKSEL	0x97	F	Oscillator Clock Selection Register	page 175
CPT0MD	0x89	1	Comparator 0 Mode Selection	page 125
CPT1MD	0x89	2	Comparator 1 Mode Selection	page 125
CPT2MD	0x89	3	Comparator 2 Mode Selection	page 125
CPT0CN	0x88	1	Comparator 0 Control	page 124
CPT1CN	0x88	2	Comparator 1 Control	page 124
CPT2CN	0x88	3	Comparator 2 Control	page 124
DAC0CN <sup>3</sup>	0xD4	0	DAC0 Control	page 108
DAC0H <sup>3</sup>	0xD3	0	DAC0 High	page 107
DAC0L <sup>3</sup>	0xD2	0	DAC0 Low	page 107
DAC1CN <sup>3</sup>	0xD4	1	DAC1 Control	page 110
DAC1H <sup>3</sup>	0xD3	1	DAC1 High Byte	page 109
2/10/1/1	_	1	J 7	1 9



# **Table 12.3. Special Function Registers (Continued)**

SFRs are listed in alphabetical order. All undefined SFR locations are reserved.

Register	Address	SFR Page	Description	Page No.
DAC1L <sup>3</sup>	0xD2	1	DAC1 Low Byte	page 109
DPH	0x83	All Pages	Data Pointer High	page 150
DPL	0x82		Data Pointer Low	page 150
EIE1	0xE6	All Pages	Extended Interrupt Enable 1	page 159
EIE2	0xE7	All Pages	Extended Interrupt Enable 2	page 160
EIP1	0xF6	All Pages	Extended Interrupt Priority 1	page 161
EIP2	0xF7	All Pages	Extended Interrupt Priority 2	page 162
EMI0CF	0xA3	0	EMIF Configuration	page 190
EMI0CN	0xA2	0	External Memory Interface Control	page 189
EMI0TC	0xA1	0	EMIF Timing Control	page 195
FLACL	0xB7	F	Flash Access Limit	page 184
FLSCL	0xB7	0	Flash Scale	page 184
HVA0CN	0xD6	0	High Voltage Differential Amp Control	page 53 <sup>1</sup> , page 75 <sup>2</sup>
IE	0xA8	All Pages	Interrupt Enable	page 157
IP	0xB8	All Pages	Interrupt Priority	page 158
OSCICL	0x8B	F	Internal Oscillator Calibration	page 174
OSCICN	0x8A	F	Internal Oscillator Control	page 174
OSCXCN	0x8C	F	External Oscillator Control	page 176
P0	0x80	All Pages	Port 0 Latch	page 215
P0MDOUT	0xA4	F	Port 0 Output Mode Configuration	page 216
P1	0x90	All Pages	Port 1 Latch	page 216
P1MDIN	0xAD	F	Port 1 Input Mode Configuration	page 217
P1MDOUT	0xA5	F	Port 1 Output Mode Configuration	page 217
P2	0xA0	All Pages	Port 2 Latch	page 218
P2MDIN	0xAE	F	Port 2 Input Mode Configuration	page 218
P2MDOUT	0xA6	F	Port 2 Output Mode Configuration	page 219
P3	0xB0	All Pages	Port 3 Latch	page 219
P3MDIN	0xAF	F	Port 3 Input Mode Configuration	page 220
P3MDOUT	0xA7	F	Port 3 Output Mode Configuration	page 220
P4 <sup>4</sup>	0xC8	F	Port 4 Latch	page 222
P4MDOUT <sup>4</sup>	0x9C	F	Port 4 Output Mode Configuration	page 222
P5 <sup>4</sup>	0xD8	F	Port 5 Latch	page 223
P5MDOUT <sup>4</sup>	0x9D	F	Port 5 Output Mode Configuration	page 223
P6 <sup>4</sup>	0xE8	F	Port 6 Latch	page 224
P6MDOUT <sup>4</sup>	0x9E	F	Port 6 Output Mode Configuration	page 224
P7 <sup>4</sup>	0xF8	F	Port 7 Latch	page 225
P7MDOUT <sup>4</sup>	0x9F	F	Port 7 Output Mode Configuration	page 225
PCA0CN	0xD8	0	PCA Control	page 312
PCA0CPH0 0xFC 0		0	PCA Capture 0 High	page 316
PCA0CPH1 0xFE 0		0	PCA Capture 1 High	page 316
PCA0CPH2 0xEA 0		0	PCA Capture 2 High	page 316
PCA0CPH3	0xEC	0	PCA Capture 3 High	page 316



# **Table 12.3. Special Function Registers (Continued)**

SFRs are listed in alphabetical order. All undefined SFR locations are reserved.

Register	Address	SFR Page	Description	Page No.	
PCA0CPH4	0xEE	0	PCA Capture 4 High	page 316	
PCA0CPH5	0xE2	0	PCA Capture 5 High	page 316	
PCA0CPL0	0xFB	0	PCA Capture 0 Low	page 316	
PCA0CPL1	0xFD	0	PCA Capture 1 Low	page 316	
PCA0CPL2	0xE9	0	PCA Capture 2 Low	page 316	
PCA0CPL3	0xEB	0	PCA Capture 3 Low	page 316	
PCA0CPL4	0xED	0	PCA Capture 4 Low	page 316	
PCA0CPL5	0xE1	0	PCA Capture 5 Low	page 316	
PCA0CPM0	0xDA	0	PCA Module 0 Mode Register	page 314	
PCA0CPM1	0xDB	0	PCA Module 1 Mode Register	page 314	
PCA0CPM2	0xDC	0	PCA Module 2 Mode Register	page 314	
PCA0CPM3	0xDD	0	PCA Module 3 Mode Register	page 314	
PCA0CPM4	0xDE	0	PCA Module 4 Mode Register	page 314	
PCA0CPM5	0xDF	0	PCA Module 5 Mode Register	page 314	
PCA0H	0xFA	0	PCA Counter High	page 315	
PCA0L	0xF9	0	PCA Counter Low	page 315	
PCA0MD	0xD9	0	PCA Mode	page 313	
PCON	0x87	All Pages	Power Control	page 164	
PSCTL	0x8F	0	Program Store R/W Control	page 185	
PSW	0xD0	All Pages	Program Status Word	page 151	
RCAP2H	0xCB	0	Timer/Counter 2 Capture/Reload High	page 301	
RCAP2L	0xCA	0	Timer/Counter 2 Capture/Reload Low	page 301	
RCAP3H	0xCB	1	Timer/Counter 3 Capture/Reload High	page 301	
RCAP3L	0xCA	1	Timer/Counter 3 Capture/Reload Low	page 301	
RCAP4H	0xCB	2	Timer/Counter 4 Capture/Reload High	page 301	
RCAP4L	0xCA	2	Timer/Counter 4 Capture/Reload Low	page 301	
REF0CN	0xD1	0	Programmable Voltage Reference Control	page 114 <sup>4</sup> , page 118 <sup>5</sup>	
RSTSRC	0xEF	0	Reset Source Register	page 170	
SADDR0	0xA9	0	UART 0 Slave Address	page 276	
SADEN0	0xB9	0	UART 0 Slave Address Enable	page 276	
SBUF0	0x99	0	UART 0 Data Buffer	page 276	
SBUF1	0x99	1	UART 1 Data Buffer	page 283	
SCON0	0x98	0	UART 0 Control	page 274	
SCON1	0x98	1	UART 1 Control	page 282	
SFRPAGE	0x84	All Pages	SFR Page Register	page 142	
SFRPGCN	0x96	F	SFR Page Control Register	page 142	
SFRNEXT	0x85	All Pages	SFR Next Page Stack Access Register	page 143	
SFRLAST	0x86	All Pages	SFR Last Page Stack Access Register	page 143	
SMB0ADR	0xC3	0	SMBus Slave Address	page 250	
SMB0CN	0xC0	0	SMBus Control	page 247	
SMB0CR	0xCF	0	SMBus Clock Rate	page 248	
SMB0DAT	0xC2	0	SMBus Data	page 249	
SMB0STA	0xC1	0	SMBus Status	page 251	
SP	0x81	All Pages	Stack Pointer	page 150	



## **Table 12.3. Special Function Registers (Continued)**

SFRs are listed in alphabetical order. All undefined SFR locations are reserved.

Register	Address	SFR Page	Description	Page No.
SPI0CFG	0x9A	0	SPI Configuration	page 261
SPI0CKR	0x9D	0	SPI Clock Rate Control	page 263
SPI0CN	0xF8	0	SPI Control	page 262
SPI0DAT	0x9B	0	SPI Data	page 264
SSTA0	0x91	0	UART0 Status and Clock Selection	page 275
TCON	0x88	0	Timer/Counter Control	page 291
TH0	0x8C	0	Timer/Counter 0 High	page 294
TH1	0x8D	0	Timer/Counter 1 High	page 294
TL0	0x8A	0	Timer/Counter 0 Low	page 293
TL1	0x8B	0	Timer/Counter 1 Low	page 294
TMOD	0x89	0	Timer/Counter Mode	page 292
TMR2CF	0xC9	0	Timer/Counter 2 Configuration	page 300
TMR2CN	0xC8	0	Timer/Counter 2 Control	page 299
TMR2H	0xCD	0	Timer/Counter 2 High	page 302
TMR2L	0xCC	0	Timer/Counter 2 Low	page 301
TMR3CF	0xC9	1	Timer/Counter 3 Configuration	page 300
TMR3CN	0xC8	1	Timer 3 Control	page 299
TMR3H	0xCD	1	Timer/Counter 3 High	page 302
TMR3L	0xCC	1	Timer/Counter 3 Low	page 301
TMR4CF	0xC9	2	Timer/Counter 4 Configuration	page 300
TMR4CN	0xC8	2	Timer/Counter 4 Control	page 299
TMR4H	0xCD	2	Timer/Counter 4 High	page 302
TMR4L	0xCC	2	Timer/Counter 4 Low	page 301
WDTCN	0xFF	All Pages	Watchdog Timer Control	page 169
XBR0	0xE1	F	Port I/O Crossbar Control 0	page 212
XBR1	0xE2	F	Port I/O Crossbar Control 1	page 213
XBR2	0xE3	F	Port I/O Crossbar Control 2	page 214
XBR3	0xE4	F	Port I/O Crossbar Control 3	page 215
0x97, 0xA2, 0xB3, 0xB4, 0xCE, 0xDF			Reserved	

#### Notes:

- 1. Refers to a register in the C8051F040 only.
- 2. Refers to a register in the C8051F041 only.
- 3. Refers to a register in C8051F040/1/2/3 only.
- 4. Refers to a register in the C8051F040/2/4/6 only.
- **5.** Refers to a register in the C8051F041/3/5/7 only.



### 12.2.7. Register Descriptions

Following are descriptions of SFRs related to the operation of the CIP-51 System Controller. Reserved bits should not be set to logic 1. Future product versions may use these bits to implement new features, in which case the reset value of the bit will be logic 0, selecting the feature's default state. Detailed descriptions of the remaining SFRs are included in the sections of the data sheet associated with their corresponding system function.

#### SFR Definition 12.5. SP: Stack Pointer

ı	R/W	Reset Value							
									00000111
	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	
								SFR Address	s: 0x81

SFR Page: All Pages

Bits7-0: SP: Stack Pointer.

The Stack Pointer holds the location of the top of the stack. The stack pointer is incremented before every PUSH operation. The SP register defaults to 0x07 after reset.

#### SFR Definition 12.6. DPL: Data Pointer Low Byte

R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value	
							00000000	
Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>	
SFR Address: 0x82								
	·						Bit6 Bit5 Bit4 Bit3 Bit2 Bit1 Bit0 SFR Addres	

Bits7-0: DPL: Data Pointer Low.

The DPL register is the low byte of the 16-bit DPTR. DPTR is used to access indirectly addressed XRAM and Flash memory.

#### SFR Definition 12.7. DPH: Data Pointer High Byte

	R/W	Reset Value							
									00000000
_	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>_</del>
								OFD Address	- 000

SFR Address: 0x83 SFR Page: All Pages

Bits7-0: DPH: Data Pointer High.

The DPH register is the high byte of the 16-bit DPTR. DPTR is used to access indirectly

addressed XRAM and Flash memory.



## SFR Definition 12.8. PSW: Program Status Word

R/W	Reset Value							
CY	AC	F0	RS1	RS0	OV	F1	PARITY	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xD0 SFR Page: All Pages

Bit7: CY: Carry Flag.

This bit is set when the last arithmetic operation resulted in a carry (addition) or a borrow

(subtraction). It is cleared to 0 by all other arithmetic operations.

Bit6: AC: Auxiliary Carry Flag

This bit is set when the last arithmetic operation resulted in a carry into (addition) or a borrow from (subtraction) the high order nibble. It is cleared to 0 by all other arithmetic operations.

Bit5: F0: User Flag 0.

This is a bit-addressable, general purpose flag for use under software control.

Bits4-3: RS1-RS0: Register Bank Select.

These bits select which register bank is used during register accesses.

RS1	RS0	Register Bank	Address
0	0	0	0x00-0x07
0	1	1	0x08-0x0F
1	0	2	0x10-0x17
1	1	3	0x18-0x1F

Bit2: OV: Overflow Flag.

This bit is set to 1 under the following circumstances:

- An ADD, ADDC, or SUBB instruction causes a sign-change overflow.
- A MUL instruction results in an overflow (result is greater than 255).
- A DIV instruction causes a divide-by-zero condition.

The OV bit is cleared to 0 by the ADD, ADDC, SUBB, MUL, and DIV instructions in all other cases.

Bit1: F1: User Flag 1.

This is a bit-addressable, general purpose flag for use under software control.

Bit0: PARITY: Parity Flag.

This bit is set to 1 if the sum of the eight bits in the accumulator is odd and cleared if the sum

is even.



#### SFR Definition 12.9. ACC: Accumulator

R/W	Reset Value							
ACC.7	ACC.6	ACC.5	ACC.4	ACC.3	ACC.2	ACC.1	ACC.0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xE0 SFR Page: All Pages

Bits7-0: ACC: Accumulator.

This register is the accumulator for arithmetic operations.

# SFR Definition 12.10. B: B Register

R/W	Reset Value							
B.7	B.6	B.5	B.4	B.3	B.2	B.1	B.0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xF0 SFR Page: All Pages

Bits7-0: B: B Register.

This register serves as a second accumulator for certain arithmetic operations.



### 12.3. Interrupt Handler

The CIP-51 includes an extended interrupt system supporting a total of 20 interrupt sources with two priority levels. The allocation of interrupt sources between on-chip peripherals and external inputs pins varies according to the specific version of the device. Each interrupt source has one or more associated interrupt-pending flag(s) located in an SFR. When a peripheral or external source meets a valid interrupt condition, the associated interrupt-pending flag is set to logic 1.

If interrupts are enabled for the source, an interrupt request is generated when the interrupt-pending flag is set. As soon as execution of the current instruction is complete, the CPU generates an LCALL to a predetermined address to begin execution of an interrupt service routine (ISR). Each ISR must end with an RETI instruction, which returns program execution to the next instruction that would have been executed if the interrupt request had not occurred. If interrupts are not enabled, the interrupt-pending flag is ignored by the hardware and program execution continues as normal. The interrupt-pending flag is set to logic 1 regardless of the interrupt's enable/disable state.

Each interrupt source can be individually enabled or disabled through the use of an associated interrupt enable bit in an SFR (IE-EIE2). However, interrupts must first be globally enabled by setting the EA bit (IE.7) to logic 1 before the individual interrupt enables are recognized. Setting the EA bit to logic 0 disables all interrupt sources regardless of the individual interrupt-enable settings.

**Note:** Any instruction that clears the EA bit should be immediately followed by an instruction that has two or more opcode bytes. For example:

```
// in 'C':
EA = 0;    // clear EA bit
EA = 0;    // ... followed by another 2-byte opcode
; in assembly:
CLR EA    ; clear EA bit
CLR EA    ; ... followed by another 2-byte opcode
```

If an interrupt is posted during the execution phase of a "CLR EA" opcode (or any instruction which clears the EA bit), and the instruction is followed by a single-cycle instruction, the interrupt may be taken. However, a read of the EA bit will return a '0' inside the interrupt service routine. When the "CLR EA" opcode is followed by a multi-cycle instruction, the interrupt will not be taken.

Some interrupt-pending flags are automatically cleared by the hardware when the CPU vectors to the ISR. However, most are not cleared by the hardware and must be cleared by software before returning from the ISR. If an interrupt-pending flag remains set after the CPU completes the return-from-interrupt (RETI) instruction, a new interrupt request will be generated immediately and the CPU will re-enter the ISR after the completion of the next instruction.

#### 12.3.1. MCU Interrupt Sources and Vectors

The MCUs support 20 interrupt sources. Software can simulate an interrupt event by setting any interrupt-pending flag to logic 1. If interrupts are enabled for the flag, an interrupt request will be generated and the CPU will vector to the ISR address associated with the interrupt-pending flag. MCU interrupt sources, associated vector addresses, priority order and control bits are summarized in Table 12.4. Refer to the datasheet section associated with a particular on-chip peripheral for information regarding valid interrupt conditions for the peripheral and the behavior of its interrupt-pending flag(s).



#### 12.3.2. External Interrupts

The external interrupt sources (/INT0 and /INT1) are configurable as active-low level-sensitive or active-low edge-sensitive inputs depending on the setting of bits IT0 (TCON.0) and IT1 (TCON.2). IE0 (TCON.1) and IE1 (TCON.3) serve as the interrupt-pending flag for the /INT0 and /INT1 external interrupts, respectively. If an /INT0 or /INT1 external interrupt is configured as edge-sensitive, the corresponding interrupt-pending flag is automatically cleared by the hardware when the CPU vectors to the ISR. When configured as level sensitive, the interrupt-pending flag follows the state of the external interrupt's input pin. The external interrupt source must hold the input active until the interrupt request is recognized. It must then deactivate the interrupt request before execution of the ISR completes or another interrupt request will be generated.

**Table 12.4. Interrupt Summary** 

Interrupt Source	Interrupt Vector	Priority Order	Pending Flag	Bit addressable?	Cleared by HW?	SFRPAGE (SFRPGEN = 1)	Enable Flag	Priority Control
Reset	0x0000	Тор	None	N/A	N/A	0	Always Enabled	Always Highest
External Interrupt 0 (/INT0)	0x0003	0	IE0 (TCON.1)	Υ	Υ	0	EX0 (IE.0)	PX0 (IP.0)
Timer 0 Overflow	0x000B	1	TF0 (TCON.5)	Υ	Υ	0	ET0 (IE.1)	PT0 (IP.1)
External Interrupt 1 (/INT1)	0x0013	2	IE1 (TCON.3)	Υ	Υ	0	EX1 (IE.2)	PX1 (IP.2)
Timer 1 Overflow	0x001B	3	TF1 (TCON.7)	Υ	Υ	0	ET1 (IE.3)	PT1 (IP.3)
UART0	0x0023	4	RI0 (SCON0.0) TI0 (SCON0.1)	Υ		0	ES0 (IE.4)	PS0 (IP.4)
Timer 2	0x002B	5	TF2 (TMR2CN.7)	Υ		0	ET2 (IE.5)	PT2 (IP.5)
Serial Peripheral Interface	0x0033	6	SPIF (SPI0CN.7) WCOL (SPI0CN.6) MODF (SPI0CN.5) RXOVRN (SPI0CN.4)	Υ		0	ESPI0 (EIE1.0)	PSPI0 (EIP1.0)
SMBus Interface	0x003B	7	SI (SMB0CN.3)	Υ		0	ESMB0 (EIE1.1)	PSMB0 (EIP1.1)
ADC0 Window Comparator	0x0043	8	AD0WINT (ADC0CN.2)	Υ		0	EWADC0 (EIE1.2)	PWADC0 (EIP1.2)
Programmable Counter Array	0x004B	9	CF (PCA0CN.7) CCFn (PCA0CN.n)	Υ		0	EPCA0 (EIE1.3)	PPCA0 (EIP1.3)
Comparator 0	0x0053	10	CP0FIF/CP0RIF (CPT0CN.4/.5)			1	CP0IE (EIE1.4)	PCP0 (EIP1.4)



**Table 12.4. Interrupt Summary (Continued)** 

Interrupt Source	Interrupt Vector	Priority Order	Pending Flag	Bit addressable?	Cleared by HW?	SFRPAGE (SFRPGEN = 1)	Enable Flag	Priority Control
Comparator 1	0x005B	11	CP1FIF/CP1RIF (CPT1CN.4/.5)			2	CP1IE (EIE1.5)	PCP1 (EIP1.5)
Comparator 2	0x0063	12	CP2FIF/CP2RIF (CPT2CN.4/.5)			3	CP2IE (EIE1.6)	PCP2 (EIP1.6)
Timer 3	0x0073	14	TF3 (TMR3CN.7)			1	ET3 (EIE2.0)	PT3 (EIP2.0)
ADC0 End of Conversion	0x007B	15	ADC0INT (ADC0CN.5)	Υ		0	EADC0 (EIE2.1)	PADC0 (EIP2.1)
Timer 4	0x0083	16	TF4 (TMR4CN.7)			2	ET4 (EIE2.2)	PT4 (EIP2.2)
ADC2 Window Comparator	0x0093	17	AD2WINT (ADC2CN.0)			2	EWADC2 (EIE2.3)	PWADC2 (EIP2.3)
ADC2 End of Conversion	0x008B	18	ADC2INT (ADC1CN.5)			2	EADC1 (EIE2.4)	PADC1 (EIP2.4)
CAN Interrupt	0x009B	19	CAN0CN.7		Υ	1	ECAN0 (EIE2.5)	PCAN0 (EIP2.5)
UART1	0x00A3	20	RI1 (SCON1.0) TI1 (SCON1.1)			1	ES1 (EIE2.6)	PS1 (EIP2.6)



#### 12.3.3. Interrupt Priorities

Each interrupt source can be individually programmed to one of two priority levels: low or high. A low priority interrupt service routine can be preempted by a high priority interrupt. A high priority interrupt cannot be preempted. Each interrupt has an associated interrupt priority bit in an SFR (IP-EIP2) used to configure its priority level. Low priority is the default. If two interrupts are recognized simultaneously, the interrupt with the higher priority is serviced first. If both interrupts have the same priority level, a fixed priority order is used to arbitrate, given in Table 12.4.

#### 12.3.4. Interrupt Latency

Interrupt response time depends on the state of the CPU when the interrupt occurs. Pending interrupts are sampled and priority decoded each system clock cycle. The fastest possible response time is 5 system clock cycles: 1 clock cycle to detect the interrupt and 4 clock cycles to complete the LCALL to the ISR. If an interrupt is pending when a RETI is executed, a single instruction is executed before an LCALL is made to service the pending interrupt. Therefore, the slowest response time for an interrupt (when no other interrupt is currently being serviced or the new interrupt is of greater priority) occurs when the CPU is performing an RETI instruction followed by a DIV as the next instruction. In this case, the response time is 18 system clock cycles: 1 clock cycle to detect the interrupt, 5 clock cycles to execute the RETI, 8 clock cycles to complete the DIV instruction and 4 clock cycles to execute the LCALL to the ISR. If the CPU is executing an ISR for an interrupt with equal or higher priority, the new interrupt will not be serviced until the current ISR completes, including the RETI and following instruction.

#### 12.3.5. Interrupt Register Descriptions

The SFRs used to enable the interrupt sources and set their priority level are described below. Refer to the datasheet section associated with a particular on-chip peripheral for information regarding valid interrupt conditions for the peripheral and the behavior of its interrupt-pending flag(s).



## SFR Definition 12.11. IE: Interrupt Enable

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
EA	IEGF0	ET2	ES0	ET1	EX1	ET0	EX0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xA8 SFR Page: All Pages

Bit7: EA: Enable All Interrupts.

This bit globally enables/disables all interrupts. It overrides the individual interrupt mask settings.

0: Disable all interrupt sources.

1: Enable each interrupt according to its individual mask setting.

Bit6: IEGF0: General Purpose Flag 0.

This is a general purpose flag for use under software control.

Bit5: ET2: Enabler Timer 2 Interrupt.

This bit sets the masking of the Timer 2 interrupt.

0: Disable Timer 2 interrupt.

1: Enable interrupt requests generated by the TF2 flag.

Bit4: ES0: Enable UART0 Interrupt.

This bit sets the masking of the UART0 interrupt.

0: Disable UART0 interrupt.

1: Enable UART0 interrupt.

Bit3: ET1: Enable Timer 1 Interrupt.

This bit sets the masking of the Timer 1 interrupt.

0: Disable all Timer 1 interrupt.

1: Enable interrupt requests generated by the TF1 flag.

Bit2: EX1: Enable External Interrupt 1.

This bit sets the masking of external interrupt 1.

0: Disable external interrupt 1.

1: Enable interrupt requests generated by the /INT1 pin.

Bit1: ET0: Enable Timer 0 Interrupt.

This bit sets the masking of the Timer 0 interrupt.

0: Disable all Timer 0 interrupt.

1: Enable interrupt requests generated by the TF0 flag.

Bit0: EX0: Enable External Interrupt 0.

This bit sets the masking of external interrupt 0.

0: Disable external interrupt 0.

1: Enable interrupt requests generated by the /INT0 pin.



## SFR Definition 12.12. IP: Interrupt Priority

R/W	Reset Value							
-	-	PT2	PS0	PT1	PX1	PT0	PX0	11000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xB8 SFR Page: All Pages

Bits7-6: UNUSED. Read = 11b, Write = don't care. PT2: Timer 2 Interrupt Priority Control. Bit5:

> This bit sets the priority of the Timer 2 interrupt. 0: Timer 2 interrupt priority set to low priority level. 1: Timer 2 interrupts set to high priority level.

Bit4: PS0: UARTO Interrupt Priority Control.

> This bit sets the priority of the UART0 interrupt. 0: UART0 interrupt priority set to low priority level. 1: UART0 interrupts set to high priority level.

PT1: Timer 1 Interrupt Priority Control. Bit3:

> This bit sets the priority of the Timer 1 interrupt. 0: Timer 1 interrupt priority set to low priority level. 1: Timer 1 interrupts set to high priority level.

Bit2: PX1: External Interrupt 1 Priority Control.

> This bit sets the priority of the External Interrupt 1 interrupt. 0: External Interrupt 1 priority set to low priority level.

1: External Interrupt 1 set to high priority level.

Bit1: PT0: Timer 0 Interrupt Priority Control.

> This bit sets the priority of the Timer 0 interrupt. 0: Timer 0 interrupt priority set to low priority level.

1: Timer 0 interrupt set to high priority level.

Bit0: PX0: External Interrupt 0 Priority Control.

This bit sets the priority of the External Interrupt 0 interrupt.

0: External Interrupt 0 priority set to low priority level.

1: External Interrupt 0 set to high priority level.



### SFR Definition 12.13. EIE1: Extended Interrupt Enable 1

R/V	V	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
		CP2IE	CP1IE	CP0IE	EPCA0	EWADC0	ESMB0	ESPI0	00000000
Bit	7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>

SFR Address: 0xE6 SFR Page: All Pages

Bit7: Reserved. Read = 0b, Write = don't care.

Bit6: CP2IE: Enable Comparator (CP2) Interrupt.

This bit sets the masking of the CP2 interrupt.

0: Disable CP2 interrupts.

1: Enable interrupt requests generated by the CP2IF flag.

Bit6: CP1IE: Enable Comparator (CP1) Interrupt.

This bit sets the masking of the CP1 interrupt.

0: Disable CP1 interrupts.

1: Enable interrupt requests generated by the CP1IF flag.

Bit6: CP0IE: Enable Comparator (CP0) Interrupt.

This bit sets the masking of the CP0 interrupt.

0: Disable CP0 interrupts.

1: Enable interrupt requests generated by the CP0IF flag.

Bit3: EPCA0: Enable Programmable Counter Array (PCA0) Interrupt.

This bit sets the masking of the PCA0 interrupts.

0: Disable all PCA0 interrupts.

1: Enable interrupt requests generated by PCA0.

Bit2: EWADC0: Enable Window Comparison ADC0 Interrupt.

This bit sets the masking of ADC0 Window Comparison interrupt.

0: Disable ADC0 Window Comparison Interrupt.

1: Enable Interrupt requests generated by ADC0 Window Comparisons.

Bit1: ESMB0: Enable System Management Bus (SMBus0) Interrupt.

This bit sets the masking of the SMBus interrupt.

0: Disable all SMBus interrupts.

1: Enable interrupt requests generated by the SI flag.

Bit0: ESPI0: Enable Serial Peripheral Interface (SPI0) Interrupt.

This bit sets the masking of SPI0 interrupt.

0: Disable all SPI0 interrupts.

1: Enable Interrupt requests generated by the SPI0 flag.



### SFR Definition 12.14. EIE2: Extended Interrupt Enable 2

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
-	ES1	ECAN0	EADC2	EWADC2	ET4	EADC0	ET3	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xE7 SFR Page: All Pages

Bit7: Reserved

Bit6: ES1: Enable UART1 Interrupt.

This bit sets the masking of the UART1 interrupt.

0: Disable UART1 interrupt.1: Enable UART1 interrupt.

Bit5: ECAN0: Enable CAN Controller Interrupt.

This bit sets the masking of the CAN Controller Interrupt.

0: Disable CAN Controller Interrupt.

1: Enable interrupt requests generated by the CAN Controller.

Bit4: EADC2: Enable ADC2 End Of Conversion Interrupt (C8051F040/1/2/3 only).

This bit sets the masking of the ADC2 End of Conversion interrupt.

0: Disable ADC2 End of Conversion interrupt.

1: Enable interrupt requests generated by the ADC2 End of Conversion Interrupt.

Bit3: EWADC2: Enable Window Comparison ADC2 Interrupt (C8051F040/1/2/3 only).

This bit sets the masking of ADC2 Window Comparison interrupt.

0: Disable ADC2 Window Comparison Interrupt.

1: Enable Interrupt requests generated by ADC2 Window Comparisons.

Bit2: ET4: Enable Timer 4 Interrupt

This bit sets the masking of the Timer 4 interrupt.

0: Disable Timer 4 interrupt.

1: Enable interrupt requests generated by the TF4 flag.

Bit1: EADC0: Enable ADC0 End of Conversion Interrupt.

This bit sets the masking of the ADC0 End of Conversion Interrupt.

0: Disable ADC0 Conversion Interrupt.

1: Enable interrupt requests generated by the ADC0 Conversion Interrupt.

Bit0: ET3: Enable Timer 3 Interrupt.

This bit sets the masking of the Timer 3 interrupt.

0: Disable all Timer 3 interrupts.

1: Enable interrupt requests generated by the TF3 flag.



### SFR Definition 12.15. EIP1: Extended Interrupt Priority 1

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
-	PCP2	PCP1	PCP0	PPCA0	PWADC0	PSMB0	PSPI0	00000000
Rit7	Bit6	Bit5	Rit4	Bit3	Bit2	Rit1	Bit0	<u> </u>

SFR Address: 0xF6 SFR Page: All Pages

Bit7: Reserved.

Bit6: PCP2: Comparator2 (CP2) Interrupt Priority Control.

This bit sets the priority of the CP2 interrupt.

0: CP2 interrupt set to low priority level.

1: CP2 interrupt set to high priority level.

Bit5: PCP1: Comparator1 (CP1) Interrupt Priority Control.

This bit sets the priority of the CP1 interrupt.

0: CP1 interrupt set to low priority level.

1: CP1 interrupt set to high priority level.

Bit4: PCP0: Comparator0 (CP0) Interrupt Priority Control.

This bit sets the priority of the CP0 interrupt.

0: CP0 interrupt set to low priority level.

1: CP0 interrupt set to high priority level.

Bit3: PPCA0: Programmable Counter Array (PCA0) Interrupt Priority Control.

This bit sets the priority of the PCA0 interrupt.

0: PCA0 interrupt set to low priority level.

1: PCA0 interrupt set to high priority level.

Bit2: PWADC0: ADC0 Window Comparator Interrupt Priority Control.

This bit sets the priority of the ADC0 Window interrupt.

0: ADC0 Window interrupt set to low priority level.

1: ADC0 Window interrupt set to high priority level.

Bit1: PSMB0: System Management Bus (SMBus0) Interrupt Priority Control.

This bit sets the priority of the SMBus0 interrupt.

0: SMBus interrupt set to low priority level.

1: SMBus interrupt set to high priority level.

Bit0: PSPI0: Serial Peripheral Interface (SPI0) Interrupt Priority Control.

This bit sets the priority of the SPI0 interrupt.
0: SPI0 interrupt set to low priority level.
1: SPI0 interrupt set to high priority level.



### SFR Definition 12.16. EIP2: Extended Interrupt Priority 2

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
-	EP1	PX7	PADC2	PWADC2	PT4	PADC0	PT3	00000000
Rit7	Rit6	Bit5	Rit4	Bit3	Rit2	Rit1	Rit∩	

SFR Address: 0xF7 SFR Page: All Pages

Bit7: Reserved.

Bit6: EP1: UART1 Interrupt Priority Control.

This bit sets the priority of the UART1 interrupt.

0: UART1 interrupt set to low level.1: UART1 interrupt set to high level.

Bit5: PCAN0: CAN Interrupt Priority Control.

This bit sets the priority of the CAN Interrupt.

0: CAN Interrupt set to low priority level.

1: CAN Interrupt set to high priority level.

Bit4: PADC2: ADC2 End Of Conversion Interrupt Priority Control (C8051F040/1/2/3 only).

This bit sets the priority of the ADC2 End of Conversion interrupt.

0: ADC2 End of Conversion interrupt set to low level.1: ADC2 End of Conversion interrupt set to low level.

Bit3: PWADC2: ADC2 Window Comparator Interrupt Priority Control (C8051F040/1/2/3 only).

0: ADC2 Window interrupt set to low level.

1: ADC2 Window interrupt set to high level.

Bit2: PT4: Timer 4 Interrupt Priority Control.

This bit sets the priority of the Timer 4 interrupt.

0: Timer 4 interrupt set to low level.1: Timer 4 interrupt set to low level.

Bit1: PADC0: ADC End of Conversion Interrupt Priority Control.

This bit sets the priority of the ADC0 End of Conversion Interrupt. 0: ADC0 End of Conversion interrupt set to low priority level. 1: ADC0 End of Conversion interrupt set to high priority level.

Bit0: PT3: Timer 3 Interrupt Priority Control.

This bit sets the priority of the Timer 3 interrupts.

0: Timer 3 interrupt set to low priority level.

1: Timer 3 interrupt set to high priority level.

### 12.17. Power Management Modes

The CIP-51 core has two software programmable power management modes: Idle and Stop. Idle mode halts the CPU while leaving the external peripherals and internal clocks active. In Stop mode, the CPU is halted, all interrupts and timers (except the Missing Clock Detector) are inactive, and the internal oscillator is stopped. Since clocks are running in Idle mode, power consumption is dependent upon the system clock frequency and the number of peripherals left in active mode before entering Idle. Stop mode consumes the least power. SFR Definition 12.18 describes the Power Control Register (PCON) used to control the CIP-51's power management modes.

Although the CIP-51 has Idle and Stop modes built in (as with any standard 8051 architecture), power management of the entire MCU is better accomplished by enabling/disabling individual peripherals as needed. Each analog peripheral can be disabled when not in use and put into low power mode. Digital peripherals, such as timers or serial buses, draw little power whenever they are not in use. Turning off the oscillator saves even more power, but requires a reset to restart the MCU.

#### 12.17.1.ldle Mode

Setting the Idle Mode Select bit (PCON.0) causes the CIP-51 to halt the CPU and enter Idle mode as soon as the instruction that sets the bit completes. All internal registers and memory maintain their original data. All analog and digital peripherals can remain active during Idle mode.

Idle mode is terminated when an enabled interrupt or /RST is asserted. The assertion of an enabled interrupt will cause the Idle Mode Selection bit (PCON.0) to be cleared and the CPU to resume operation. The pending interrupt will be serviced and the next instruction to be executed after the return from interrupt (RETI) will be the instruction immediately following the one that set the Idle Mode Select bit. If Idle mode is terminated by an internal or external reset, the CIP-51 performs a normal reset sequence and begins program execution at address 0x0000.

If enabled, the WDT will eventually cause an internal watchdog reset and thereby terminate the Idle mode. This feature protects the system from an unintended permanent shutdown in the event of an inadvertent write to the PCON register. If this behavior is not desired, the WDT may be disabled by software prior to entering the Idle mode if the WDT was initially configured to allow this operation. This provides the opportunity for additional power savings, allowing the system to remain in the Idle mode indefinitely, waiting for an external stimulus to wake up the system. Refer to **Section 13.7** for more information on the use and configuration of the WDT.

**Note:** Any instruction that sets the IDLE bit should be immediately followed by an instruction that has 2 or more opcode bytes. For example:

If the instruction following the write of the IDLE bit is a single-byte instruction and an interrupt occurs during the execution phase of the instruction that sets the IDLE bit, the CPU may not wake from IDLE mode when a future interrupt occurs.



### 12.17.2.Stop Mode

Setting the Stop Mode Select bit (PCON.1) causes the CIP-51 to enter Stop mode as soon as the instruction that sets the bit completes. In Stop mode, the CPU and internal oscillators are stopped, effectively shutting down all digital peripherals. Each analog peripheral must be shut down individually prior to entering Stop Mode. Stop mode can only be terminated by an internal or external reset. On reset, the CIP-51 performs the normal reset sequence and begins program execution at address 0x0000.

If enabled, the Missing Clock Detector will cause an internal reset and thereby terminate the Stop mode. The Missing Clock Detector should be disabled if the CPU is to be put to sleep for longer than the MCD timeout of  $100 \, \mu s$ .

#### SFR Definition 12.18. PCON: Power Control

R/W	Reset Value							
_	_	_	_	_	_	STOP	IDLE	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0x87 SFR Page: All Pages

Bits7-3: Reserved.

Bit1: STOP: STOP Mode Select.

Writing a '1' to this bit will place the CIP-51 into STOP mode. This bit will always read '0'.

0: No effect.

1: CIP-51 forced into power-down mode. (Turns off internal oscillator).

Bit0: IDLE: IDLE Mode Select.

Writing a '1' to this bit will place the CIP-51 into IDLE mode. This bit will always read '0'.

0: No effect.

1: CIP-51 forced into idle mode. (Shuts off clock to CPU, but clock to Timers, Interrupts, and

all peripherals remain active.)



#### 13. Reset Sources

Reset circuitry allows the controller to be easily placed in a predefined default condition. On entry to this reset state, the following occur:

- CIP-51 halts program execution
- Special Function Registers (SFRs) are initialized to their defined reset values
- · External port pins are forced to a known state
- Interrupts and timers are disabled.

All SFRs are reset to the predefined values noted in the SFR detailed descriptions. The contents of internal data memory are unaffected during a reset; any previously stored data is preserved. However, since the stack pointer SFR is reset, the stack is effectively lost even though the data on the stack are not altered.

The I/O port latches are reset to 0xFF (all logic 1s), activating internal weak pullups which take the external I/O pins to a high state. For  $V_{DD}$  Monitor resets, the /RST pin is driven low until the end of the  $V_{DD}$  reset timeout.

On exit from the reset state, the program counter (PC) is reset, and the system clock defaults to the internal oscillator running at its lowest frequency. Refer to Section "14. Oscillators" on page 173 for information on selecting and configuring the system clock source. The Watchdog Timer is enabled using its longest timeout interval (see Section "13.7. Watchdog Timer Reset" on page 167). Once the system clock source is stable, program execution begins at location 0x0000.

There are seven sources for putting the MCU into the reset state: power-on, power-fail, external /RST pin, external CNVSTR0 signal, software command, Comparator0, Missing Clock Detector, and Watchdog Timer. Each reset source is described in the following sections.




Figure 13.1. Reset Sources



#### 13.1. Power-On Reset

The C8051F04x family incorporates a power supply monitor that holds the MCU in the reset state until  $V_{DD}$  rises above the  $V_{RST}$  level during power-up. See Figure 13.2 for timing diagram, and refer to Table 13.1 for the Electrical Characteristics of the power supply monitor circuit. The /RST pin is asserted low until the end of the 100 ms  $V_{DD}$  Monitor timeout in order to allow the  $V_{DD}$  supply to stabilize. The  $V_{DD}$  Monitor reset is enabled and disabled using the external  $V_{DD}$  monitor enable pin (MONEN).

On exit from a power-on reset, the PORSF flag (RSTSRC.1) is set by hardware to logic 1. All of the other reset flags in the RSTSRC register are indeterminate. PORSF is cleared by all other resets. Since all resets cause program execution to begin at the same location (0x0000), software can read the PORSF flag to determine if a power-up was the cause of reset. The contents of internal data memory should be assumed to be undefined after a power-on reset.




Figure 13.2. Reset Timing

#### 13.2. Power-Fail Reset

When a power-down transition or power irregularity causes  $V_{DD}$  to drop below  $V_{RST}$ , the power supply monitor will drive the /RST pin low and return the CIP-51 to the reset state. When  $V_{DD}$  returns to a level above  $V_{RST}$ , the CIP-51 will leave the reset state in the same manner as that for the power-on reset (see Figure 13.2). Note that even though internal data memory contents are not altered by the power-fail reset, it is impossible to determine if  $V_{DD}$  dropped below the level required for data retention. If the PORSF flag is set to logic 1, the data may no longer be valid.

#### 13.3. External Reset

The external /RST pin provides a means for external circuitry to force the MCU into a reset state. Asserting the /RST pin low will cause the MCU to enter the reset state. It may be desirable to provide an external pul-



lup and/or decoupling of the /RST pin to avoid erroneous noise-induced resets. The MCU will remain in reset until at least 12 clock cycles after the active-low /RST signal is removed. The PINRSF flag (RST-SRC.0) is set on exit from an external reset.

#### 13.4. Missing Clock Detector Reset

The Missing Clock Detector is essentially a one-shot circuit that is triggered by the MCU system clock. If the system clock goes away for more than 100  $\mu$ s, the one-shot will time out and generate a reset. After a Missing Clock Detector reset, the MCDRSF flag (RSTSRC.2) will be set, signifying the MCD as the reset source; otherwise, this bit reads '0'. The state of the /RST pin is unaffected by this reset. Setting the MCDRSF bit, RSTSRC.2 (see Section "14. Oscillators" on page 173) enables the Missing Clock Detector.

#### 13.5. Comparator Reset

Comparator0 can be configured as a reset input by writing a '1' to the CORSEF flag (RSTSRC.5). Comparator0 should be enabled using CPT0CN.7 (see Section "11. Comparators" on page 121) prior to writing to CORSEF to prevent any turn-on chatter on the output from generating an unwanted reset. The Comparator0 reset is active-low: if the non-inverting input voltage (CP0+ pin) is less than the inverting input voltage (CP0- pin), the MCU is put into the reset state. After a Comparator0 Reset, the CORSEF flag (RSTSRC.5) will read '1' signifying Comparator0 as the reset source; otherwise, this bit reads '0'. The state of the /RST pin is unaffected by this reset.

#### 13.6. External CNVSTR0 Pin Reset

The external CNVSTR0 signal can be configured as a reset input by writing a '1' to the CNVRSEF flag (RSTSRC.6). The CNVSTR0 signal can appear on any of the P0, P1, P2 or P3 I/O pins as described in Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204. Note that the Crossbar must be configured for the CNVSTR0 signal to be routed to the appropriate Port I/O. The Crossbar should be configured and enabled before the CNVRSEF is set. When configured as a reset, CNVSTR0 is active-low and level sensitive. After a CNVSTR0 reset, the CNVRSEF flag (RSTSRC.6) will read '1' signifying CNVSTR0 as the reset source; otherwise, this bit reads '0'. The state of the /RST pin is unaffected by this reset.

#### 13.7. Watchdog Timer Reset

The MCU includes a programmable Watchdog Timer (WDT) running off the system clock. A WDT overflow will force the MCU into the reset state. To prevent the reset, the WDT must be restarted by application software before overflow. If the system experiences a software or hardware malfunction preventing the software from restarting the WDT, the WDT will overflow and cause a reset. This should prevent the system from running out of control.

Following a reset the WDT is automatically enabled and running with the default maximum time interval. If desired the WDT can be disabled by system software or locked on to prevent accidental disabling. Once locked, the WDT cannot be disabled until the next system reset. The state of the /RST pin is unaffected by this reset.

The WDT consists of a 21-bit timer running from the programmed system clock. The timer measures the period between specific writes to its control register. If this period exceeds the programmed limit, a WDT reset is generated. The WDT can be enabled and disabled as needed in software, or can be permanently enabled if desired. Watchdog features are controlled via the Watchdog Timer Control Register (WDTCN) shown in SFR Definition 13.1.



#### 13.7.1. Enable/Reset WDT

The watchdog timer is both enabled and reset by writing 0xA5 to the WDTCN register. The user's application software should include periodic writes of 0xA5 to WDTCN as needed to prevent a watchdog timer overflow. The WDT is enabled and reset as a result of any system reset.

#### 13.7.2. Disable WDT

Writing 0xDE followed by 0xAD to the WDTCN register disables the WDT. The following code segment illustrates disabling the WDT:

```
CLR EA ; disable all interrupts
MOV WDTCN,#0DEh ; disable software watchdog timer
MOV WDTCN,#0ADh
SETB EA ; re-enable interrupts
```

The writes of 0xDE and 0xAD must occur within 4 clock cycles of each other, or the disable operation is ignored. Interrupts should be disabled during this procedure to avoid delay between the two writes.

#### 13.7.3. Disable WDT Lockout

Writing 0xFF to WDTCN locks out the disable feature. Once locked out, the disable operation is ignored until the next system reset. Writing 0xFF does not enable or reset the watchdog timer. Applications always intending to use the watchdog should write 0xFF to WDTCN in the initialization code.

#### 13.7.4. Setting WDT Interval

WDTCN.[2:0] control the watchdog timeout interval. The interval is given by the following equation:

```
4^{3 \, + \, WDTCN[2 \, - \, 0]} \times T_{sysclk} ; where T_{\rm sysclk} is the system clock period.
```

For a 3 MHz system clock, this provides an interval range of 0.021 ms to 349.5 ms. WDTCN.7 must be logic 0 when setting this interval. Reading WDTCN returns the programmed interval. WDTCN.[2:0] reads 111b after a system reset.



## SFR Definition 13.1. WDTCN: Watchdog Timer Control

R/W	Reset Value							
								xxxxx111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xFF SFR Page: All Pages

Bits7-0: WDT Control

Writing 0xA5 both enables and reloads the WDT.

Writing 0xDE followed within 4 system clocks by 0xAD disables the WDT.

Writing 0xFF locks out the disable feature.

Bit4: Watchdog Status Bit (when Read)

Reading the WDTCN.[4] bit indicates the Watchdog Timer Status.

0: WDT is inactive 1: WDT is active

Bits2-0: Watchdog Timeout Interval Bits

The WDTCN.[2:0] bits set the Watchdog Timeout Interval. When writing these bits,

WDTCN.7 must be set to 0.



#### SFR Definition 13.2. RSTSRC: Reset Source

	R	R/W	R/W	R/W	R	R/W	R	R/W	Reset Value
	-	CNVRSEF	C0RSEF	SWRSEF	WDTRSF	MCDRSF	PORSF	PINRSF	00000000
-	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>-</del>

SFR Address: 0xEF SFR Page: 0

Bit7: Reserved.

Bit6: CNVRSEF: Convert Start Reset Source Enable and Flag

Write: 0: CNVSTR0 is not a reset source.

1: CNVSTR0 is a reset source (active low).

Read: 0: Source of prior reset was not CNVSTR0.

1: Source of prior reset was CNVSTR0. Bit5:

CORSEF: Comparator Reset Enable and Flag.

Write: 0: Comparator 0 is not a reset source. 1: Comparator 0 is a reset source (active low).

0: Source of last reset was not Comparator0.

1: Source of last reset was Comparator0.

Bit4: SWRSF: Software Reset Force and Flag.

Write: 0: No effect.

1: Forces an internal reset. /RST pin is not effected.

Read: 0: Source of last reset was not a write to the SWRSF bit.

1: Source of last reset was a write to the SWRSF bit.

Bit3: WDTRSF: Watchdog Timer Reset Flag.

0: Source of last reset was not WDT timeout.

1: Source of last reset was WDT timeout.

MCDRSF: Missing Clock Detector Flag. Bit2:

0: Missing Clock Detector disabled.

1: Missing Clock Detector enabled; triggers a reset if a missing clock condition is

detected.

Read: 0: Source of last reset was not a Missing Clock Detector timeout.

1: Source of last reset was a Missing Clock Detector timeout.

PORSF: Power-On Reset Flag. Bit1:

> Write: If the V<sub>DD</sub> monitor circuitry is enabled (by tying the MONEN pin to a logic high state), this bit can be written to select or de-select the V<sub>DD</sub> monitor as a reset source.

0: De-select the  $V_{\mbox{\scriptsize DD}}$  monitor as a reset source.

1: Select the V<sub>DD</sub> monitor as a reset source.

Important: At power-on, the V<sub>DD</sub> monitor is enabled/disabled using the external V<sub>DD</sub> monitor enable pin (MONEN). The PORSF bit does not disable or enable the  $\ensuremath{\text{V}_{\text{DD}}}$  monitor circuit. It simply selects the V<sub>DD</sub> monitor as a reset source.

Read: This bit is set whenever a power-on reset occurs. This may be due to a true power-on reset or a V<sub>DD</sub> monitor reset. In either case, data memory should be considered indeterminate following the reset.

0: Source of last reset was not a power-on or V<sub>DD</sub> monitor reset.

Source of last reset was a power-on or V<sub>DD</sub> monitor reset.

Note: When this flag is read as '1', all other reset flags are indeterminate.

Bit0: PINRSF: HW Pin Reset Flag.

Write: 0: No effect.

1: Forces a Power-On Reset. /RST is driven low.

0: Source of prior reset was not /RST pin.

1: Source of prior reset was /RST pin.



# **Table 13.1. Reset Electrical Characteristics**

-40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
RST Output Low Voltage	$I_{OL} = 8.5 \text{ mA}, V_{DD} = 2.7 \text{ V to } 3.6 \text{ V}$	_	_	0.6	V
RST Input High Voltage		0.7 x V <sub>DD</sub>	_		V
RST Input Low Voltage			_	0.3 x V <sub>DD</sub>	
RST Input Leakage Current	RST = 0.0 V	1	50	1	μΑ
V <sub>DD</sub> for /RST Output Valid		1.0	_		V
AV+ for /RST Output Valid		1.0	_		V
V <sub>DD</sub> POR Threshold (V <sub>RST</sub> )		2.40	2.55	2.70	V
Minimum /RST Low Time to Generate a System Reset		10		l	ns
Reset Time Delay	RST rising edge after V <sub>DD</sub> crosses V <sub>RST</sub> threshold	80	100	120	ms
Missing Clock Detector Timeout	Time from last system clock to reset initiation	100	220	500	μs





### 14. Oscillators




Figure 14.1. Oscillator Diagram

### 14.1. Programmable Internal Oscillator

All C8051F04x devices include a programmable internal oscillator that defaults as the system clock after a system reset. The internal oscillator period can be programmed via the OSCICL register as defined by SFR Definition 14.1. OSCICL is factory calibrated to obtain a 24.5 MHz frequency.

Electrical specifications for the precision internal oscillator are given in Table 14.1 on page 175. The programmed internal oscillator frequency must not exceed 25 MHz. The system clock may be derived from the programmed internal oscillator divided by 1, 2, 4, or 8, as defined by the IFCN bits in register OSCICN.



#### SFR Definition 14.1. OSCICL: Internal Oscillator Calibration

R/W	Reset Value							
								Variable
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>

SFR Address: 0x8B SFR Page: F

Bits 7-0: OSCICL: Internal Oscillator Calibration Register

This register calibrates the internal oscillator period. The reset value for OSCICL defines the internal oscillator base frequency. The reset value is factory calibrated to generate an internal oscillator frequency of 24.5 MHz.

#### SFR Definition 14.2. OSCICN: Internal Oscillator Control

R/W	R/W	R/W	R	R/W	R/W	R/W	R/W	Reset Value
IOSCEN	IFRDY	-	-	-	-	IFCN1	IFCN0	11000000
Rit7	Rit6	Rit5	Rit∕I	Rit3	Rit2	Rit1	Rit∩	

SFR Address: 0x8A SFR Page: F

Bit7: IOSCEN: Internal Oscillator Enable Bit.

0: Internal Oscillator Disabled

1: Internal Oscillator Enabled

Bit6: IFRDY: Internal Oscillator Frequency Ready Flag.

0: Internal Oscillator is not running at programmed frequency.

1: Internal Oscillator is running at programmed frequency.

Bits5-2: Reserved.

Bits1-0: IFCN1-0: Internal Oscillator Frequency Control Bits.

00: SYSCLK derived from Internal Oscillator divided by 8.

01: SYSCLK derived from Internal Oscillator divided by 4.

10: SYSCLK derived from Internal Oscillator divided by 2.

11: SYSCLK derived from Internal Oscillator divided by 1.



**Table 14.1. Internal Oscillator Electrical Characteristics** 

-40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Calibrated Internal Oscillator Frequency		24	24.5	25	MHz
$\begin{array}{c} \text{Internal Oscillator Supply Current} \\ \text{(from $V_{\rm DD}$)} \end{array}$	OSCICN.7 = 1	_	450	_	μΑ
External Clock Frequency		0	-	30	MHz
T <sub>XCH</sub> (External Clock High Time)		15	1	1	ns
T <sub>XCL</sub> (External Clock Low Time)		15		_	ns


#### 14.2. External Oscillator Drive Circuit

The external oscillator circuit may drive an external crystal, ceramic resonator, capacitor, or RC network. A CMOS clock may also provide a clock input. For a crystal or ceramic resonator configuration, the crystal/ resonator must be wired across the XTAL1 and XTAL2 pins as shown in Option 1 of Figure 14.1. In RC, capacitor, or CMOS clock configuration, the clock source should be wired to the XTAL2 and/or XTAL1 pin(s) as shown in Option 2, 3, or 4 of Figure 14.1. The type of external oscillator must be selected in the OSCXCN register, and the frequency control bits (XFCN) must be selected appropriately (see SFR Definition 14.4).

### 14.3. System Clock Selection

The CLKSL bit in register CLKSEL selects which oscillator is used as the system clock. CLKSL must be set to '1' for the system clock to run from the external oscillator; however the external oscillator may still clock peripherals (timers, PCA) when the internal oscillator is selected as the system clock. The system clock may be switched on-the-fly between the internal and external oscillator, so long as the selected oscillator is enabled and has settled. The internal oscillator requires little start-up time and may be enabled and selected as the system clock in the same write to OSCICN. External crystals and ceramic resonators typically require a start-up time before they are settled and ready for use as the system clock. The Crystal Valid Flag (XTLVLD in register OSCXCN) is set to '1' by hardware when the external oscillator is settled. To avoid reading a false XTLVLD in crystal mode, software should delay at least 1 ms between enabling the external oscillator and checking XTLVLD. RC and C modes typically require no startup time.

#### SFR Definition 14.3. CLKSEL: Oscillator Clock Selection



Bits7-1: Reserved.

Bit0: CLKSL: System Clock Source Select Bit.

0: SYSCLK derived from the Internal Oscillator, and scaled as per the IFCN bits in OSCICN.

1: SYSCLK derived from the External Oscillator circuit.



#### SFR Definition 14.4. OSCXCN: External Oscillator Control

R	R/W	R/W	R/W	R	R/W	R/W	R/W	Reset Value
XTLVLD	XOSCMD2	XOSCMD1	XOSCMD0	-	XFCN2	XFCN1	XFCN0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0x8C SFR Page: F

Bit7: XTLVLD: Crystal Oscillator Valid Flag.

(Read only when XOSCMD = 11x.)

0: Crystal Oscillator is unused or not yet stable.

1: Crystal Oscillator is running and stable.

Bits6-4: XOSCMD2-0: External Oscillator Mode Bits.

00x: External Oscillator circuit off.

010: External CMOS Clock Mode (External CMOS Clock input on XTAL1 pin).

011: External CMOS Clock Mode with divide by 2 stage (External CMOS Clock input on

XTAL1 pin).

10x: RC/C Oscillator Mode with divide by 2 stage.

110: Crystal Oscillator Mode.

111: Crystal Oscillator Mode with divide by 2 stage.

Bit3: RESERVED. Read = 0, Write = don't care.

Bits2-0: XFCN2-0: External Oscillator Frequency Control Bits.

000-111: see table below:

XFCN	Crystal (XOSCMD = 11x)	RC (XOSCMD = 10x)	C (XOSCMD = 10x)
000	f ≤ 32 kHz	f ≤ 25 kHz	K Factor = 0.87
001	32 kHz < f ≤ 84 kHz	25 kHz < f ≤ 50 kHz	K Factor = 2.6
010	84 kHz < f ≤ 225 kHz	50 kHz < f ≤ 100 kHz	K Factor = 7.7
011	225 kHz < f ≤ 590 kHz	100 kHz < f ≤ 200 kHz	K Factor = 22
100	590 kHz < f ≤ 1.5 MHz	200 kHz < f ≤ 400 kHz	K Factor = 65
101	$1.5 \text{ MHz} < f \le 4 \text{ MHz}$	400 kHz < f ≤ 800 kHz	K Factor = 180
110	$4 \text{ MHz} < f \le 10 \text{ MHz}$	800 kHz < f ≤ 1.6 MHz	K Factor = 664
111	10 MHz $< f \le 30$ MHz	$1.6 \text{ MHz} < f \leq 3.2 \text{ MHz}$	K Factor = 1590

**CRYSTAL MODE** (Circuit from Figure 14.1, Option 1; XOSCMD = 11x)

Choose XFCN value to match crystal frequency.

**RC MODE** (Circuit from Figure 14.1, Option 2; XOSCMD = 10x)

Choose XFCN value to match frequency range:

 $f = 1.23(10^3) / (R \times C)$ , where

f = frequency of oscillation in MHz

C = capacitor value in pF

 $R = Pullup resistor value in k\Omega$ 

**C MODE** (Circuit from Figure 14.1, Option 3; XOSCMD = 10x)

Choose K Factor (KF) for the oscillation frequency desired:

 $f = KF / (C \times V_{DD})$ , where

f = frequency of oscillation in MHz

C = capacitor value on XTAL1, XTAL2 pins in pF

V<sub>DD</sub> = Power Supply on MCU in volts



#### 14.4. External Crystal Example

If a crystal or ceramic resonator is used as an external oscillator source for the MCU, the circuit should be configured as shown in Figure 14.1, Option 1. The External Oscillator Frequency Control value (XFCN) should be chosen from the Crystal column of the table in SFR Definition 14.4 (OSCXCN register). For example, an 11.0592 MHz crystal requires an XFCN setting of 111b.

When the crystal oscillator is enabled, the oscillator amplitude detection circuit requires a settle time to achieve proper bias. Introducing a delay of at least 1 ms between enabling the oscillator and checking the XTLVLD bit will prevent a premature switch to the external oscillator as the system clock. Switching to the external oscillator before the crystal oscillator has stabilized can result in unpredictable behavior. The recommended procedure is:

- Step 1. Enable the external oscillator in crystal oscillator mode.
- Step 2. Wait at least 1 ms.
- Step 3. Poll for XTLVLD => '1'.
- Step 4. Switch the system clock to the external oscillator.

Note: Tuning-fork crystals may require additional settling time before XTLVLD returns a valid result.

The capacitors shown in the external crystal configuration provide the load capacitance required by the crystal for correct oscillation. These capacitors are "in series" as seen by the crystal and "in parallel" with the stray capacitance of the XTAL1 and XTAL2 pins.

**Note:** The load capacitance depends upon the crystal and the manufacturer. Please refer to the crystal data sheet when completing these calculations.

For example, a tuning-fork crystal of 32.768 kHz with a recommended load capacitance of 12.5 pF should use the configuration shown in Figure 14.1, Option 1. The total value of the capacitors and the stray capacitance of the XTAL pins should equal 25 pF. With a stray capacitance of 3 pF per pin, the 22 pF capacitors yield an equivalent capacitance of 12.5 pF across the crystal, as shown in Figure 14.2.




Figure 14.2. 32.768 kHz External Crystal Example

**Important Note on External Crystals:** Crystal oscillator circuits are quite sensitive to PCB layout. The crystal should be placed as close as possible to the XTAL pins on the device. The traces should be as short as possible and shielded with ground plane from any other traces which could introduce noise or interference.



### 14.5. External RC Example

If an RC network is used as an external oscillator source for the MCU, the circuit should be configured as shown in Figure 14.1, Option 2. The capacitor should be no greater than 100 pF; however, for very small capacitors, the total capacitance may be dominated by parasitic capacitance in the PCB layout. To determine the required External Oscillator Frequency Control value (XFCN) in the OSCXCN Register, first select the RC network value to produce the desired frequency of oscillation. If the frequency desired is 100 kHz, let R =  $246 \text{ k}\Omega$  and C = 50 pF:

$$f = 1.23(10^3) / RC = 1.23(10^3) / [246 \times 50] = 0.1 MHz = 100 kHz$$

Referring to the table in SFR Definition 14.4, the required XFCN setting is 010b.

### 14.6. External Capacitor Example

If a capacitor is used as an external oscillator for the MCU, the circuit should be configured as shown in Figure 14.1, Option 3. The capacitor should be no greater than 100 pF; however, for very small capacitors, the total capacitance may be dominated by parasitic capacitance in the PCB layout. To determine the required External Oscillator Frequency Control value (XFCN) in the OSCXCN Register, select the desired frequency of oscillation and find the capacitor to be used from the equations below. Assume  $V_{DD} = 3.0 \text{ V}$  and f = 50 kHz:

$$f = KF / (C \times V_{DD}) = KF / (C \times 3) = 0.050 MHz$$

If a frequency of roughly 50 kHz is desired, select the K Factor from the table in SFR Definition 14.4 as KF = 7.7:

 $0.050 \text{ MHz} = 7.7 / (C \times 3)$ 

$$C \times 3 = 7.7 / 0.050 = 154$$
, so  $C = 154 / 3 pF = 51.3 pF$ 

Therefore, the XFCN value to use in this example is 010b.



## 15. Flash Memory

The C8051F04x family includes 64 kB + 128 (C8051F040/1/2/3/4/5) or 32 kB + 128 (C8051F046/7) of onchip, reprogrammable Flash memory for program code and non-volatile data storage. The Flash memory can be programmed in-system, a single byte at a time, through the JTAG interface or by software using the MOVX write instructions. Once cleared to logic 0, a Flash bit must be erased to set it back to logic 1. The bytes would typically be erased (set to 0xFF) before being reprogrammed. Flash write and erase operations are automatically timed by hardware for proper execution; data polling to determine the end of the write/erase operation is not required. The CPU is stalled during write/erase operations while the device peripherals remain active. Interrupts that occur during Flash write/erase operations are held, and are then serviced in their priority order once the Flash operation has completed. Refer to Table 15.1 for the electrical characteristics of the Flash memory.

### 15.1. Programming The Flash Memory

The simplest means of programming the Flash memory is through the JTAG interface using programming tools provided by Silicon Labs or a third party vendor. This is the only means for programming a non-initialized device. For details on the JTAG commands to program Flash memory, see **Section "25.2. Flash Programming Commands" on page 321**.

The Flash memory can be programmed by software using the MOVX write instruction with the address and data byte to be programmed provided as normal operands. Before writing to Flash memory using MOVX, Flash write operations must be enabled by setting the PSWE Program Store Write Enable bit (PSCTL.0) to logic 1. This directs the MOVX writes to Flash memory instead of to XRAM, which is the default target. The PSWE bit remains set until cleared by software. To avoid errant Flash writes, it is recommended that interrupts be disabled while the PSWE bit is logic 1.

Flash memory is read using the MOVC instruction. MOVX reads are always directed to XRAM, regardless of the state of PSWE.

**Note**: To ensure the integrity of Flash memory contents, it is strongly recommended that the on-chip  $V_{DD}$  monitor be enabled by connecting the  $V_{DD}$  monitor enable pin (MONEN) to  $V_{DD}$  in any system that executes code that writes and/or erases Flash memory from software. See "Reset Sources" on page 165 for more information.

A write to Flash memory can clear bits but cannot set them; only an erase operation can set bits in Flash. A byte location to be programmed must be erased before a new value can be written. The Flash memory is organized in 512-byte pages. The erase operation applies to an entire page (setting all bytes in the page to 0xFF). The following steps illustrate the algorithm for programming Flash by user software.

- Step 1. Disable interrupts.
- Step 2. Set FLWE (FLSCL.0) to enable Flash writes/erases via user software.
- Step 3. Set PSEE (PSCTL.1) to enable Flash erases.
- Step 4. Set PSWE (PSCTL.0) to redirect MOVX commands to write to Flash.
- Step 5. Use the MOVX command to write a data byte to any location within the 512-byte page to be erased.
- Step 6. Clear PSEE to disable Flash erases
- Step 7. Use the MOVX command to write a data byte to the desired byte location within the erased 512-byte page. Repeat this step until all desired bytes are written (within the target page).
- Step 8. Clear the PSWE bit to redirect MOVX commands to the XRAM data space.
- Step 9. Re-enable interrupts.

Write/Erase timing is automatically controlled by hardware. Note that code execution in the 8051 is stalled while the Flash is being programmed or erased. Note that 512 bytes at locations 0xFE00 (C8051F040/1/2/



3/4/5) and all locations above 0x8000 (C8051F046/7) are reserved. Flash writes and erases targeting the reserved area should be avoided.

#### **Table 15.1. Flash Electrical Characteristics**

 $V_{DD} = 2.7 \text{ to } 3.6 \text{ V}; T_a = -40 \text{ to } +85 \text{ }^{\circ}\text{C}$ 

Parameter	Conditions	Min	Тур	Max	Units
Flash Size <sup>1</sup>	C8051F040/1/2/3/4/5 C8051F046/7		65664 <sup>2</sup> 32896		Bytes
Endurance		20 k	100 k	_	Erase/Write
Erase Cycle Time		10	12	14	ms
Write Cycle Time		40	50	60	μs

#### Notes:

- 1. Includes 128-byte scratchpad.
- 2. 512 bytes at locations 0xFE00 to 0xFFFF are reserved.

### 15.2. Non-volatile Data Storage

The Flash memory can be used for non-volatile data storage as well as program code. This allows data such as calibration coefficients to be calculated and stored at run time. Data is written using the MOVX write instruction (as described in the previous section) and read using the MOVC instruction.

An additional 128-byte sector of Flash memory is included for non-volatile data storage. Its smaller sector size makes it particularly well suited as general purpose, non-volatile scratchpad memory. Even though Flash memory can be written a single byte at a time, an entire sector must be erased first. In order to change a single byte of a multi-byte data set, the data must be moved to temporary storage. The 128-byte sector-size facilitates updating data without wasting program memory or RAM space. The 128-byte sector is double-mapped over the 64k byte Flash memory; its address ranges from 0x00 to 0x7F (see Figure 15.1). To access this 128-byte sector, the SFLE bit in PSCTL must be set to logic 1. Code execution from this 128-byte scratchpad sector is not permitted.


#### 15.3. Security Options


The CIP-51 provides security options to protect the Flash memory from inadvertent modification by software as well as prevent the viewing of proprietary program code and constants. The Program Store Write Enable (PSCTL.0) and the Program Store Erase Enable (PSCTL.1) bits protect the Flash memory from accidental modification by software. These bits must be explicitly set to logic 1 before software can write or erase the Flash memory. Additional security features prevent proprietary program code and data constants from being read or altered across the JTAG interface or by software running on the system controller.

A set of security lock bytes stored at 0xFDFE and 0xFDFF (C8051F040/1/2/3/4/5) and at 0x7FFE and 0x7FFF (C8051F046/7) protect the Flash program memory from being read or altered across the JTAG interface. Each bit in a security lock-byte protects one 8k-byte block of memory. Clearing a bit to logic 0 in a Read Lock Byte prevents the corresponding block of Flash memory from being read across the JTAG interface. Clearing a bit in the Write/Erase Lock Byte protects the block from JTAG erasures and/or writes.

The Read Lock Byte is at locations 0xFDFF (C8051F040/1/2/3/4/5) and 0x7FFF (C8051F046/7). The Write/Erase Lock Byte is located at 0xFDFE (C8051F040/1/2/3/4/5) and 0x7FFE (C8051F046/7). Figure 15.1 shows the location and bit definitions of the security bytes. **The 512-byte sector containing the lock bytes can be written to, but not erased by software**. An attempted read of a read-locked byte returns undefined data. Debugging code in a read-locked sector is not possible through the JTAG interface.







#### Flash Read Lock Byte

Bits7-0: Each bit locks a corresponding block of memory. (Bit7 is MSB).

- 0: Read operations are locked (disabled) for corresponding block across the JTAG interface.
- 1: Read operations are unlocked (enabled) for corresponding block across the JTAG interface.

#### Flash Write/Erase Lock Byte

Bits7-0: Each bit locks a corresponding block of memory.

- 0: Write/Erase operations are locked (disabled) for corresponding block across the JTAG interface.
- 1: Write/Erase operations are unlocked (enabled) for corresponding block across the JTAG interface.

NOTE: When the highest block is locked, the security bytes may be written but not erased.

#### Flash access Limit Register (FLACL)

The content of this register is used as the high byte of the 16-bit Software Read Limit address. This 16-bit read limit address value is calculated as 0xNN00 where NN is replaced by content of this register on reset. Software running at or above this address is prohibited from using the MOVX and MOVC instructions to read, write, or erase Flash locations below this address. Any attempts to read locations below this limit will return the value 0x00.

Figure 15.1. Flash Program Memory Map and Security Bytes



The lock bits can always be read and cleared to logic 0 regardless of the security setting applied to the block containing the security bytes. This allows additional blocks to be protected after the block containing the security bytes has been locked. Important Note: The only means of removing a lock once set is to erase the entire program memory space by performing a JTAG erase operation (i.e., cannot be done in user firmware). Addressing either security byte while performing a JTAG erase operation will automatically initiate erasure of the entire program memory space (except for the reserved area). This erasure can only be performed via JTAG. If a non-security byte in the 0xFBFF-0xFDFF (C8051F040/1/2/3/4/5) or 0x7DFF-0x7FFF (C8051F046/7) page is addressed during the JTAG erasure, only that page (including the security bytes) will be erased.

The Flash Access Limit security feature (see Figure 15.1) protects proprietary program code and data from being read by software running on the C8051F04x. This feature provides support for OEMs that wish to program the MCU with proprietary value-added firmware before distribution. The value-added firmware can be protected while allowing additional code to be programmed in remaining program memory space later.

The Software Read Limit (SRL) is a 16-bit address that establishes two logical partitions in the program memory space. The first is an upper partition consisting of all the program memory locations at or above the SRL address, and the second is a lower partition consisting of all the program memory locations starting at 0x0000 up to (but excluding) the SRL address. Software in the upper partition can execute code in the lower partition, but is prohibited from reading locations in the lower partition using the MOVC instruction. (Executing a MOVC instruction from the upper partition with a source address in the lower partition will always return a data value of 0x00.) Software running in the lower partition can access locations in both the upper and lower partition without restriction.

The Value-added firmware should be placed in the lower partition. On reset, control is passed to the value-added firmware via the reset vector. Once the value-added firmware completes its initial execution, it branches to a predetermined location in the upper partition. If entry points are published, software running in the upper partition may execute program code in the lower partition, but it cannot read the contents of the lower partition. Parameters may be passed to the program code running in the lower partition either through the typical method of placing them on the stack or in registers before the call or by placing them in prescribed memory locations in the upper partition.

The SRL address is specified using the contents of the Flash Access Register. The 16-bit SRL address is calculated as 0xNN00, where NN is the contents of the SRL Security Register. Thus, the SRL can be located on 256-byte boundaries anywhere in program memory space. However, the 512-byte erase sector size essentially requires that a 512 boundary be used. The contents of a non-initialized SRL security byte is 0x00, thereby setting the SRL address to 0x0000 and allowing read access to all locations in program memory space by default.



#### 15.3.1. Summary of Flash Security Options

There are three Flash access methods supported on the C8051F04x devices; 1) Accessing Flash through the JTAG debug interface, 2) Accessing Flash from firmware residing below the Flash Access Limit, and 3) Accessing Flash from firmware residing at or above the Flash Access Limit.

Accessing Flash through the JTAG debug interface:

- 1. The Read and Write/Erase Lock bytes (security bytes) provide security for Flash access through the JTAG interface.
- 2. Any unlocked page may be read from, written to, or erased.
- 3. Locked pages cannot be read from, written to, or erased.
- 4. Reading the security bytes is always permitted.
- 5. Locking additional pages by writing to the security bytes is always permitted.
- 6. If the page containing the security bytes is **unlocked**, it can be directly erased. **Doing so will** reset the security bytes and unlock all pages of Flash.
- 7. If the page containing the security bytes is **locked**, it cannot be directly erased. **To unlock the page containing the security bytes**, **a full JTAG device erase is required**. A full JTAG device erase will erase all Flash pages, including the page containing the security bytes and the security bytes themselves.
- 8. The Reserved Area cannot be read from, written to, or erased at any time.

Accessing Flash from firmware residing below the Flash Access Limit:

- The Read and Write/Erase Lock bytes (security bytes) do not restrict Flash access from user firmware
- 2. Any page of Flash except the page containing the security bytes may be read from, written to, or erased
- 3. The page containing the security bytes cannot be erased. Unlocking pages of Flash can only be performed via the JTAG interface.
- 4. The page containing the security bytes may be read from or written to. Pages of Flash can be locked from JTAG access by writing to the security bytes.
- 5. The Reserved Area cannot be read from, written to, or erased at any time.

Accessing Flash from firmware residing at or above the Flash Access Limit:

- 1. The Read and Write/Erase Lock bytes (security bytes) do not restrict Flash access from user firmware.
- 2. Any page of Flash at or above the Flash Access Limit except the page containing the security bytes may be read from, written to, or erased.
- 3. Any page of Flash below the Flash Access Limit cannot be read from, written to, or erased.
- 4. Code branches to locations below the Flash Access Limit are permitted.
- 5. **The page containing the security bytes cannot be erased.** Unlocking pages of Flash can only be performed via the JTAG interface.
- 6. The page containing the security bytes may be read from or written to. Pages of Flash can be locked from JTAG access by writing to the security bytes.
- 7. The Reserved Area cannot be read from, written to, or erased at any time.



#### SFR Definition 15.1. FLACL: Flash Access Limit

R/W	Reset Value												
								00000000					
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:					
							SFR Addres	ss: 0xB7					
							SFR Page: F						

Bits 7-0: FLACL: Flash Access Limit.

This register holds the high byte of the 16-bit program memory read/write/erase limit address. The entire 16-bit access limit address value is calculated as 0xNN00 where NN is replaced by contents of FLACL. A write to this register sets the Flash Access Limit. This register can only be written once after any reset. Any subsequent writes are ignored until the next reset.

## SFR Definition 15.2. FLSCL: Flash Memory Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
FOSE	FRAE	Reserved	Reserved	Reserved	Reserved	Reserved	FLWE	10000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:
							SFR Address: SFR Page:	-
Bit7:	FOSE: Flash This is the ti 0: Flash One 1: Flash One	mer that tur e-Shot Time	ns off the ser disabled.	ense amps				
Bit6:	FRAE: Flash 0: Flash read 1: Flash read	ds occur as	necessary	•	_	).		
Bits5-1:	RESERVED	). Read = 00	0000b. Mus	•				
Bit0:	FLWE: Flash	h Write/Eras	se Enable					

This bit must be set to allow Flash writes/erases from user software.

0: Flash writes/erases disabled.

1: Flash writes/erases enabled.



## SFR Definition 15.3. PSCTL: Program Store Read/Write Control

R/W	Reset Value							
-	-	-	-	-	SFLE	PSEE	PSWE	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	SFR Address:

SFR Address: 0x8F SFR Page: 0

Bits7-3: UNUSED. Read = 00000b, Write = don't care.
Bit2: SFLE: Scratchpad Flash Memory Access Enable

When this bit is set, Flash reads and writes from user software are directed to the 128-byte Scratchpad Flash sector. When SFLE is set to logic 1, Flash accesses out of the address range 0x00-0x7F should not be attempted. Reads/Writes out of this range will yield undefined results.

0: Flash access from user software directed to the Program/Data Flash sector.1: Flash access from user software directed to the 128 byte Scratchpad sector.

Bit1: PSEE: Program Store Erase Enable.

Setting this bit allows an entire page of the Flash program memory to be erased provided the PSWE bit is also set. After setting this bit, a write to Flash memory using the MOVX instruction will erase the entire page that contains the location addressed by the MOVX instruction. The value of the data byte written does not matter. Note: The Flash page containing the Read Lock Byte and Write/Erase Lock Bytes cannot be erased by soft-

0: Flash program memory erasure disabled.

1: Flash program memory erasure enabled.

Bit0: PSWE: Program Store Write Enable.

Setting this bit allows writing a byte of data to the Flash program memory using the MOVX write instruction. The location must be erased prior to writing data.

0: Write to Flash program memory disabled. MOVX write operations target External RAM. 1: Write to Flash program memory enabled. MOVX write operations target Flash memory.





## 16. External Data Memory Interface and On-Chip XRAM

The C8051F04x MCUs include 4 kB of on-chip RAM mapped into the external data memory space (XRAM), as well as an External Data Memory Interface which can be used to access off-chip memories and memory-mapped devices connected to the GPIO ports. The external memory space may be accessed using the external move instruction (MOVX) and the data pointer (DPTR), or using the MOVX indirect addressing mode using R0 or R1. If the MOVX instruction is used with an 8-bit address operand (such as @R1), then the high byte of the 16-bit address is provided by the External Memory Interface Control Register (EMIOCN, shown in SFR Definition 16.1). **Note**: the MOVX instruction can also be used for writing to the Flash memory. See **Section "15. Flash Memory" on page 179** for details. The MOVX instruction accesses XRAM by default. The EMIF can be configured to appear on the lower GPIO Ports (P0-P3) or the upper GPIO Ports (P4-P7).

## 16.1. Accessing XRAM

The XRAM memory space is accessed using the MOVX instruction. The MOVX instruction has two forms, both of which use an indirect addressing method. The first method uses the Data Pointer, DPTR, a 16-bit register which contains the effective address of the XRAM location to be read from or written to. The second method uses R0 or R1 in combination with the EMI0CN register to generate the effective XRAM address. Examples of both of these methods are given below.

## 16.1.1. 16-Bit MOVX Example

The 16-bit form of the MOVX instruction accesses the memory location pointed to by the contents of the DPTR register. The following series of instructions reads the value of the byte at address 0x1234 into the accumulator A:

```
MOV DPTR, \#1234h ; load DPTR with 16-bit address to read (0x1234) MOVX A, @DPTR ; load contents of 0x1234 into accumulator A
```

The above example uses the 16-bit immediate MOV instruction to set the contents of DPTR. Alternately, the DPTR can be accessed through the SFR registers DPH, which contains the upper 8-bits of DPTR, and DPL, which contains the lower 8-bits of DPTR.

#### 16.1.2. 8-Bit MOVX Example

The 8-bit form of the MOVX instruction uses the contents of the EMI0CN SFR to determine the upper 8-bits of the effective address to be accessed and the contents of R0 or R1 to determine the lower 8-bits of the effective address to be accessed. The following series of instructions read the contents of the byte at address 0x1234 into the accumulator A.

```
MOV EMIOCN, #12h ; load high byte of address into EMIOCN MOV R0, #34h ; load low byte of address into R0 (or R1) MOVX a, @R0 ; load contents of 0x1234 into accumulator A
```



## 16.2. Configuring the External Memory Interface

Configuring the External Memory Interface consists of five steps:

- 1. Select EMIF on Low Ports (P3, P2, P1, and P0) or High Ports (P7, P6, P5, and P4).
- 2. Configure the Output Modes of the port pins as either push-pull or open-drain.
- 3. Select Multiplexed mode or Non-multiplexed mode.
- 4. Select the memory mode (on-chip only, split mode without bank select, split mode with bank select, or off-chip only).
- 5. Set up timing to interface with off-chip memory or peripherals.

Each of these five steps is explained in detail in the following sections. The Port selection, Multiplexed mode selection, and Mode bits are located in the EMIOCF register shown in SFR Definition 16.2.

#### 16.3. Port Selection and Configuration

The External Memory Interface can appear on Ports 3, 2, 1, and 0 (C8051F04x devices) or on Ports 7, 6, 5, and 4 (C8051F040/2/4/6 devices only), depending on the state of the PRTSEL bit (EMI0CF.5). If the lower Ports are selected, the EMIFLE bit (XBR2.1) must be set to a '1' so that the Crossbar will skip over P0.7 (/WR), P0.6 (/RD), and, if multiplexed mode is selected, P0.5 (ALE). For more information about the configuring the Crossbar, see **Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204**.

The External Memory Interface claims the associated Port pins for memory operations ONLY during the execution of an off-chip MOVX instruction. Once the MOVX instruction has completed, control of the Port pins reverts to the Port latches or to the Crossbar (on Ports 3, 2, 1, and 0). See Section "17. Port Input/Output" on page 203 for more information about the Crossbar and Port operation and configuration. The Port latches should be explicitly configured as push-pull to 'park' the External Memory Interface pins in a dormant state, most commonly by setting them to a logic 1.

During the execution of the MOVX instruction, the External Memory Interface will explicitly disable the drivers on all Port pins that are acting as Inputs (Data[7:0] during a READ operation, for example). The Output mode of the Port pins (whether the pin is configured as Open-Drain or Push-Pull) is unaffected by the External Memory Interface operation, and remains controlled by the PnMDOUT registers. In most cases, the output modes of all EMIF pins should be configured for push-pull mode. See Section "17.1.2. Configuring the Output Modes of the Port Pins" on page 206.



## SFR Definition 16.1. EMIOCN: External Memory Interface Control

R/W	Reset Value							
PGSEL7	PGSEL6	PGSEL5	PGSEL4	PGSEL3	PGSEL2	PGSEL1	PGSEL0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	•

SFR Address: 0xA2 SFR Page: 0

Bits7-0: PGSEL[7:0]: XRAM Page Select Bits.

The XRAM Page Select Bits provide the high byte of the 16-bit external data memory address when using an 8-bit MOVX command, effectively selecting a 256-byte page of

RAM.

0x00: 0x0000 to 0x00FF 0x01: 0x0100 to 0x01FF

...

0xFE: 0xFE00 to 0xFEFF 0xFF: 0xFF00 to 0xFFFF



## SFR Definition 16.2. EMI0CF: External Memory Configuration

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
-	-	PRTSEL	EMD2	EMD1	EMD0	EALE1	EALE0	00000011
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xA3 SFR Page: 0

Bits7-6: Unused. Read = 00b. Write = don't care.

Bit5: PRTSEL: EMIF Port Select.

0: EMIF active on P0-P3.

1: EMIF active on P4-P7.

Bit4: EMD2: EMIF Multiplex Mode Select.

0: EMIF operates in multiplexed address/data mode.

1: EMIF operates in non-multiplexed mode (separate address and data pins).

Bits3-2: EMD1-0: EMIF Operating Mode Select.

These bits control the operating mode of the External Memory Interface.

00: Internal Only: MOVX accesses on-chip XRAM only. All effective addresses alias to on-chip memory space.

- 01: Split Mode without Bank Select: Accesses below the 4k boundary are directed on-chip. Accesses above the 4k boundary are directed off-chip. 8-bit off-chip MOVX operations use the current contents of the Address High port latches to resolve upper address byte. Note that in order to access off-chip space, EMI0CN must be set to a page that is not contained in the on-chip address space.
- 10: Split Mode with Bank Select: Accesses below the 4k boundary are directed on-chip. Accesses above the 4k boundary are directed off-chip. 8-bit off-chip MOVX operations use the contents of EMI0CN to determine the high-byte of the address.
- 11: External Only: MOVX accesses off-chip XRAM only. On-chip XRAM is not visible to the CPU.

Bits1-0: EALE1-0: ALE Pulse-Width Select Bits (only has effect when EMD2 = 1).

00: ALE high and ALE low pulse width = 1 SYSCLK cycle.

01: ALE high and ALE low pulse width = 2 SYSCLK cycles.

10: ALE high and ALE low pulse width = 3 SYSCLK cycles.

11: ALE high and ALE low pulse width = 4 SYSCLK cycles.



### 16.4. Multiplexed and Non-multiplexed Selection

The External Memory Interface is capable of acting in a Multiplexed mode or a Non-multiplexed mode, depending on the state of the EMD2 (EMIOCF.4) bit.

#### 16.4.1. Multiplexed Configuration

In Multiplexed mode, the Data Bus and the lower 8-bits of the Address Bus share the same Port pins: AD[7:0]. In this mode, an external latch (74HC373 or equivalent logic gate) is used to hold the lower 8-bits of the RAM address. The external latch is controlled by the ALE (Address Latch Enable) signal, which is driven by the External Memory Interface logic. An example of a Multiplexed Configuration is shown in Figure 16.1.

In Multiplexed mode, the external MOVX operation can be broken into two phases delineated by the state of the ALE signal. During the first phase, ALE is high and the lower 8-bits of the Address Bus are presented to AD[7:0]. During this phase, the address latch is configured such that the 'Q' outputs reflect the states of the 'D' inputs. When ALE falls, signaling the beginning of the second phase, the address latch outputs remain fixed and are no longer dependent on the latch inputs. Later in the second phase, the Data Bus controls the state of the AD[7:0] port at the time /RD or /WR is asserted.

See Section "16.6.2. Multiplexed Mode" on page 199 for more information.




Figure 16.1. Multiplexed Configuration Example



### 16.4.2. Non-multiplexed Configuration

In Non-multiplexed mode, the Data Bus and the Address Bus pins are not shared. An example of a Non-multiplexed Configuration is shown in Figure 16.2. See **Section "16.6.1. Non-multiplexed Mode" on page 196** for more information about Non-multiplexed operation.




Figure 16.2. Non-multiplexed Configuration Example



### 16.5. Memory Mode Selection

The external data memory space can be configured in one of four modes, shown in Figure 16.3, based on the EMIF Mode bits in the EMIOCF register (SFR Definition 16.2). These modes are summarized below. More information about the different modes can be found in **Section "16.6. Timing" on page 194**.

#### 16.5.1. Internal XRAM Only

When EMIOCF.[3:2] are set to '00', all MOVX instructions will target the internal XRAM space on the device. Memory accesses to addresses beyond the populated space will wrap on 4k boundaries. As an example, the addresses 0x1000 and 0x2000 both evaluate to address 0x0000 in on-chip XRAM space.

- 8-bit MOVX operations use the contents of EMI0CN to determine the high-byte of the effective address and R0 or R1 to determine the low-byte of the effective address.
- 16-bit MOVX operations use the contents of the 16-bit DPTR to determine the effective address.

#### 16.5.2. Split Mode without Bank Select

When EMIOCF.[3:2] are set to '01', the XRAM memory map is split into two areas, on-chip space and off-chip space.

- Effective addresses below the 4k boundary will access on-chip XRAM space.
- Effective addresses above the 4k boundary will access off-chip space.
- 8-bit MOVX operations use the contents of EMI0CN to determine whether the memory access is onchip or off-chip. However, in the "No Bank Select" mode, an 8-bit MOVX operation will not drive the
  upper 8-bits A[15:8] of the Address Bus during an off-chip access. This allows the user to manipulate
  the upper address bits at will by setting the Port state directly via the port latches. This behavior is in
  contrast with "Split Mode with Bank Select" described below. The lower 8-bits of the Address Bus
  A[7:0] are driven, determined by R0 or R1.
- 16-bit MOVX operations use the contents of DPTR to determine whether the memory access is onchip or off-chip, and unlike 8-bit MOVX operations, the full 16-bits of the Address Bus A[15:0] are driven during the off-chip transaction.




Figure 16.3. EMIF Operating Modes



#### 16.5.3. Split Mode with Bank Select

When EMIOCF.[3:2] are set to '10', the XRAM memory map is split into two areas, on-chip space and off-chip space.

- Effective addresses below the 4k boundary will access on-chip XRAM space.
- Effective addresses above the 4k boundary will access off-chip space.
- 8-bit MOVX operations use the contents of EMI0CN to determine whether the memory access is onchip or off-chip. The upper 8-bits of the Address Bus A[15:8] are determined by EMI0CN, and the lower 8-bits of the Address Bus A[7:0] are determined by R0 or R1. All 16-bits of the Address Bus A[15:0] are driven in "Bank Select" mode.
- 16-bit MOVX operations use the contents of DPTR to determine whether the memory access is onchip or off-chip, and the full 16-bits of the Address Bus A[15:0] are driven during the off-chip transaction.

#### 16.5.4. External Only

When EMI0CF[3:2] are set to '11', all MOVX operations are directed to off-chip space. On-chip XRAM is not visible to the CPU. This mode is useful for accessing off-chip memory located between 0x0000 and the 4k boundary.

- 8-bit MOVX operations ignore the contents of EMI0CN. The upper Address bits A[15:8] are not driven (identical behavior to an off-chip access in "Split Mode without Bank Select" described above). This allows the user to manipulate the upper address bits at will by setting the Port state directly. The lower 8-bits of the effective address A[7:0] are determined by the contents of R0 or R1.
- 16-bit MOVX operations use the contents of DPTR to determine the effective address A[15:0]. The full 16-bits of the Address Bus A[15:0] are driven during the off-chip transaction.

## **16.6. Timing**

The timing parameters of the External Memory Interface can be configured to enable connection to devices having different setup and hold time requirements. The Address Setup time, Address Hold time, / RD and

/WR strobe widths, and in multiplexed mode, the width of the ALE pulse are all programmable in units of SYSCLK periods through EMIOTC, shown in SFR Definition 16.3, and EMIOCF[1:0].

The timing for an off-chip MOVX instruction can be calculated by adding 4 SYSCLK cycles to the timing parameters defined by the EMI0TC register. Assuming non-multiplexed operation, the minimum execution time for an off-chip XRAM operation is 5 SYSCLK cycles (1 SYSCLK for /RD or /WR pulse + 4 SYSCLKs). For multiplexed operations, the Address Latch Enable signal will require a minimum of 2 additional SYSCLK cycles. Therefore, the minimum execution time of an off-chip XRAM operation in multiplexed mode is 7 SYSCLK cycles (2 SYSCLKs for /ALE, 1 for /RD or /WR + 4 SYSCLKs). The programmable setup and hold times default to the maximum delay settings after a reset.

Table 16.1 lists the AC parameters for the External Memory Interface, and Figure 16.4 through Figure 16.9 show the timing diagrams for the different External Memory Interface modes and MOVX operations.



## **SFR Definition 16.3. EMIOTC: External Memory Timing Control**

R/W	Reset Value							
EAS1	EAS0	ERW3	EWR2	EWR1	EWR0	EAH1	EAH0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xA1 SFR Page: 0

Bits7-6: EAS1-0: EMIF Address Setup Time Bits.

00: Address setup time = 0 SYSCLK cycles. 01: Address setup time = 1 SYSCLK cycle. 10: Address setup time = 2 SYSCLK cycles. 11: Address setup time = 3 SYSCLK cycles.

Bits5-2: EWR3-0: EMIF /WR and /RD Pulse-Width Control Bits.

0000: /WR and /RD pulse width = 1 SYSCLK cycle. 0001: /WR and /RD pulse width = 2 SYSCLK cycles. 0010: /WR and /RD pulse width = 3 SYSCLK cycles. 0011: /WR and /RD pulse width = 4 SYSCLK cycles. 0100: /WR and /RD pulse width = 5 SYSCLK cycles. 0101: /WR and /RD pulse width = 6 SYSCLK cycles. 0110: /WR and /RD pulse width = 7 SYSCLK cycles. 0111: /WR and /RD pulse width = 8 SYSCLK cycles. 1000: /WR and /RD pulse width = 9 SYSCLK cycles. 1001: /WR and /RD pulse width = 10 SYSCLK cycles. 1010: /WR and /RD pulse width = 11 SYSCLK cycles. 1011: /WR and /RD pulse width = 12 SYSCLK cycles. 1100: /WR and /RD pulse width = 13 SYSCLK cycles. 1101: /WR and /RD pulse width = 14 SYSCLK cycles.

1110: /WR and /RD pulse width = 15 SYSCLK cycles. 1111: /WR and /RD pulse width = 16 SYSCLK cycles.

EAH1-0: EMIF Address Hold Time Bits. Bits1-0:

> 00: Address hold time = 0 SYSCLK cycles. 01: Address hold time = 1 SYSCLK cycle. 10: Address hold time = 2 SYSCLK cycles. 11: Address hold time = 3 SYSCLK cycles.



#### 16.6.1. Non-multiplexed Mode

16.6.1.1.16-bit MOVX: EMI0CF[4:2] = '101', '110', or '111'.





Figure 16.4. Non-multiplexed 16-bit MOVX Timing



16.6.1.2.8-bit MOVX without Bank Select: EMI0CF[4:2] = '101' or '111'.

#### Nonmuxed 8-bit WRITE without Bank Select



#### Nonmuxed 8-bit READ without Bank Select




Figure 16.5. Non-multiplexed 8-bit MOVX without Bank Select Timing



16.6.1.3.8-bit MOVX with Bank Select: EMI0CF[4:2] = '110'.




Figure 16.6. Non-multiplexed 8-bit MOVX with Bank Select Timing



### 16.6.2. Multiplexed Mode

16.6.2.1.16-bit MOVX: EMI0CF[4:2] = '001', '010', or '011'.




Figure 16.7. Multiplexed 16-bit MOVX Timing



16.6.2.2.8-bit MOVX without Bank Select: EMI0CF[4:2] = '001' or '011'.




Figure 16.8. Multiplexed 8-bit MOVX without Bank Select Timing



### 16.6.2.3.8-bit MOVX with Bank Select: EMI0CF[4:2] = '010'.




Figure 16.9. Multiplexed 8-bit MOVX with Bank Select Timing



**Table 16.1. AC Parameters for External Memory Interface** 

Parameter	Description	Min	Max	Units
T <sub>SYSCLK</sub>	System Clock Period	40	_	ns
T <sub>ACS</sub>	Address/Control Setup Time	0	3 x T <sub>SYSCLK</sub>	ns
T <sub>ACW</sub>	Address/Control Pulse Width	1 x T <sub>SYSCLK</sub>	16 x T <sub>SYSCLK</sub>	ns
T <sub>ACH</sub>	Address/Control Hold Time	0	3 x T <sub>SYSCLK</sub>	ns
T <sub>ALEH</sub>	Address Latch Enable High Time	1 x T <sub>SYSCLK</sub>	4 x T <sub>SYSCLK</sub>	ns
T <sub>ALEL</sub>	Address Latch Enable Low Time	1 x T <sub>SYSCLK</sub>	4 x T <sub>SYSCLK</sub>	ns
T <sub>WDS</sub>	Write Data Setup Time	1 x T <sub>SYSCLK</sub>	19 x T <sub>SYSCLK</sub>	ns
T <sub>WDH</sub>	Write Data Hold Time	0	3 x T <sub>SYSCLK</sub>	ns
T <sub>RDS</sub>	Read Data Setup Time	20	_	ns
T <sub>RDH</sub>	Read Data Hold Time	0	_	ns

# 17. Port Input/Output

The C8051F04x family of devices are fully integrated mixed-signal System on a Chip MCUs with 64 digital I/O pins (C8051F040/2/4/6) or 32 digital I/O pins (C8051F041/3/5/7), organized as 8-bit Ports. All ports are both bit- and byte-addressable through their corresponding Port Data registers. All Port pins are 5 V-tolerant, and all support configurable Open-Drain or Push-Pull output modes and weak pullups. A block diagram of the Port I/O cell is shown in Figure 17.1. Complete Electrical Specifications for the Port I/O pins are given in Table 17.1.




Figure 17.1. Port I/O Cell Block Diagram

#### Table 17.1. Port I/O DC Electrical Characteristics

 $V_{DD}$  = 2.7 to 3.6 V, -40 to +85 °C unless otherwise specified.

Parameter	Conditions	Min	Тур	Max	Units
Output High Voltage	I <sub>OH</sub> = -3 mA, Port I/O Push-Pull	$V_{DD} - 0.7$	_	_	
(V <sub>OH</sub> )	$I_{OH} = -10 \mu A$ , Port I/O Push-Pull	$V_{DD} - 0.1$	<u> </u>	_	V
(VOH)	I <sub>OH</sub> = -10 mA, Port I/O Push-Pull		$V_{DD} - 0.8$	_	
Output Law Valtage	I <sub>OL</sub> = 8.5 mA	_	_	0.6	
Output Low Voltage	I <sub>OL</sub> = 10 μA	_	_	0.1	V
(V <sub>OL</sub> )	I <sub>OL</sub> = 25 mA	_	1.0	_	
Input High Voltage (VIH)		0.7 x V <sub>DD</sub>	_	_	
Input Low Voltage (VIL)		_	_	0.3 x V <sub>DD</sub>	
	DGND < Port Pin < V <sub>DD</sub> , Pin Tri-state	_	_		
Input Leakage Current	Weak Pullup Off	_	_	± 1	μΑ
	Weak Pullup On	_	10	_	
Input Capacitance		_	5	_	pF



The C8051F04x family of devices have a wide array of digital resources which are available through the four lower I/O Ports: P0, P1, P2, and P3. Each of the pins on P0, P1, P2, and P3, can be defined as a General-Purpose I/O (GPIO) pin or can be controlled by a digital peripheral or function (like UART0 or /INT1 for example), as shown in Figure 17.2. The system designer controls which digital functions are assigned pins, limited only by the number of pins available. This resource assignment flexibility is achieved through the use of a Priority Crossbar Decoder. The state of a Port I/O pin can always be read from its associated Data register regardless of whether that pin has been assigned to a digital peripheral or behaves as GPIO. The Port pins on Ports 1, 2, and 3 can be used as Analog Inputs to ADC2 (C8051F040/1/2/3 only), Analog Voltage Comparators, and ADC0, respectively.




Figure 17.2. Port I/O Functional Block Diagram

An External Memory Interface, which is active during the execution of an off-chip MOVX instruction, can be active on either the lower Ports or the upper Ports. See **Section** "16. External Data Memory Interface and On-Chip XRAM" on page 187 for more information about the External Memory Interface.

#### 17.1. Ports 0 through 3 and the Priority Crossbar Decoder

The Priority Crossbar Decoder, or "Crossbar", allocates and assigns Port pins on Port 0 through Port 3 to the digital peripherals (UARTs, SMBus, PCA, Timers, etc.) on the device using a priority order. The Port pins are allocated in order starting with P0.0 and continue through P3.7, if necessary. The digital peripherals are assigned Port pins in a priority order which is listed in Figure 17.3, with UART0 having the highest priority and CNVSTR2 having the lowest priority.



P0											P1								Р	2							F	93				Crossbar Register Bits		
PIN I/O	0	1	2	3		5	6	7	0	1	2	3		5	6	5 7	7	0	1	2	3	4	5	6	7	0	1	2	3	4	5	6	7	Crossbar Register Bits
TX0	•																																	UART0EN: XBR0.2
RX0		•																																OAKTOEN. ABRO.2
SCK	•		•																															
MISO		•		•																														SPI0EN: XBR0.1
MOSI			•		•																													OI IOLIN. ADINO.1
NSS				•		•		NS	SS i	s no	ot a	ssig	gned	l to	a p	ort	pi	n w	he	n th	ie S	PI i	s pl	ace	d ir	ı 3-'	wir	e m	ode					
SDA	•		•	•	•	•	•																											SMB0EN: XBR0.0
SCL		•		•	•	•	•	•																										OMBOLN. ABIO.0
TX1	•		•	•	•	•	•	•	•																									UART1EN: XBR2.2
RX1		•		•	•	•	•	•	•	•																								OAKTIEN. ABIX2.2
CEX0	•		•	•	•	•	•	•	•	•	•																							
CEX1		•		•	•	•	•	•	•	•	•	•																						
CEX2			•		•	•	•	•	•	•	•	•	•																					PCA0ME: XBR0.[5:3]
CEX3				•		•	•	•	•	•	•	•	•	•																				FCAUME. ABRU.[3.3]
CEX4					•		•	•	•	•	•	•	•	•	•	•																		
CEX5						•		•	•	•	•	•	•	•	•	•	•																	
ECI	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•																ECI0E: XBR0.6
CP0	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•															CP0E: XBR0.7
CP1	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•														CP1E: XBR1.0
CP2	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•													CP2E: XBR3.3
T0	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•												T0E: XBR1.1
/INT0	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•											INT0E: XBR1.2
T1	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•										T1E: XBR1.3
/INT1	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•									INT1E: XBR1.4
T2	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•								T2E: XBR1.5
T2EX	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•							T2EXE: XBR1.6
T3	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•						T3E: XBR3.0
T3EX	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•					T3EXE: XBR3.1
T4	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•				T4E: XBR2.3
T4EX	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•	•	•	•	•	•			T4EXE: XBR2.4
/SYSCLK	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		SYSCKE: XBR1.7
CNVSTR0	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	CNVSTE0: XBR2.0
CNVSTR2	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	CNVSTE2: XBR3.2
						ALE	/RD	WR	≥ AIN1.0/A8	= LA = AIN1.1/A9	phdu AIN1.2/A10		u-u AIN1.4/A12						B A9m/A1	후 A10m/A2	± A11m/A3		ă A13m/A5	P A14m/A6	գ ր- A15m/A7	AD0/D0	axny AD1/D1	Q AD2/D2	ta/N	a-u AD4/D4	AD5/D5	9D/9De	™ AD7/D7	

Figure 17.3. Priority Crossbar Decode Table (EMIFLE = 0; P1MDIN = 0xFF)

#### 17.1.1. Crossbar Pin Assignment and Allocation

The Crossbar assigns Port pins to a peripheral if the corresponding enable bits of the peripheral are set to a logic 1 in the Crossbar configuration registers XBR0, XBR1, XBR2, and XBR3, shown in SFR Definition 17.1, SFR Definition 17.2, SFR Definition 17.3, and SFR Definition 17.4. For example, if the UART0EN bit (XBR0.2) is set to a logic 1, the TX0 and RX0 pins will be mapped to P0.0 and P0.1 respectively. Because UART0 has the highest priority, its pins will always be mapped to P0.0 and P0.1 when UART0EN is set to a logic 1. If a digital peripheral's enable bits are not set to a logic 1, then its ports are not accessible at the Port pins of the device. Also note that the Crossbar assigns pins to all associated functions when a serial communication peripheral is selected (i.e. SMBus, SPI, UART). It would be impossible, for example, to assign TX0 to a Port pin without assigning RX0 as well. Each combination of enabled peripherals results in a unique device pinout.

All Port pins on Ports 0 through 3 that are not allocated by the Crossbar can be accessed as General-Purpose I/O (GPIO) pins by reading and writing the associated Port Data registers (See SFR Definition 17.5.



SFR Definition 17.7, SFR Definition 17.10, and SFR Definition 17.13), a set of SFRs which are both byteand bit-addressable. The output states of Port pins that are allocated by the Crossbar are controlled by the digital peripheral that is mapped to those pins. Writes to the Port Data registers (or associated Port bits) will have no effect on the states of these pins.

A Read of a Port Data register (or Port bit) will always return the logic state present at the pin itself, regardless of whether the Crossbar has allocated the pin for peripheral use or not. An exception to this occurs during the execution of a *read-modify-write* instruction (ANL, ORL, XRL, CPL, INC, DEC, DJNZ, JBC, CLR, SET, and the bitwise MOV operation). During the *read* cycle of the *read-modify-write* instruction, it is the contents of the Port Data register, not the state of the Port pins themselves, which is read.

Because the Crossbar registers affect the pinout of the peripherals of the device, they are typically configured in the initialization code of the system before the peripherals themselves are configured. Once configured, the Crossbar registers are typically left alone.

Once the Crossbar registers have been properly configured, the Crossbar is enabled by setting XBARE (XBR2.4) to a logic 1. Until XBARE is set to a logic 1, the output drivers on Ports 0 through 3 are explicitly disabled in order to prevent possible contention on the Port pins while the Crossbar registers and other registers which can affect the device pinout are being written.

The output drivers on Crossbar-assigned input signals (like RX0, for example) are explicitly disabled; thus the values of the Port Data registers and the PnMDOUT registers have no effect on the states of these pins.

#### 17.1.2. Configuring the Output Modes of the Port Pins

The output drivers on Ports 0 through 3 remain disabled until the Crossbar is enabled by setting XBARE (XBR2.4) to a logic 1.

The output mode of each port pin can be configured to be either Open-Drain or Push-Pull. In the Push-Pull configuration, writing a logic 0 to the associated bit in the Port Data register will cause the Port pin to be driven to GND, and writing a logic 1 will cause the Port pin to be driven to  $V_{DD}$ . In the Open-Drain configuration, writing a logic 0 to the associated bit in the Port Data register will cause the Port pin to be driven to GND, and a logic 1 will cause the Port pin to assume a high-impedance state. The Open-Drain configuration is useful to prevent contention between devices in systems where the Port pin participates in a shared interconnection in which multiple outputs are connected to the same physical wire (like the SDA signal on an SMBus connection).

The output modes of the Port pins on Ports 0 through 3 are determined by the bits in the associated PnMDOUT registers (See SFR Definition 17.6, SFR Definition 17.9, SFR Definition 17.12, and SFR Definition 17.15). For example, a logic 1 in P3MDOUT.7 will configure the output mode of P3.7 to Push-Pull; a logic 0 in P3MDOUT.7 will configure the output mode of P3.7 to Open-Drain. All Port pins default to Open-Drain output.

The PnMDOUT registers control the output modes of the port pins regardless of whether the Crossbar has allocated the Port pin for a digital peripheral or not. The exceptions to this rule are: the Port pins connected to SDA, SCL, RX0 (if UART0 is in Mode 0), and RX1 (if UART1 is in Mode 0) are always configured as Open-Drain outputs, regardless of the settings of the associated bits in the PnMDOUT registers.

#### 17.1.3. Configuring Port Pins as Digital Inputs

A Port pin is configured as a digital input by setting its output mode to "Open-Drain" in the PnMDOUT register and writing a logic 1 to the associated bit in the Port Data register. For example, P3.7 is configured as

a digital input by setting P3MDOUT.7 to a logic 0, which selects open-drain output mode, and P3.7 to a logic 1, which disables the low-side output driver.

If the Port pin has been assigned to a digital peripheral by the Crossbar and that pin functions as an input (for example RX0, the UART0 receive pin), then the output drivers on that pin are automatically disabled.

#### 17.1.4. Weak Pullups

By default, each Port pin has an internal weak pullup device enabled which provides a resistive connection (about 100 k $\Omega$ ) between the pin and V<sub>DD</sub>. The weak pullup devices can be globally disabled by writing a logic 1 to the Weak Pullup Disable bit, (WEAKPUD, XBR2.7). The weak pullup is automatically deactivated on any pin that is driving a logic 0; that is, an output pin will not contend with its own pullup device. The weak pullup device can also be explicitly disabled on Ports 1, 2, and 3 pin by configuring the pin as an Analog Input, as described below.

### 17.1.5. Configuring Port 1, 2, and 3 Pins as Analog Inputs

The pins on Port 1 can serve as analog inputs to the ADC2 analog MUX (C8051F040/1/2/3 only), the pins on Port 2 can serve as analog inputs to the Comparators, and the pins on Port 3 can serve as inputs to ADC0. A Port pin is configured as an Analog Input by writing a logic 0 to the associated bit in the PnMDIN registers. All Port pins default to a Digital Input mode. Configuring a Port pin as an analog input:

- Disables the digital input path from the pin. This prevents additional power supply current from being drawn when the voltage at the pin is near V<sub>DD</sub> / 2. A read of the Port Data bit will return a logic 0 regardless of the voltage at the Port pin.
- 2. Disables the weak pullup device on the pin.
- 3. Causes the Crossbar to "skip over" the pin when allocating Port pins for digital peripherals.

Note that the output drivers on a pin configured as an Analog Input are not explicitly disabled. Therefore, the associated PnMDOUT bits of pins configured as Analog Inputs should explicitly be set to logic 0 (Open-Drain output mode), and the associated Port Data bits should be set to logic 1 (high-impedance). Also note that it is not required to configure a Port pin as an Analog Input in order to use it as an input to the ADC's or Comparators; however, it is strongly recommended. See the analog peripheral's corresponding section in this datasheet for further information.



#### 17.1.6. External Memory Interface Pin Assignments

If the External Memory Interface (EMIF) is enabled on the Low ports (Ports 0 through 3), EMIFLE (XBR2.5) should be set to a logic 1 so that the Crossbar will not assign peripherals to P0.7 (/WR), P0.6 (/RD), and, if the External Memory Interface is in Multiplexed mode, P0.5 (ALE). Figure 17.4 shows an example Crossbar Decode Table with EMIFLE=1 and the EMIF in Multiplexed mode. Figure 17.5 shows an example Crossbar Decode Table with EMIFLE=1 and the EMIF in Non-multiplexed mode.

If the External Memory Interface is enabled on the Low ports and an off-chip MOVX operation occurs, the External Memory Interface will control the output states (logic 1 or logic 0) of the affected Port pins during the execution phase of the MOVX instruction, regardless of the settings of the Crossbar registers or the Port Data registers. The output configuration (push-pull or open-drain) of the Port pins is not affected by the EMIF operation, except that Read operations will explicitly disable the output drivers on the Data Bus. In most cases, GPIO pins used in EMIF operations (especially the /WR and /RD lines) should be configured as push-pull and 'parked' at a logic 1 state. See Section "16. External Data Memory Interface and On-Chip XRAM" on page 187 for more information about the External Memory Interface.

PRINO	l: XBR0.2
RX0	
RX0 SCK MISO MOSI NSS NSS is not assigned to a port pin when the SPI is placed in 3-wire mode  SDA SCL SMB0EI  TX1 RX1 CEX0 CEX1 CEX2 CEX3 CEX4 CEX5 CEX4 CEX5 CEX6 CEX6 CEX7 CEX7 CEX7 CEX8 CEX8 CEX8 CEX8 CEX8 CEX8 CEX8 CEX8	
MISO MOSI  NSS  NSS is not assigned to a port pin when the SPI is placed in 3-wire mode  SMB0EI  TX1  RX1  CEX0  CEX1  CEX2  CEX3  CEX4  CEX5  EGI  CP0  CP1  CP1  CP2  TO  NT0  INT0  T1  INT1  T1  INT1  T2  T2EX  T3EX  T3EX  T3EX	l: XBR0.1
MOSI	I: XBR0.1
MOSI	i. ADIO.1
SDA SCL TX1 RX1 UART1EI  CEXO CEX2 CEX3 CEX4 CEX5 ECI CP1 CP2 T0 T0 T0 INT0 T1 INT1 T1 INT1 T2 T2EX T3 T3EX T3EX T3EX T3EX T3EX T3EX T3EX	
SCL	
TX1       UART1EI         RX1       UART1EI         CEX0       UART1EI         CEX1       CEX1         CEX2       CEX3         CEX4       CEX5         ECI       ECI         CP0       CP1         CP1       CP2         T0       CP2         T0       T0         INT0       INT0         T1       T1         I/INT1       T2         T2EX       T2EX         T3       T3EX	I. YRDOO
RX1 CEX0 CEX1 CEX2 CEX3 CEX4 CEX5 ECI CP0 CP1 CP1 CP2 CP2 TO INT0 INT0 T1 INT1 T2 T2EX T3EX T3EX T3EX T3EX CEX1 CEX1 CEX2 CEX3 CEX4 CEX5 CEX6 CEX7 CEX7 CEX7 CEX8 CEX8 CEX8 CEX8 CEX8 CEX8 CEX8 CEX8	i. ABRU.U
RX1 CEX0 CEX1 CEX2 CEX3 CEX4 CEX5 ECI CP0 CP1 CP2 T0 INT0 T1 INT1 T2 T2EX T3 T3EX T3EX T3EX T3EX T3EX T3EX T3EX	I. VDD2.2
CEX1 CEX2 CEX3 CEX4 CEX5 ECI	i. ADRZ.Z
CEX2 CEX3 CEX4 CEX5 ECI	
CEX3 CEX4 CEX5 ECI	
CEX3 CEX4 CEX5 ECI	. VDD0 (F 61
CEX5         CECI         CECI <td< td=""><td>:: XBK0.[5:3]</td></td<>	:: XBK0.[5:3]
ECI	
CP0 CP1 CP2 CP3 CP2 TO CP3 TO INTO T1 INT1 T2 T2EX T3 T3EX T3EX CP4 CP4 CP5 CP4 CP5 CP7 CP7 CP7 CP7 CP8 CP8 CP8 CP9	
CP1 CP2 CP2 TO TO INTO T1 INTO T2 T2EX T3 T3EX T3EX T3EX T3EX T3EX T3EX T2EX TCP1 CP2 TCP1 TCP1 TCP1 TCP1 TCP1 TCP1 TCP1 TCP1	: XBR0.6
CP2	: XBR0.7
TO	: XBR1.0
INTO	: XBR3.3
T1	: XBR1.1
/INT1       • • • • • • • • • • • • • • • • • • •	: XBR1.2
T2	: XBR1.3
T2EX	: XBR1.4
T3	: XBR1.5
T3EX • • • • • • • • • • • • • • • • • • •	: XBR1.6
	: XBR3.0
T4 • • • • • • • • • • • • • • • • • • •	: XBR3.1
	: XBR2.3
T4EX • • • • • T4EX	
/SYSCLK • • • • • SYSCKI	: XBR2.4
CNVSTRO • • • • • • CNVSTE	: XBR2.4 :: XBR1.7
CNVSTR2 • • • • • • • • • • • • • • • • • • •	
8 0 1 2 E 4 5	: XBR1.7
ALE  MR  AIN1.0/A8  AIN1.1/A9  AIN1.5/A15  AIN1.5/A15  AIN1.5/A15  AIN1.5/A15  AIN1.4/A12  AIN1.5/A15  AIN1.6/A14  AIN1.6/A14	: XBR1.7 ): XBR2.0
ALE ANN ANN ANN 1/48	: XBR1.7 ): XBR2.0
AIN1 Inputs/Non-muxed Addr H Muxed Addr H/Non-muxed Addr L Muxed Data/Non-muxed Data	: XBR1.7 ): XBR2.0

Figure 17.4. Priority Crossbar Decode Table

(EMIFLE = 1; EMIF in Multiplexed Mode; P1MDIN = 0xFF)



	0	P0									۲	1							Р	2							Р	3				Crosch	r Poni	ster Bits
TX0		1	2	3 4	5	(	6 7	0	1	2	3	4	5	6	7	0	1	2	3	4	5	6	7	0	1	2	3	4	5	6	7	CIOSSDE	i itegi	ster Dits
	•																															HADT	EN: XI	BBn 2
RX0		•																														UAKI	LIN. A	BKU.Z
SCK	•		•																															
MISO		•		•																												eni	EN: XI	BB0 4
MOSI			•	•																												371	EN: A	DKU. I
NSS				•	•			N	ISS i	is no	ot as	sign	ed to	a po	ort p	in v	vhei	n the	SP	I is p	olace	ed in	3-v	vire	mod	le								
SDA	•		•	• •	•			•																								CMD	EN: XI	BB0 0
SCL		•		• •	•			•	•																							SIVID	EN: A	DKU.U
TX1	•		•	• •	•			•	•	•																						HART	EN: XI	BB2 2
RX1		•		• •	•			•	•	•	•																					UAKI	EN: A	DKZ.Z
CEX0	•		•	• •	•			•	•	•	•	•																						
CEX1		•		• •	•			•	•	•	•	•	•																					
CEX2			•	•	•			•	•	•	•	•	•	•																		DOA	ME. V	DD0 [E-0]
CEX3				•	•			•	•	•	•	•	•	•	•																	PCA	WE: A	BR0.[5:3]
CEX4				•				•	•	•	•	•	•	•	•	•																		
CEX5					•				•	•	•	•	•	•	•	•	•																	
ECI	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•														EC	IOE: X	BR0.6
CP0	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•													C	POE: X	BR0.7
CP1	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•												C	1E: X	BR1.0
CP2	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•											С	2E: X	BR3.3
T0	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•											Γ0E: XI	BR1.1
/INT0	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•									IN	Γ0E: X	BR1.2
T1	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•									Γ1E: XI	BR1.3
/INT1	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•							IN	Γ1E: XI	BR1.4
T2	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•							Γ2E: XI	BR1.5
T2EX	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•					T28	XE: X	BR1.6
T3	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•					Γ3E: XI	BR3.0
T3EX	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•			Т31	XE: X	BR3.1
T4	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•			Γ4E: XI	BR2.3
T4EX	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	T48	XE: X	BR2.4
/SYSCLK	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	SYSC	KE: X	BR1.7
CNVSTR0	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	CNVS	Γ <b>Ε</b> 0: ΧΙ	BR2.0
CNVSTR2	•	•	•	• •	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	CNVS	Γ <b>E2</b> : XI	BR3.2
								œ	6	10	7	12	13	4	15																			
								AIN1.0/A8	AIN1.1/A9	AIN1.2/A10	AIN1.3/A11	AIN1.4/A12	AIN1.5/A13	AIN1.6/A14	AIN1.7/A15	AO	A.	A10m/A2	A11m/A3	/A4	A13m/A5	A14m/A6	A15m/A7	8	5	D2	D3	4	D5	90	D7			
					AF	1 9	WR WR	Σ	Σ	Σ	Σ̈́	Ž.	Ž.	Ž.	Ž.	A8m/A0	A9m/A1	10m	11m	A12m/A4	13m	14m	15n	AD0/D0	AD1/D1	AD2/D2	AD3/D3	AD4/D4	AD5/D5	AD6/D6	AD7/D7			
					A		< >					n-mu																	uxec					

Figure 17.5. Priority Crossbar Decode Table
(EMIFLE = 1; EMIF in Non-multiplexed Mode; P1MDIN = 0xFF)



### 17.1.7. Crossbar Pin Assignment Example

In this example (Figure 17.6), we configure the Crossbar to allocate Port pins for UART0, the SMBus, UART1, /INT0, and /INT1 (8 pins total). Additionally, we configure the External Memory Interface to operate in Multiplexed mode and to appear on the Low ports. Further, we configure P1.2, P1.3, and P1.4 for Analog Input mode so that the voltages at these pins can be measured by ADC2. The configuration steps are as follows:

- 1. XBR0, XBR1, and XBR2 are set such that UART0EN = 1, SMB0EN = 1, INT0E = 1, INT1E = 1, and EMIFLE = 1. Thus: XBR0 = 0x05, XBR1 = 0x14, and XBR2 = 0x02.
- 2. We configure the External Memory Interface to use Multiplexed mode and to appear on the Low ports. PRTSEL = 0, EMD2 = 0.
- 3. We configure the desired Port 1 pins to Analog Input mode by setting P1MDIN to 0xE3 (P1.4, P1.3, and P1.2 are Analog Inputs, so their associated P1MDIN bits are set to logic 0).
- 4. We enable the Crossbar by setting XBARE = 1: XBR2 = 0x42.
  - UART0 has the highest priority, so P0.0 is assigned to TX0, and P0.1 is assigned to RX0.
  - The SMBus is next in priority order, so P0.2 is assigned to SDA, and P0.3 is assigned to SCL.
  - UART1 is next in priority order, so P0.4 is assigned to TX1. Because the External Memory Interface is selected on the lower Ports, EMIFLE = 1, which causes the Crossbar to skip P0.6 (/RD) and P0.7 (/WR). Because the External Memory Interface is configured in Multiplexed mode, the Crossbar will also skip P0.5 (ALE). RX1 is assigned to the next non-skipped pin, which in this case is P1.0.
  - /INT0 is next in priority order, so it is assigned to P1.1.
  - P1MDIN is set to 0xE3, which configures P1.2, P1.3, and P1.4 as Analog Inputs, causing the Crossbar to skip these pins.
  - /INT1 is next in priority order, so it is assigned to the next non-skipped pin, which is P1.5.
  - The External Memory Interface will drive Ports 2 and 3 (denoted by red dots in Figure 17.6) during the execution of an off-chip MOVX instruction.
- 5. We set the UART0 TX pin (TX0, P0.0) and UART1 TX pin (TX1, P0.4) outputs to Push-Pull by setting P0MDOUT = 0x11.
- 6. We configure all EMIF-controlled pins to push-pull output mode by setting P0MDOUT |= 0xE0; P2MDOUT = 0xFF; P3MDOUT = 0xFF.
- 7. We explicitly disable the output drivers on the 3 Analog Input pins by setting P1MDOUT = 0x00 (configure outputs to Open-Drain) and P1 = 0xFF (a logic 1 selects the high-impedance state).






Figure 17.6. Crossbar Example:

(EMIFLE = 1; EMIF in Multiplexed Mode; P1MDIN = 0xE3; XBR0 = 0x05; XBR1 = 0x14; XBR2 = 0x42)



## SFR Definition 17.1. XBR0: Port I/O Crossbar Register 0

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
CP0E	ECI0E		PCA0ME		UART0EN	SPI0EN	SMB0EN	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	•

SFR Address: 0xE1 SFR Page: F

Bit7: CP0E: Comparator 0 Output Enable Bit.

0: CP0 unavailable at Port pin.1: CP0 routed to Port pin.

Bit6: ECI0E: PCA0 External Counter Input Enable Bit.

0: PCA0 External Counter Input unavailable at Port pin.1: PCA0 External Counter Input (ECI0) routed to Port pin.

Bits5-3: PCA0ME: PCA0 Module I/O Enable Bits.

000: All PCA0 I/O unavailable at port pins.

001: CEX0 routed to port pin.

010: CEX0, CEX1 routed to 2 port pins.

011: CEX0, CEX1, and CEX2 routed to 3 port pins.

100: CEX0, CEX1, CEX2, and CEX3 routed to 4 port pins.

101: CEX0, CEX1, CEX2, CEX3, and CEX4 routed to 5 port pins.

110: CEX0, CEX1, CEX2, CEX3, CEX4, and CEX5 routed to 6 port pins.

Bit2: UART0EN: UART0 I/O Enable Bit.

0: UART0 I/O unavailable at Port pins.

1: UART0 TX routed to P0.0, and RX routed to P0.1.

Bit1: SPI0EN: SPI0 Bus I/O Enable Bit.

0: SPI0 I/O unavailable at Port pins.

1: SPI0 SCK, MISO, MOSI, and NSS routed to 4 Port pins. Note that the NSS signal is not

assigned to a port pin if the SPI is in 3-wire mode. See Section "20. Enhanced Serial

Peripheral Interface (SPI0)" on page 255 for more information.

Bit0: SMB0EN: SMBus0 Bus I/O Enable Bit.

0: SMBus0 I/O unavailable at Port pins.

1: SMBus0 SDA and SCL routed to 2 Port pins.

## SFR Definition 17.2. XBR1: Port I/O Crossbar Register 1

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
SYSCKE	T2EXE	T2E	INT1E	T1E	INT0E	T0E	CP1E	00000000
Rit7	Rit6	Rit5	Rit4	Rit3	Rit2	Rit1	Rit∩	<del>_</del>

SFR Address: 0xE2 SFR Page: F

Bit7: SYSCKE: /SYSCLK Output Enable Bit.

0: /SYSCLK unavailable at Port pin.

1: /SYSCLK routed to Port pin.

Bit6: T2EXE: T2EX Input Enable Bit.

0: T2EX unavailable at Port pin.

1: T2EX routed to Port pin.

Bit5: T2E: T2 Input Enable Bit.

0: T2 unavailable at Port pin.

1: T2 routed to Port pin.

Bit4: INT1E: /INT1 Input Enable Bit.

0: /INT1 unavailable at Port pin.

1: /INT1 routed to Port pin.

Bit3: T1E: T1 Input Enable Bit.

0: T1 unavailable at Port pin.

1: T1 routed to Port pin.

Bit2: INT0E: /INT0 Input Enable Bit.

0: /INT0 unavailable at Port pin.

1: /INT0 routed to Port pin.

Bit1: T0E: T0 Input Enable Bit.

0: T0 unavailable at Port pin.

1: T0 routed to Port pin.

Bit0: CP1E: CP1 Output Enable Bit.

0: CP1 unavailable at Port pin.

1: CP1 routed to Port pin.



## SFR Definition 17.3. XBR2: Port I/O Crossbar Register 2

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
WEAKPUD	XBARE	_	T4EXE	T4E	UART1E	EMIFLE	CNVST0E	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xE3 SFR Page: F

Bit7: WEAKPUD: Weak PullUp Disable Bit.

0: Weak pullups globally enabled.

1: Weak pullups globally disabled.

Bit6: XBARE: Crossbar Enable Bit.

0: Crossbar disabled. All pins on Ports 0, 1, 2, and 3, are forced to Input mode.

1: Crossbar enabled.

Bit5: UNUSED. Read = 0, Write = don't care.

Bit4: T4EXE: T4EX Input Enable Bit.

0: T4EX unavailable at Port pin.

1: T4EX routed to Port pin.

Bit3: T4E: T4 Input Enable Bit.

0: T4 unavailable at Port pin.

1: T4 routed to Port pin.

Bit2: UART1E: UART1 I/O Enable Bit.

0: UART1 I/O unavailable at Port pins.

1: UART1 TX and RX routed to 2 Port pins.

Bit1: EMIFLE: External Memory Interface Low-Port Enable Bit.

0: P0.7, P0.6, and P0.5 functions are determined by the Crossbar or the Port latches.

1: If EMIOCF.4 = '0' (External Memory Interface is in Multiplexed mode)

P0.7 (/WR), P0.6 (/RD), and P0.5 (ALE) are 'skipped' by the Crossbar and their output states are determined by the Port latches and the External Memory Interface.

1: If EMIOCF.4 = '1' (External Memory Interface is in Non-multiplexed mode)

P0.7 (/WR) and P0.6 (/RD) are 'skipped' by the Crossbar and their output states are

determined by the Port latches and the External Memory Interface.

Bit0: CNVST0E: ADC0 External Convert Start Input Enable Bit.

0: CNVST0 for ADC0 unavailable at Port pin.

1: CNVST0 for ADC0 routed to Port pin.



### SFR Definition 17.4. XBR3: Port I/O Crossbar Register 3

R/W	R	R	R	R/W	R/W	R/W	R/W	Reset Value
CTXOUT	_	_	_	CP2E	CNVST2E	T3EXE	T3E	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xE4 SFR Page: F

Bit7: CTXOUT: CAN Transmit Pin (CTX) Output Mode.

0: CTX pin output mode is configured as open-drain.1: CTX pin output mode is configured as push-pull.

Bit6-4: Reserved

Bit3: CP2E: CP2 Output Enable Bit.

0: CP2 unavailable at Port pin.

1: CP2 routed to Port pin.

Bit2: CNVST2E: ADC2 External Convert Start Input Enable Bit (C8051F040/1/2/3 only).

0: CNVST2 for ADC2 unavailable at Port pin.

1: CNVST2 for ADC2 routed to Port pin.

Bit1: T3EXE: T3EX Input Enable Bit.

0: T3EX unavailable at Port pin.1: T3EX routed to Port pin.

Bit0: T3E: T3 Input Enable Bit.

0: T3 unavailable at Port pin.

1: T3 routed to Port pin.

#### SFR Definition 17.5. P0: Port0 Data

R/W	Reset Value							
P0.7	P0.6	P0.5	P0.4	P0.3	P0.2	P0.1	P0.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0x80 SFR Page: All Pages

Bits7-0: P0.[7:0]: Port0 Output Latch Bits.

(Write - Output appears on I/O pins per XBR0, XBR1, XBR2, and XBR3 Registers)

0: Logic Low Output.

1: Logic High Output (open if corresponding P0MDOUT.n bit = 0).

(Read - Regardless of XBR0, XBR1, XBR2, and XBR3 Register settings).

0: P0.n pin is logic low.1: P0.n pin is logic high.

Note: P0.7 (/WR), P0.6 (/RD), and P0.5 (ALE) can be driven by the External Data Memory Interface. See **Section "16. External Data Memory Interface and On-Chip XRAM" on page 187** for more information. See also SFR Definition 17.3 for information about configuring the Crossbar for External Memory accesses.



### SFR Definition 17.6. P0MDOUT: Port0 Output Mode

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xA4 SFR Page: F

Bits7-0: P0MDOUT.[7:0]: Port0 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.1: Port Pin output mode is configured as Push-Pull.

Note: SDA, SCL, and RX0 (when UART0 is in Mode 0) and RX1 (when UART1 is in Mode 0) are

always configured as Open-Drain when they appear on Port pins.

#### SFR Definition 17.7. P1: Port1 Data

R/W	Reset Value							
P1.7	P1.6	P1.5	P1.4	P1.3	P1.2	P1.1	P1.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0x90 SFR Page: All Pages

Bits7-0: P1.[7:0]: Port1 Output Latch Bits.

(Write - Output appears on I/O pins per XBR0, XBR1, XBR2, and XBR3 Registers)

0: Logic Low Output.

1: Logic High Output (open if corresponding P1MDOUT.n bit = 0).

(Read - Regardless of XBR0, XBR1, XBR2, and XBR3 Register settings).

0: P1.n pin is logic low.

1: P1.n pin is logic high.

#### Notes:

P1.[7:0] can be configured as inputs to ADC1 as AIN1.[7:0], in which case they are 'skipped' by the Crossbar assignment process and their digital input paths are disabled, depending on P1MDIN (See SFR Definition 17.8). Note that in analog mode, the output mode of the pin is determined by the Port 1 latch and P1MDOUT (SFR Definition 17.9). See Section "7. 8-Bit ADC (ADC2, C8051F040/1/2/3 Only)" on page 91 for more information about ADC2.

P1.[7:0] can be driven by the External Data Memory Interface (as Address[15:8] in Non-multiplexed mode). See Section "16. External Data Memory Interface and On-Chip XRAM" on page 187 for more information about the External Memory Interface.



### SFR Definition 17.8. P1MDIN: Port1 Input Mode

R/W	Reset Value							
								11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xAD SFR Page: F

Bits7-0: P1MDIN.[7:0]: Port 1 Input Mode Bits.

0: Port Pin is configured in Analog Input mode. The digital input path is disabled (a read from the Port bit will always return '0'). The weak pullup on the pin is disabled.

1: Port Pin is configured in Digital Input mode. A read from the Port bit will return the logic level at the Pin. The state of the weak pullup is determined by the WEAKPUD bit (XBR2.7, see SFR Definition 17.3).

### SFR Definition 17.9. P1MDOUT: Port1 Output Mode

	R/W	Reset Value							
									00000000
-	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xA5 SFR Page: F

Bits7-0: P1MDOUT.[7:0]: Port1 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.1: Port Pin output mode is configured as Push-Pull.

Note: SDA, SCL, and RX0 (when UART0 is in Mode 0) and RX1 (when UART1 is in Mode 0) are

always configured as Open-Drain when they appear on Port pins.



### SFR Definition 17.10. P2: Port2 Data

Reset Value	R/W							
11111111	P2.0	P2.1	P2.2	P2.3	P2.4	P2.5	P2.6	P2.7
Bit Addessable	Bit0	Bit1	Bit2	Bit3	Bit4	Bit5	Bit6	Bit7

SFR Address: 0xA0 SFR Page: All Pages

Bits7-0: P2.[7:0]: Port2 Output Latch Bits.

(Write - Output appears on I/O pins per XBR0, XBR1, XBR2, and XBR3 Registers)

0: Logic Low Output.

1: Logic High Output (open if corresponding P2MDOUT.n bit = 0).

(Read - Regardless of XBR0, XBR1, XBR2, and XBR3 Register settings).

0: P2.n pin is logic low.1: P2.n pin is logic high.

Note: P2.[7:0] can be driven by the External Data Memory Interface (as Address[15:8] in Multi-

plexed mode, or as Address[7:0] in Non-multiplexed mode). See Section "16. External Data Memory Interface and On-Chip XRAM" on page 187 for more information about the

External Memory Interface.

### SFR Definition 17.11. P2MDIN: Port2 Input Mode

R/W	Reset Value							
								11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>
							SFR Addres	s: 0xAE

SFR Page: F

Bits7-0: P1MDIN.[7:0]: Port 2 Input Mode Bits.

0: Port Pin is configured in Analog Input mode. The digital input path is disabled (a read from the Port bit will always return '0'). The weak pullup on the pin is disabled.

1: Port Pin is configured in Digital Input mode. A read from the Port bit will return the logic level at the Pin. The state of the weak pullup is determined by the WEAKPUD bit (XBR2.7, see SFR Definition 17.3).



### SFR Definition 17.12. P2MDOUT: Port2 Output Mode

	R/W	Reset Value							
									00000000
-	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>_</del>

SFR Address: 0xA6 SFR Page: F

Bits7-0: P2MDOUT.[7:0]: Port2 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.1: Port Pin output mode is configured as Push-Pull.

Note: SDA, SCL, and RX0 (when UART0 is in Mode 0) and RX1 (when UART1 is in Mode 0) are

always configured as Open-Drain when they appear on Port pins.

### SFR Definition 17.13. P3: Port3 Data

R/W	Reset Value							
P3.7	P3.6	P3.5	P3.4	P3.3	P3.2	P3.1	P3.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xB0 SFR Page: All Pages

Bits7-0: P3.[7:0]: Port3 Output Latch Bits.

(Write - Output appears on I/O pins per XBR0, XBR1, XBR2, and XBR3 Registers)

0: Logic Low Output.

1: Logic High Output (open if corresponding P3MDOUT.n bit = 0).

(Read - Regardless of XBR0, XBR1, XBR2, and XBR3 Register settings).

0: P3.n pin is logic low.

1: P3.n pin is logic high.

Note: P3.[7:0] can be driven by the External Data Memory Interface (as AD[7:0] in Multiplexed

mode, or as D[7:0] in Non-multiplexed mode). See **Section "16. External Data Memory Interface and On-Chip XRAM" on page 187** for more information about the External Mem-

ory Interface.



### SFR Definition 17.14. P3MDIN: Port3 Input Mode

R/W	Reset Value							
								11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xAF SFR Page: F

Bits7-0: P1MDIN.[7:0]: Port 3 Input Mode Bits.

0: Port Pin is configured in Analog Input mode. The digital input path is disabled (a read from the Port bit will always return '0'). The weak pullup on the pin is disabled.

1: Port Pin is configured in Digital Input mode. A read from the Port bit will return the logic level at the Pin. The state of the weak pullup is determined by the WEAKPUD bit (XBR2.7, see SFR Definition 17.3).

### SFR Definition 17.15. P3MDOUT: Port3 Output Mode

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value		
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0			
SFR Address: 0xA7 SFR Page: F										
Bits7-0: P2MDOUT.[7:0]: Port3 Output Mode Bits. 0: Port Pin output mode is configured as Open-Drain. 1: Port Pin output mode is configured as Push-Pull.										

### 17.2. Ports 4 through 7

On C8051F040/2/4/6 devices, all Port pins on Ports 4 through 7 can be accessed as General-Purpose I/O (GPIO) pins by reading and writing the associated Port Data registers (See SFR Definition 17.16, SFR Definition 17.18, SFR Definition 17.20, and SFR Definition 17.22 **located on SFR Page F**), a set of SFRs which are both bit and byte-addressable.

A Read of a Port Data register (or Port bit) will always return the logic state present at the pin itself, regardless of whether the Crossbar has allocated the pin for peripheral use or not. An exception to this occurs during the execution of a *read-modify-write* instruction (ANL, ORL, XRL, CPL, INC, DEC, DJNZ, JBC, CLR, SET, and the bitwise MOV operation). During the *read* cycle of the *read-modify-write* instruction, it is the contents of the Port Data register, not the state of the Port pins themselves, which is read.



### 17.2.1. Configuring Ports Which are Not Pinned Out

Although P4, P5, P6, and P7 are not brought out to pins on the C8051F041/3/5/7 devices, the Port Data registers are still present and can be used by software. Because the digital input paths also remain active, it is recommended that these pins not be left in a 'floating' state in order to avoid unnecessary power dissipation arising from the inputs floating to non-valid logic levels. This condition can be prevented by any of the following:

- 1. Leave the weak pullup devices enabled by setting WEAKPUD (XBR2.7) to a logic 0.
- 2. Configure the output modes of P4, P5, P6, and P7 to "Push-Pull" by writing PnOUT = 0xFF.
- 3. Force the output states of P4, P5, P6, and P7 to logic 0 by writing zeros to the Port Data registers: P4 = 0x00, P5 = 0x00, P6 = 0x00, and P7 = 0x00.

### 17.2.2. Configuring the Output Modes of the Port Pins

The output mode of each port pin can be configured to be either Open-Drain or Push-Pull. In the Push-Pull configuration, a logic 0 in the associated bit in the Port Data register will cause the Port pin to be driven to GND, and a logic 1 will cause the Port pin to be driven to V<sub>DD</sub>. In the Open-Drain configuration, a logic 0 in the associated bit in the Port Data register will cause the Port pin to be driven to GND, and a logic 1 will cause the Port pin to assume a high-impedance state. The Open-Drain configuration is useful to prevent contention between devices in systems where the Port pin participates in a shared interconnection in which multiple outputs are connected to the same physical wire.

The output modes of the Port pins on Ports 4 through 7 are determined by the bits in their respective PnMDOUT Output Mode Registers. Each bit in PnMDOUT controls the output mode of its corresponding port pin (see SFR Definition 17.17, SFR Definition 17.19, SFR Definition 17.21, and SFR Definition 17.23). For example, to place Port pin 4.3 in push-pull mode (digital output), set P4MDOUT.3 to logic 1. All port pins default to open-drain mode upon device reset.

### 17.2.3. Configuring Port Pins as Digital Inputs

A Port pin is configured as a digital input by setting its output mode to "Open-Drain" in the PnMDOUT register and writing a logic 1 to the associated bit in the Port Data register. For example, P7.7 is configured as a digital input by setting P7MDOUT.7 to a logic 0, which selects open-drain output mode, and P3.7 to a logic 1, which disables the low-side output driver.

### 17.2.4. Weak Pullups

By default, each Port pin has an internal weak pullup device enabled which provides a resistive connection (about 100  $\rm k\Omega$ ) between the pin and V<sub>DD</sub>. The weak pullup devices can be globally disabled by writing a logic 1 to the Weak Pullup Disable bit, (WEAKPUD, XBR2.7). The weak pullup is automatically deactivated on any pin that is driving a logic 0; that is, an output pin will not contend with its own pullup device.

### 17.2.5. External Memory Interface

If the External Memory Interface (EMIF) is enabled on the High ports (Ports 4 through 7), EMIFLE (XBR2.5) should be set to a logic 0.

If the External Memory Interface is enabled on the High ports and an off-chip MOVX operation occurs, the External Memory Interface will control the output states of the affected Port pins during the execution phase of the MOVX instruction, regardless of the settings of the Port Data registers. The output configuration of the Port pins is not affected by the EMIF operation, except that Read operations will explicitly disable the output drivers on the Data Bus during the MOVX execution. See **Section "16. External Data Memory Interface and On-Chip XRAM" on page 187** for more information about the External Memory Interface.



### SFR Definition 17.16. P4: Port4 Data

R/W	Reset Value							
P4.7	P4.6	P4.5	P4.4	P4.3	P4.2	P4.1	P4.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xC8 SFR Page: F

Bits7-0: P4.[7:0]: Port4 Output Latch Bits.

Write - Output appears on I/O pins.

0: Logic Low Output.

1: Logic High Output (Open-Drain if corresponding P4MDOUT.n bit = 0). See SFR Definition

17.17.

Read - Returns states of I/O pins.

0: P4.n pin is logic low.

1: P4.n pin is logic high.

Note: P4.7 (/WR), P4.6 (/RD), and P4.5 (ALE) can be driven by the External Data Memory Interface. See **Section** "16. External Data Memory Interface and On-Chip XRAM" on page 187 for more information.

### SFR Definition 17.17. P4MDOUT: Port4 Output Mode

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>

SFR Address: 0x9C SFR Page: F

Bits7-0: P4MDOUT.[7:0]: Port4 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.1: Port Pin output mode is configured as Push-Pull.



### SFR Definition 17.18. P5: Port5 Data

R/W	Reset Value							
P5.7	P5.6	P5.5	P5.4	P5.3	P5.2	P5.1	P5.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xD8 SFR Page: F

Bits7-0: P5.[7:0]: Port5 Output Latch Bits.

Write - Output appears on I/O pins.

0: Logic Low Output.

1: Logic High Output (Open-Drain if corresponding P5MDOUT bit = 0). See SFR Definition

17.19.

Read - Returns states of I/O pins.

0: P5.n pin is logic low.

1: P5.n pin is logic high.

Note: P5.[7:0] can be driven by the External Data Memory Interface (as Address[15:8] in Non-multiplexed mode). See **Section "16. External Data Memory Interface and On-Chip XRAM"** 

on page 187 for more information about the External Memory Interface.

### SFR Definition 17.19. P5MDOUT: Port5 Output Mode

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>
							055 4 1 1	0.00

SFR Address: 0x9D SFR Page: F

Bits7-0: P5MDOUT.[7:0]: Port5 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.1: Port Pin output mode is configured as Push-Pull.



### SFR Definition 17.20. P6: Port6 Data

R/W	Reset Value							
P6.7	P6.6	P6.5	P6.4	P6.3	P6.2	P6.1	P6.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xE8 SFR Page: F

Bits7-0: P6.[7:0]: Port6 Output Latch Bits.

Write - Output appears on I/O pins.

0: Logic Low Output.

1: Logic High Output (Open-Drain if corresponding P6MDOUT bit = 0). See SFR Definition

17.21.

Read - Returns states of I/O pins.

0: P6.n pin is logic low.

1: P6.n pin is logic high.

P6.[7:0] can be driven by the External Data Memory Interface (as Address[15:8] in Multi-Note:

plexed mode, or as Address[7:0] in Non-multiplexed mode). See Section "16. External Data Memory Interface and On-Chip XRAM" on page 187 for more information about the

External Memory Interface.

### SFR Definition 17.21. P6MDOUT: Port6 Output Mode

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>
							SER Addres	e: 0v0E

SFR Page: F

Bits7-0: P6MDOUT.[7:0]: Port6 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.

1: Port Pin output mode is configured as Push-Pull.



### SFR Definition 17.22. P7: Port7 Data

R/W	Reset Value							
P7.7	P7.6	P7.5	P7.4	P7.3	P7.2	P7.1	P7.0	11111111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xF8 SFR Page: F

Bits7-0: P7.[7:0]: Port7 Output Latch Bits.

Write - Output appears on I/O pins.

0: Logic Low Output.

1: Logic High Output (Open-Drain if corresponding P7MDOUT bit = 0). See SFR Definition

17.23.

Read - Returns states of I/O pins.

0: P7.n pin is logic low.1: P7.n pin is logic high.

Note: P7.[7:0] can be driven by the External Data Memory Interface (as AD[7:0] in Multiplexed

mode, or as D[7:0] in Non-multiplexed mode). See **Section "16. External Data Memory Interface and On-Chip XRAM" on page 187** for more information about the External Mem-

ory Interface.

### SFR Definition 17.23. P7MDOUT: Port7 Output Mode

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u>—</u>

SFR Address: 0x9F SFR Page: F

Bits7-0: P7MDOUT.[7:0]: Port7 Output Mode Bits.

0: Port Pin output mode is configured as Open-Drain.1: Port Pin output mode is configured as Push-Pull.

Note: SDA, SCL, and RX0 (when UART0 is in Mode 0) and RX1 (when UART1 is in Mode 0) are

always configured as Open-Drain when they appear on Port pins.





### 18. Controller Area Network (CAN0)

**IMPORTANT DOCUMENTATION NOTE:** The Bosch CAN Controller is integrated in the C8051F04x Family of devices. This section of the data sheet gives a description of the CAN controller as an overview and offers a description of how the Silicon Labs CIP-51 MCU interfaces with the on-chip Bosch CAN controller. In order to use the CAN controller, please refer to Bosch's C\_CAN User's Manual (revision 1.2) as an accompanying manual to Silicon Labs' C8051F04x Data sheet.

The C8051F04x family of devices feature a Control Area Network (CAN) controller that enables serial communication using the CAN protocol. Silicon Labs CAN facilitates communication on a CAN network in accordance with the Bosch specification 2.0A (basic CAN) and 2.0B (full CAN). The CAN controller consists of a CAN Core, Message RAM (separate from the CIP-51 RAM), a message handler state machine, and control registers. Silicon Labs CAN is a protocol controller and does not provide physical layer drivers (i.e., transceivers). Figure 18.1 shows an example typical configuration on a CAN bus.

Silicon Labs CAN operates at bit rates of up to 1 Mbit/second, though this can be limited by the physical layer chosen to transmit data on the CAN bus. The CAN processor has 32 Message Objects that can be configured to transmit or receive data. Incoming data, message objects and their identifier masks are stored in the CAN message RAM. All protocol functions for transmission of data and acceptance filtering is performed by the CAN controller and not by the CIP-51 MCU. In this way, minimal CPU bandwidth is needed to use CAN communication. The CIP-51 configures the CAN controller, accesses received data, and passes data for transmission via Special Function Registers (SFRs) in the CIP-51.




Figure 18.1. Typical CAN Bus Configuration



### 18.1. Bosch CAN Controller Operation

The CAN Controller featured in the C8051F04x family of devices is a full implementation of Bosch's full CAN module and fully complies with CAN specification 2.0B. A block diagram of the CAN controller is shown in Figure 18.2. The CAN Core provides shifting (CANTX and CANRX), serial/parallel conversion of messages, and other protocol related tasks such as transmission of data and acceptance filtering. The message RAM stores 32 message objects which can be received or transmitted on a CAN network. The CAN registers and message handler provide an interface for data transfer and notification between the CAN controller and the CIP-51.

The function and use of the CAN Controller is detailed in the *Bosch CAN User's Guide*. The User's Guide should be used as a reference to configure and use the CAN controller. This Silicon Labs data sheet describes how to access the CAN controller.

The CAN Controller is typically initialized using the following steps:

- Step 1. Set the SFRPAGE register to CANO PAGE.
- Step 2. Set the INIT the CCE bits to '1' in the CAN0CN Register. See the CAN User's Guide for bit definitions.
- Step 3. Set timing parameters in the Bit Timing Register and the BRP Extension Register.
- Step 4. Initialize each message object or set it's MsgVal bit to NOT VALID.
- Step 5. Reset the INIT bit to '0'.

The CAN Control Register (CAN0CN), CAN Test Register (CAN0TST), and CAN Status Register (CAN0STA) in the CAN controller can be accessed directly or indirectly via CIP-51 SFR's. All other CAN registers must be accessed via an indirect indexing method described in **Section "18.2.5. Using CAN0ADR, CAN0DATH, and CANDATL to Access CAN Registers" on page 232**.




Figure 18.2. CAN Controller Diagram



### 18.1.1. CAN Controller Timing

The CAN controller's system clock (f<sub>sys</sub>) is derived from the CIP-51 system clock (SYSCLK). Note that an external oscillator (such as a quartz crystal) is typically required due to the high accuracy requirements for CAN communication. Refer to Section "4.10.4 Oscillator Tolerance Range" in the Bosch CAN User's Guide for further information regarding this topic.

### 18.1.2. Example Timing Calculation for 1 Mbit/Sec Communication

This example shows how to configure the CAN contoller timing parameters for a 1 Mbit/Sec bit rate. Table 18.1 shows timing-related system parameters needed for the calculation.

Parameter	Value	Description
CIP-51 system clock (SYSCLK)	22.1184 MHz	External oscillator in 'Crystal Oscillator Mode'. A 22.1184 MHz quartz crystal is connected between XTAL1 and XTAL2.
CAN Controller system clock (f <sub>sys</sub> )	22.1184 MHz	Derived from SYSCLK.
CAN clock period (t <sub>sys</sub> )	45.211 ns	Derived from 1/f <sub>sys</sub> .
CAN time quantum (t <sub>q</sub> )	45.211 ns	Derived from t <sub>sys</sub> x BRP <sup>1,2</sup>
CAN bus length	10 m	5 ns/m signal delay between CAN nodes.
Propagation delay time <sup>3</sup>	400 ns	2 x (transceiver loop delay + bus line delay)

**Table 18.1. Background System Information** 

#### Notes:

- 1. The CAN time quantum  $(t_q)$  is the smallest unit of time recognized by the CAN contoller. Bit timing parameters are often specified in integer multiples of the time quantum.
- 2. The Baud Rate Prescaler (BRP) is defined as the value of the BRP Extension Register plus 1. The BRP Extension Register has a reset value of 0x0000; the Baud Rate Prescaler has a reset value of 1.
- 3. Based on an ISO-11898 compliant transceiver. CAN does not specify a physical layer.

Each bit transmitted on a CAN network has 4 segments (Sync\_Seg, Prop\_Seg, Phase\_Seg1, and Phase\_Seg2), as shown in Figure 18.3. The sum of these segments determines the CAN bit time (1/bit rate). In this example, the desired bit rate is 1 Mbit/sec; therefore, the desired bit time is 1000 ns.




Figure 18.3. Four Segments of a CAN Bit Time



We will adjust the length of the 4 bit segments so that their sum is as close as possible to the desired bit time. Since each segment must be an integer multiple of the time quantum ( $t_q$ ), the closest achievable bit time is 22  $t_q$  (994.642 ns), yielding a bit rate of 1.00539 Mbit/sec. The Sync\_Seg is a constant 1  $t_q$ . The Prop\_Seg must be greater than or equal to the propagation delay of 400 ns; we choose 9  $t_q$  (406.899 ns).

The remaining time quanta  $(t_q)$  in the bit time are divided between Phase\_Seg1 and Phase\_Seg2 as shown in Figure 18.1. We select Phase\_Seg1 = 6  $t_q$  and Phase\_Seg2 = 6  $t_q$ .

$$Phase\_Seg1 + Phase\_Seg2 = Bit Time - (Sync\_Seg + Prop\_Seg)$$

Note 1: If Phase Seg1 + Phase Seg2 is even, then Phase Seg2 = Phase Seg1.

Note 2: Phase\_Seg2 should be at least 2 t<sub>a</sub>.

### **Equation 18.1. Assigning the Phase Segments**

The Synchronization Jump Width (SJW) timing parameter is defined by Figure 18.2. It is used for determining the value written to the Bit Timing Register and for determining the required oscillator tolerance. Since we are using a quartz crystal as the system clock source, an oscillator tolerance calculation is not needed.

### **Equation 18.2. Synchronization Jump Width (SJW)**

The value written to the Bit Timing Register can be calculated using Equation 18.3. The BRP Extension register is left at its reset value of 0x0000.

```
BRPE = BRP - 1 = BRP Extension Register = 0x0000

SJWp = SJW - 1 = min (4, 6) - 1 = 3

TSEG1 = (Prop_Seg + Phase_Seg1 - 1) = 9 + 6 - 1 = 14

TSEG2 = (Phase_Seg2 - 1) = 5

Bit Timing Register = (TSEG2 * 0x1000) + (TSEG1 * 0x0100) + (SJWp * 0x0040) + BRPE = 0x5EC0
```

### **Equation 18.3. Calculating the Bit Timing Register Value**

The following steps are performed to initialize the CAN timing registers:

- Step 1. Set the SFRPAGE register to CAN0\_PAGE.
- Step 2. Set the INIT the CCE bits to '1' in the CAN Control Register accessible through the CANOCN SFR.
- Step 3. Set the CANOADR to 0x03 to point to the Bit Timing Register.



Step 4. Write the value 0x5EC0 to the [CAN0DATH:CAN0DATL] CIP-51 SFRs to set the Bit Timing Register using the indirect indexing method described on **Section 18.2.5 on page 232**.

Step 5. Perform other CAN initializations.

### 18.2. CAN Registers

CAN registers are classified as follows:

- 1. <u>CAN Controller Protocol Registers</u>: CAN control, interrupt, error control, bus status, test modes.
- 2. Message Object Interface Registers: Used to configure 32 Message Objects, send and receive data to and from Message Objects. The CIP-51 MCU accesses the CAN message RAM via the Message Object Interface Registers. Upon writing a message object number to an IF1 or IF2 Command Request Register, the contents of the associated Interface Registers (IF1 or IF2) will be transferred to or from the message object in CAN RAM.
- 3. <u>Message Handler Registers</u>: These read only registers are used to provide information to the CIP-51 MCU about the message objects (MSGVLD flags, Transmission Request Pending, New Data Flags) and Interrupts Pending (which Message Objects have caused an interrupt or status interrupt condition).
- CIP-51 MCU Special Function Registers (SFR): Six registers located in the CIP-51 MCU
  memory map that allow direct access to certain CAN Controller Protocol Registers, and
  Indexed indirect access to all CAN registers.

### 18.2.1. CAN Controller Protocol Registers

The CAN Control Protocol Registers are used to configure the CAN controller, process interrupts, monitor bus status, and place the controller in test modes. The CAN controller protocol registers are accessible using CIP-51 MCU SFR's by an indexed method, and some can be accessed directly by addressing the SFR's in the CIP-51 SFR map for convenience.

The registers are: CAN Control Register (CANOCN), CAN Status Register (CANOSTA), CAN Test Register (CANOTST), Error Counter Register, Bit Timing Register, and the Baud Rate Prescaler (BRP) Extension Register. CANOSTA, CANOCN, and CANOTST can be accessed via CIP-51 MCU SFR's. All others are accessed indirectly using the CAN address indexed method via CANOADR, CANODATH, and CANODATL.

Please refer to the Bosch CAN User's Guide for information on the function and use of the CAN Control Protocol Registers.

### 18.2.2. Message Object Interface Registers

There are two sets of Message Object Interface Registers used to configure the 32 Message Objects that transmit and receive data to and from the CAN bus. Message objects can be configured for transmit or receive, and are assigned arbitration message identifiers for acceptance filtering by all CAN nodes.

Message Objects are stored in Message RAM, and are accessed and configured using the Message Object Interface Registers. These registers are accessed via the CIP-51's CAN0ADR and CAN0DAT registers using the indirect indexed address method.

Please refer to the Bosch CAN User's Guide for information on the function and use of the Message Object Interface Registers.



### 18.2.3. Message Handler Registers

The Message Handler Registers are *read only* registers. Their flags can be read via the indexed access method with CAN0ADR, CAN0DATH, and CAN0DATL. The message handler registers provide interrupt, error, transmit/receive requests, and new data information.

Please refer to the Bosch CAN User's Guide for information on the function and use of the Message Handler Registers.

### 18.2.4. CIP-51 MCU Special Function Registers

C8051F04x family peripherals are modified, monitored, and controlled using Special Function Registers (SFR's). Only three of the CAN Controller's registers may be accessed directly with SFR's. However, all CAN Controller registers can be accessed indirectly using three CIP-51 MCU SFR's: the CAN Data Registers (CAN0DATH and CAN0DATL) and CAN Address Register (CAN0ADR).

### 18.2.5. Using CANOADR, CANODATH, and CANDATL to Access CAN Registers

Each CAN Controller Register has an index number (see Table 18.2). The CAN register address space is 128 words (256 bytes). A CAN register is accessed via the CAN Data Registers (CAN0DATH and CAN0DATL) when a CAN register's index number is placed into the CAN Address Register (CAN0ADR). For example, if the Bit Timing Register is to be configured with a new value, CAN0ADR is loaded with 0x03. The low byte of the desired value is accessed using CAN0DATL and the high byte of the bit timing register is accessed using CAN0DATL is bit addressable for convenience. To load the value 0x2304 into the Bit Timing Register:

```
CANOADR = 0x03; // Load Bit Timing Register's index (Table 18.1)
CANODATH = 0x23; // Move the upper byte into data reg high byte
CANODATL = 0x04; // Move the lower byte into data reg low byte
```

Note: CANOCN, CANOSTA, and CANOTST may be accessed either by using the index method, or by direct access with the CIP-51 MCU SFR's. CANOCN is located at SFR location 0xF8/SFR page 1 (SFR Definition 18.3), CANOTST at 0xDB/SFR page 1 (SFR Definition 18.4), and CANOSTA at 0xC0/SFR page 1 (SFR Definition 18.5).

### 18.2.6. CANOADR Autoincrement Feature

For ease of programming message objects, CAN0ADR features autoincrementing for the index ranges 0x08 to 0x12 (Interface Registers 1) and 0x20 to 0x2A (Interface Registers 2). When the CAN0ADR register has an index in these ranges, the CAN0ADR will autoincrement by 1 to point to the next CAN register 16-bit word upon a read/write of CAN0DATL. This speeds programming of the frequently-accessed interface registers when configuring message objects.

NOTE: Table 18.2 below supersedes Figure 5 in Section 3, "Programmer's Model" of the Bosch CAN User's Guide.



**Table 18.2. CAN Register Index and Reset Values** 

CAN Register Index	Register Name	Reset Value	Notes
0x00	CAN Control Register	0x0001	Accessible in CIP-51 SFR Map
0x01	Status Register	0x0000	Accessible in CIP-51 SFR Map
0x02	Error Register	0x0000	Read Only
0x03	Bit Timing Register	0x2301	Write Enabled by CCE Bit in CAN0CN
0x04	Interrupt Register	0x0000	Read Only
0x05	Test Register	0x0000	Bit 7 (RX) is determined by CAN bus
0x06	BRP Extension Register	0x0000	Write Enabled by TEST bit in CAN0CN
0x08	IF1 Command Request	0x0001	CAN0ADR autoincrements in IF1 index space (0x08 - 0x12) upon write to CAN0DATL
0x09	IF1 Command Mask	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x0A	IF1 Mask 1	0xFFFF	CAN0ADR autoincrement upon write to CAN0DATL
0x0B	IF1 Mask 2	0xFFFF	CAN0ADR autoincrement upon write to CAN0DATL
0x0C	IF1 Arbitration 1	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x0D	IF1 Arbitration 2	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x0E	IF1 Message Control	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x0F	IF1 Data A1	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x10	IF1 Data A2	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x11	IF1 Data B1	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x12	IF1 Data B2	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x20	IF2 Command Request	0x0001	CAN0ADR autoincrements in IF2 index space (0x20 - 0x2A) upon write to CAN0DATL
0x21	IF2 Command Mask	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x22	IF2 Mask 1	0xFFFF	CAN0ADR autoincrement upon write to CAN0DATL
0x23	IF2 Mask 2	0xFFFF	CAN0ADR autoincrement upon write to CAN0DATL
0x24	IF2 Arbitration 1	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x25	IF2 Arbitration 2	0x0000	CAN0ADR autoincrement upon write to CAN0DATL



Table 18.2. CAN Register Index and Reset Values (Continued)

CAN Register Index	Register Name	Reset Value	Notes
0x26	IF2 Message Control	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x27	IF2 Data A1	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x28	IF2 Data A2	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x29	IF2 Data B1	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x2A	IF2 Data B2	0x0000	CAN0ADR autoincrement upon write to CAN0DATL
0x40	Transmission Request 1	0x0000	Transmission request flags for message objects (read only)
0x41	Transmission Request 2	0x0000	Transmission request flags for message objects (read only)
0x48	New Data 1	0x0000	New Data flags for message objects (read only)
0x49	New Data 2	0x0000	New Data flags for message objects (read only)
0x50	Interrupt Pending 1	0x0000	Interrupt pending flags for message objects (read only)
0x51	Interrupt Pending 2	0x0000	Interrupt pending flags for message objects (read only)
0x58	Message Valid 1	0x0000	Message valid flags for message objects (read only)
0x59	Message Valid 2	0x0000	Message valid flags for message objects (read only)

Figure 18.4. CAN0DATH: CAN Data Access Register High Byte

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value		
								00000000		
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0			
							SFR Address SFR Page			
Bit7-0: CAN0DATH: CAN Data Access Register High Byte. The CAN0DAT Registers are used to read/write register values and data to and from the CAN Registers pointed to with the index number in the CAN0ADR Register.										

The CAN0ADR Register is used to point the [CAN0DATH:CAN0DATL] to a desired CAN Register. The desired CAN Register's index number is moved into CAN0ADR. The CAN0DAT Register can then read/write to and from the CAN Register.



### SFR Definition 18.1. CAN0DATL: CAN Data Access Register Low Byte

R/W	Reset Value							
								00000001
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>_</del>

SFR Address: 0xD8 SFR Page: 1

Bit7-0: CANODATL: CAN Data Access Register Low Byte.

The CANODAT Registers are used to read/write register values and data to and from the CAN Registers pointed to with the index number in the CANOADR Register.

The CANOADR Register is used to point the [CANODATH:CANODATL] to a desired CAN Register. The desired CAN Register's index number is moved into CANOADR. The CANODAT Register can then read/write to and from the CAN Register.

### SFR Definition 18.2. CANOADR: CAN Address Index

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	
							SFR Addres	s. UxDA

SFR Address: 0xDA SFR Page: 1

Bit7-0: CANOADR: CAN Address Index Register.

The CAN0ADR Register is used to point the [CAN0DATH:CAN0DATL] to a desired CAN Register. The desired CAN Register's index number is moved into CAN0ADR. The CAN0DAT Register can then read/write to and from the CAN Register.

Note: When the value of CAN0ADR is 0x08-0x12 and 0x20-0x2A (IF1 and IF2 registers), this register will autoincrement by 1 upon a write to CAN0DATL. See **Section** "18.2.6. CAN0ADR Autoincrement Feature" on page 232.

All CAN registers' functions/definitions are listed and described in the Bosch CAN User's Guide.



### SFR Definition 18.3. CAN0CN: CAN Control

R/W	R/W	R/W	R	R/W	R/W	R/W	R/W	Reset Value
*	*	*	CANIF	*	*	*	*	
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xF8 SFR Page: 1

Bit 4: CANIF: CAN Interrupt Flag. Write = don't care.

0: CAN interrupt has not occurred.

1: CAN interrupt has occurred and is active.

CANIF is controlled by the CAN controller and is cleared by hardware once all interrupt conditions have been cleared in the CAN controller. See Section 3.4.1 in the *Bosch CAN User's Guide* (page 24) for more information concerning CAN controller interrupts.

\*All CAN registers' functions/definitions are listed and described in the Bosch CAN User's Guide with the exception of the CANIF bit.

This register may be accessed directly in the CIP-51 SFR register space, or through the indirect, index method (See Section "18.2.5. Using CAN0ADR, CAN0DATH, and CANDATL to Access CAN Registers" on page 232).

### SFR Definition 18.4. CAN0TST: CAN Test

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
Pleas	e see the B	osch CAN I	User's Guid	e for a com	plete definit	tion of this r	egister	
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_
							SFR Addres	s: 0xDB
							SFR Pag	e: 1

All CAN registers' functions/definitions are listed and described in the Bosch CAN User's Guide.

This register may be accessed directly in the CIP-51 SFR register space, or through the indirect, index method (See Section "18.2.5. Using CAN0ADR, CAN0DATH, and CANDATL to Access CAN Registers" on page 232).



### SFR Definition 18.5. CANOSTA: CAN Status

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
Please see the Bosch CAN User's Guide for a complete definition of this register								
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>_</del>
	SFR Address: 0xC0 SFR Page: 1							

All CAN registers' functions/definitions are listed and described in the Bosch CAN User's Guide.

This register may be accessed directly in the CIP-51 SFR register space, or through the indirect, index method (See Section "18.2.5. Using CAN0ADR, CAN0DATH, and CANDATL to Access CAN Registers" on page 232).





## 19. System Management BUS/I<sup>2</sup>C BUS (SMBUS0)

The SMBus0 I/O interface is a two-wire, bi-directional serial bus. SMBus0 is compliant with the System Management Bus Specification, version 2, and compatible with the I<sup>2</sup>C serial bus. Reads and writes to the interface by the system controller are byte oriented with the SMBus0 interface autonomously controlling the serial transfer of the data. A method of extending the clock-low duration is available to accommodate devices with different speed capabilities on the same bus.

SMBus0 may operate as a master and/or slave, and may function on a bus with multiple masters. SMBus0 provides control of SDA (serial data), SCL (serial clock) generation and synchronization, arbitration logic, and START/STOP control and generation. SMBus0 is controlled by SFRs as described in **Section 19.4 on page 245**.




Figure 19.1. SMBus0 Block Diagram



Figure 19.2 shows a typical SMBus configuration. The SMBus0 interface will work at any voltage between 3.0 V and 5.0 V and different devices on the bus may operate at different voltage levels. The bi-directional SCL (serial clock) and SDA (serial data) lines must be connected to a positive power supply voltage through a pullup resistor or similar circuit. Every device connected to the bus must have an open-drain or open-collector output for both the SCL and SDA lines, so that both are pulled high when the bus is free. The maximum number of devices on the bus is limited only by the requirement that the rise and fall times on the bus will not exceed 300 ns and 1000 ns, respectively.




Figure 19.2. Typical SMBus Configuration

### 19.1. Supporting Documents

It is assumed the reader is familiar with or has access to the following supporting documents:

- I<sup>2</sup>C Manual (AN10216-01) -- March 24, 2003, Philips Semiconductor.
- System Management Bus Specification -- Version 1.1, SBS Implementers Forum.



### 19.2. SMBus Protocol

Two types of data transfers are possible: data transfers from a master transmitter to an addressed slave receiver (WRITE), and data transfers from an addressed slave transmitter to a master receiver (READ). The master device initiates both types of data transfers and provides the serial clock pulses on SCL. Note: multiple master devices on the same bus are supported. If two or more masters attempt to initiate a data transfer simultaneously, an arbitration scheme is employed with a single master always winning the arbitration. Note that it is not necessary to specify one device as the master in a system; any device who transmits a START and a slave address becomes the master for that transfer.

A typical SMBus transaction consists of a START condition followed by an address byte (Bits7-1: 7-bit slave address; Bit0: R/W direction bit), one or more bytes of data, and a STOP condition. Each byte that is received (by a master or slave) must be acknowledged (ACK) with a low SDA during a high SCL (see Figure 19.3). If the receiving device does not ACK, the transmitting device will read a "not acknowledge" (NACK), which is a high SDA during a high SCL.

The direction bit (R/W) occupies the least-significant bit position of the address. The direction bit is set to logic 1 to indicate a "READ" operation and cleared to logic 0 to indicate a "WRITE" operation.

All transactions are initiated by a master, with one or more addressed slave devices as the target. The master generates the START condition and then transmits the slave address and direction bit. If the transaction is a WRITE operation from the master to the slave, the master transmits the data one byte at a time and expects an ACK from the slave at the end of each byte. For READ operations, the slave transmits the data and expects an ACK from the master at the end of each byte. At the end of the data transfer, the master generates a STOP condition to terminate the transaction and free the bus. Figure 19.3 illustrates a typical SMBus transaction.




Figure 19.3. SMBus Transaction

### 19.2.1. Arbitration

A master may start a transfer only if the bus is free. The bus is free after a STOP condition or after the SCL and SDA lines remain high for a specified time (see **Section 19.2.4**). In the event that two or more devices attempt to begin a transfer at the same time, an arbitration scheme is employed to force one master to give up the bus. The master devices continue transmitting until one attempts a HIGH while the other transmits a LOW. Since the bus is open-drain, the bus will be pulled LOW. The master attempting the HIGH will detect a LOW SDA and give up the bus. The winning master continues its transmission without interruption; the losing master becomes a slave and receives the rest of the transfer. This arbitration scheme is non-destructive: one device always wins, and no data is lost.



### 19.2.2. Clock Low Extension

SMBus provides a clock synchronization mechanism, similar to I<sup>2</sup>C, which allows devices with different speed capabilities to coexist on the bus. A clock-low extension is used during a transfer in order to allow slower slave devices to communicate with faster masters. The slave may temporarily hold the SCL line LOW to extend the clock low period, effectively decreasing the serial clock frequency.

#### 19.2.3. SCL Low Timeout

If the SCL line is held low by a slave device on the bus, no further communication is possible. Furthermore, the master cannot force the SCL line high to correct the error condition. To solve this problem, the SMBus protocol specifies that devices participating in a transfer must detect any clock cycle held low longer than 25 ms as a "timeout" condition. Devices that have detected the timeout condition must reset the communication no later than 10 ms after detecting the timeout condition.

### 19.2.4. SCL High (SMBus Free) Timeout

The SMBus specification stipulates that if the SCL and SDA lines remain high for more that 50 µs, the bus is designated as free. If an SMBus device is waiting to generate a Master START, the START will be generated following the bus free timeout.

### 19.3. SMBus Transfer Modes

The SMBus0 interface may be configured to operate as a master and/or a slave. At any particular time, the interface will be operating in one of the following modes: Master Transmitter, Master Receiver, Slave Transmitter, or Slave Receiver. See Table 19.1 for transfer mode status decoding using the SMB0STA status register. The following mode descriptions illustrate an interrupt-driven SMBus0 application; SMBus0 may alternatively be operated in polled mode.

### 19.3.1. Master Transmitter Mode

Serial data is transmitted on SDA while the serial clock is output on SCL. SMBus0 generates a START condition and then transmits the first byte containing the address of the target slave device and the data direction bit. In this case the data direction bit (R/W) will be logic 0 to indicate a "WRITE" operation. The SMBus0 interface transmits one or more bytes of serial data, waiting for an acknowledge (ACK) from the slave after each byte. To indicate the end of the serial transfer, SMBus0 generates a STOP condition.




Figure 19.4. Typical Master Transmitter Sequence

### 19.3.2. Master Receiver Mode

Serial data is received on SDA while the serial clock is output on SCL. The SMBus0 interface generates a START followed by the first data byte containing the address of the target slave and the data direction bit. In this case the data direction bit (R/W) will be logic 1 to indicate a "READ" operation. The SMBus0 interface receives serial data from the slave and generates the clock on SCL. After each byte is received, SMBus0 generates an ACK or NACK depending on the state of the AA bit in register SMB0CN. SMBus0 generates a STOP condition to indicate the end of the serial transfer.




Figure 19.5. Typical Master Receiver Sequence

### 19.3.3. Slave Transmitter Mode

Serial data is transmitted on SDA while the serial clock is received on SCL. The SMBus0 interface receives a START followed by data byte containing the slave address and direction bit. If the received slave address matches the address held in register SMB0ADR, the SMBus0 interface generates an ACK. SMBus0 will also ACK if the general call address (0x00) is received and the General Call Address Enable bit (SMB0ADR.0) is set to logic 1. In this case the data direction bit (R/W) will be logic 1 to indicate a "READ" operation. The SMBus0 interface receives the clock on SCL and transmits one or more bytes of serial data, waiting for an ACK from the master after each byte. SMBus0 exits slave mode after receiving a STOP condition from the master.




Figure 19.6. Typical Slave Transmitter Sequence



### 19.3.4. Slave Receiver Mode

Serial data is received on SDA while the serial clock is received on SCL. The SMBus0 interface receives a START followed by data byte containing the slave address and direction bit. If the received slave address matches the address held in register SMB0ADR, the interface generates an ACK. SMBus0 will also ACK if the general call address (0x00) is received and the General Call Address Enable bit (SMB0ADR.0) is set to logic 1. In this case the data direction bit (R/W) will be logic 0 to indicate a "WRITE" operation. The SMBus0 interface receives one or more bytes of serial data; after each byte is received, the interface transmits an ACK or NACK depending on the state of the AA bit in SMB0CN. SMBus0 exits Slave Receiver Mode after receiving a STOP condition from the master.




Figure 19.7. Typical Slave Receiver Sequence



### 19.4. SMBus Special Function Registers

The SMBus0 serial interface is accessed and controlled through five SFRs: SMB0CN Control Register, SMB0CR Clock Rate Register, SMB0ADR Address Register, SMB0DAT Data Register and SMB0STA Status Register. The five special function registers related to the operation of the SMBus0 interface are described in the following sections.

### 19.4.1. Control Register

The SMBus0 Control register SMB0CN is used to configure and control the SMBus0 interface. All of the bits in the register can be read or written by software. Two of the control bits are also affected by the SMBus0 hardware. The Serial Interrupt flag (SI, SMB0CN.3) is set to logic 1 by the hardware when a valid serial interrupt condition occurs. It can only be cleared by software. The Stop flag (STO, SMB0CN.4) is set to logic 1 by software. It is cleared to logic 0 by hardware when a STOP condition is detected on the bus.

Setting the ENSMB flag to logic 1 enables the SMBus0 interface. Clearing the ENSMB flag to logic 0 disables the SMBus0 interface and removes it from the bus. Momentarily clearing the ENSMB flag and then resetting it to logic 1 will reset SMBus0 communication. However, ENSMB should not be used to temporarily remove a device from the bus since the bus state information will be lost. Instead, the Assert Acknowledge (AA) flag should be used to temporarily remove the device from the bus (see description of AA flag below).

Setting the Start flag (STA, SMB0CN.5) to logic 1 will put SMBus0 in a master mode. If the bus is free, SMBus0 will generate a START condition. If the bus is not free, SMBus0 waits for a STOP condition to free the bus and then generates a START condition after a 5  $\mu$ s delay per the SMB0CR value (In accordance with the SMBus protocol, the SMBus0 interface also considers the bus free if the bus is idle for 50  $\mu$ s and no STOP condition was recognized). If STA is set to logic 1 while SMBus0 is in master mode and one or more bytes have been transferred, a repeated START condition will be generated.

When the Stop flag (STO, SMB0CN.4) is set to logic 1 while the SMBus0 interface is in master mode, the interface generates a STOP condition. In a slave mode, the STO flag may be used to recover from an error condition. In this case, a STOP condition is not generated on the bus, but the SMBus hardware behaves as if a STOP condition has been received and enters the "not addressed" slave receiver mode. Note that this simulated STOP will not cause the bus to appear free to SMBus0. The bus will remain occupied until a STOP appears on the bus or a Bus Free Timeout occurs. Hardware automatically clears the STO flag to logic 0 when a STOP condition is detected on the bus.

The Serial Interrupt flag (SI, SMB0CN.3) is set to logic 1 by hardware when the SMBus0 interface enters any one of the 28 possible states except the Idle state. If interrupts are enabled for the SMBus0 interface, an interrupt request is generated when the SI flag is set. The SI flag must be cleared by software.

**Important Note:** If SI is set to logic 1 while the SCL line is low, the clock-low period of the serial clock will be stretched and the serial transfer is suspended until SI is cleared to logic 0. A high level on SCL is not affected by the setting of the SI flag.

The Assert Acknowledge flag (AA, SMB0CN.2) is used to set the level of the SDA line during the acknowledge clock cycle on the SCL line. Setting the AA flag to logic 1 will cause an ACK (low level on SDA) to be sent during the acknowledge cycle if the device has been addressed. Setting the AA flag to logic 0 will cause a NACK (high level on SDA) to be sent during acknowledge cycle. After the transmission of a byte in slave mode, the slave can be temporarily removed from the bus by clearing the AA flag. The slave's own address and general call address will be ignored. To resume operation on the bus, the AA flag must be reset to logic 1 to allow the slave's address to be recognized.



Setting the SMBus0 Free Timer Enable bit (FTE, SMB0CN.1) to logic 1 enables the timer in SMB0CR. When SCL goes high, the timer in SMB0CR counts up. A timer overflow indicates a free bus timeout: if SMBus0 is waiting to generate a START, it will do so after this timeout. The bus free period should be less than 50 µs (see SFR Definition 19.2, SMBus0 Clock Rate Register).

When the TOE bit in SMB0CN is set to logic 1, Timer 4 is used to detect SCL low timeouts. If Timer 4 is enabled (see **Section "23.2. Timer 2, Timer 3, and Timer 4" on page 295**), Timer 4 is forced to reload when SCL is high, and forced to count when SCL is low. With Timer 4 enabled and configured to overflow after 25 ms (and TOE set), a Timer 4 overflow indicates a SCL low timeout; the Timer 4 interrupt service routine can then be used to reset SMBus0 communication in the event of an SCL low timeout.



### SFR Definition 19.1. SMB0CN: SMBus0 Control

	R	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
	BUSY	ENSMB	STA	STO	SI	AA	FTE	TOE	00000000
•	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xC0 SFR Page: 0

Bit7: BUSY: Busy Status Flag.

0: SMBus0 is free

1: SMBus0 is busy

Bit6: ENSMB: SMBus Enable.

This bit enables/disables the SMBus serial interface.

0: SMBus0 disabled.1: SMBus0 enabled.

Bit5: STA: SMBus Start Flag.

0: No START condition is transmitted.

1: When operating as a master, a START condition is transmitted if the bus is free. (If the bus is not free, the START is transmitted after a STOP is received.) If STA is set after one or more bytes have been transmitted or received and before a STOP is received, a repeated START condition is transmitted.

Bit4: STO: SMBus Stop Flag.

0: No STOP condition is transmitted.

1: Setting STO to logic 1 causes a STOP condition to be transmitted. When a STOP condition is received, hardware clears STO to logic 0. If both STA and STO are set, a STOP condition is transmitted followed by a START condition. In slave mode, setting the STO flag causes SMBus to behave as if a STOP condition was received.

Bit3: SI: SMBus Serial Interrupt Flag.

This bit is set by hardware when one of 27 possible SMBus0 states is entered. (Status code 0xF8 does not cause SI to be set.) When the SI interrupt is enabled, setting this bit causes the CPU to vector to the SMBus interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit2: AA: SMBus Assert Acknowledge Flag.

This bit defines the type of acknowledge returned during the acknowledge cycle on the SCL line.

0: A "not acknowledge" (high level on SDA) is returned during the acknowledge cycle.

1: An "acknowledge" (low level on SDA) is returned during the acknowledge cycle.

Bit1: FTE: SMBus Free Timer Enable Bit

0: No timeout when SCL is high

1: Timeout when SCL high time exceeds limit specified by the SMB0CR value.

Bit0: TOE: SMBus Timeout Enable Bit

0: No timeout when SCL is low.

1: Timeout when SCL low time exceeds limit specified by Timer 4, if enabled.



### 19.4.2. Clock Rate Register

### SFR Definition 19.2. SMB0CR: SMBus0 Clock Rate

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>
							SFR Addres	s: 0xCF

FR Address: 0xCF SFR Page: 0

### Bits7-0: SMB0CR.[7:0]: SMBus0 Clock Rate Preset

The SMB0CR Clock Rate register controls the frequency of the serial clock SCL in master mode. The 8-bit word stored in the SMB0CR Register preloads a dedicated 8-bit timer. The timer counts up, and when it rolls over to 0x00, the SCL logic state toggles.

The SMB0CR setting should be bounded by the following equation, where *SMB0CR* is the unsigned 8-bit value in register SMB0CR, and *SYSCLK* is the system clock frequency in Hz:

$$SMB0CR < ((288 - 0.85 \times SYSCLK) / 1.124E6)$$

The resulting SCL signal high and low times are given by the following equations:

$$T_{LOW} = (256 - SMB0CR)/SYSCLK$$

$$T_{HIGH} \cong (258 - SMB0CR) / SYSCLK + 625ns$$

Using the same value of SMB0CR from above, the Bus Free Timeout period is given in the following equation:

$$T_{BFT} \cong 10 \times \frac{(256 - SMB0CR) + 1}{SYSCLK}$$



### 19.4.3. Data Register

The SMBus0 Data register SMB0DAT holds a byte of serial data to be transmitted or one that has just been received. Software can read or write to this register while the SI flag is set to logic 1; software should not attempt to access the SMB0DAT register when the SMBus is enabled and the SI flag reads logic 0 since the hardware may be in the process of shifting a byte of data in or out of the register.

Data in SMB0DAT is always shifted out MSB first. After a byte has been received, the first bit of received data is located at the MSB of SMB0DAT. While data is being shifted out, data on the bus is simultaneously being shifted in. Therefore, SMB0DAT always contains the last data byte present on the bus. In the event of lost arbitration, the transition from master transmitter to slave receiver is made with the correct data in SMB0DAT.

### SFR Definition 19.3. SMB0DAT: SMBus0 Data

	R/W	Reset Value							
-	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<b>_</b>
								SFR Address SFR Page	

Bits7-0: SMB0DAT: SMBus0 Data.

The SMB0DAT register contains a byte of data to be transmitted on the SMBus0 serial interface or a byte that has just been received on the SMBus0 serial interface. The CPU can read from or write to this register whenever the SI serial interrupt flag (SMB0CN.3) is set to logic 1. When the SI flag is not set, the system may be in the process of shifting data and the CPU should not attempt to access this register.

### 19.4.4. Address Register

The SMB0ADR Address register holds the slave address for the SMBus0 interface. In slave mode, the seven most-significant bits hold the 7-bit slave address. The least significant bit (Bit0) is used to enable the recognition of the general call address (0x00). If Bit0 is set to logic 1, the general call address will be recognized. Otherwise, the general call address is ignored. The contents of this register are ignored when SMBus0 is operating in master mode.



### SFR Definition 19.4. SMB0ADR: SMBus0 Address

R/W	Reset Value							
SLV6	SLV5	SLV4	SLV3	SLV2	SLV1	SLV0	GC	00000000
Rit7	Bit6	Bit5	Rit4	Bit3	Rit2	Rit1	Bit0	<u>—</u>

SFR Address: 0xC3 SFR Page: 0

Bits7-1: SLV6-SLV0: SMBus0 Slave Address.

These bits are loaded with the 7-bit slave address to which SMBus0 will respond when operating as a slave transmitter or slave receiver. SLV6 is the most significant bit of the address and corresponds to the first bit of the address byte received.

Bit0: GC: General Call Address Enable.

This bit is used to enable general call address (0x00) recognition.

0: General call address is ignored.1: General call address is recognized.

### 19.4.5. Status Register

The SMB0STA Status register holds an 8-bit status code indicating the current state of the SMBus0 interface. There are 28 possible SMBus0 states, each with a corresponding unique status code. The five most significant bits of the status code vary while the three least-significant bits of a valid status code are fixed at zero when SI = '1'. Therefore, all possible status codes are multiples of eight. This facilitates the use of status codes in software as an index used to branch to appropriate service routines (allowing 8 bytes of code to service the state or jump to a more extensive service routine).

For the purposes of user software, the contents of the SMB0STA register is only defined when the SI flag is logic 1. Software should never write to the SMB0STA register; doing so will yield indeterminate results. The 28 SMBus0 states, along with their corresponding status codes, are given in Table 19.1.



### SFR Definition 19.5. SMB0STA: SMBus0 Status

R/W	Reset Value							
STA7	STA6	STA5	STA4	STA3	STA2	STA1	STA0	11111000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0xC1 SFR Page: 0

Bits7-3: STA7-STA3: SMBus0 Status Code.

These bits contain the SMBus0 Status Code. There are 28 possible status codes; each status code corresponds to a single SMBus state. A valid status code is present in SMB0STA when the SI flag (SMB0CN.3) is set to logic 1. The content of SMB0STA is not defined when the SI flag is logic 0. Writing to the SMB0STA register at any time will yield indeterminate results.

Bits2-0: STA2-STA0: The three least significant bits of SMB0STA are always read as logic 0 when the SI flag is logic 1.



**Table 19.1. SMB0STA Status Codes and States** 

Mode	Status Code	SMBus State	Typical Action
<u>&gt;</u> &	0x08	START condition transmitted.	Load SMB0DAT with Slave Address + R/W. Clear STA.
MT/ MR	0x10	Repeated START condition transmitted.	Load SMB0DAT with Slave Address + R/W. Clear STA.
	0x18	Slave Address + W transmitted. ACK received.	Load SMB0DAT with data to be transmitted.
mitter	0x20	Slave Address + W transmitted. NACK received.	Acknowledge poll to retry. Set STO + STA.
Master Transmitter	0x28 Data I	Data byte transmitted. ACK received.	1) Load SMB0DAT with next byte, OR     2) Set STO, OR     3) Clear STO then set STA for repeated START.
Mas	0x30	Data byte transmitted. NACK received.	Retry transfer OR     Set STO.
	0x38	Arbitration Lost.	Save current data.
eiver	0x40	Slave Address + R transmitted. ACK received.	If only receiving one byte, clear AA (send NACK after received byte). Wait for received data.
r Rece	0x48 Slave Address + R transmitted. NACK received.		Acknowledge poll to retry. Set STO + STA.
Master Receiver	0x50	Data byte received. ACK transmitted.	Read SMB0DAT. Wait for next byte. If next byte is last byte, clear AA.
	0x58	Data byte received. NACK transmitted.	Set STO.



Table 19.1. SMB0STA Status Codes and States (Continued)

Mode	Status Code	SMBus State	Typical Action		
	0x60	Own slave address + W received. ACK transmitted.	Wait for data.		
	0x68	Arbitration lost in sending SLA + R/W as master. Own address + W received. ACK transmitted.	Save current data for retry when bus is free. Wait for data.		
Ļ	0x70	General call address received. ACK transmitted.	Wait for data.		
Slave Receiver			Save current data for retry when bus is free.		
slave I	0x80	Data byte received. ACK transmitted.	Read SMB0DAT. Wait for next byte or STOP.		
0)	0x88	Data byte received. NACK transmitted.	Set STO to reset SMBus.		
	0x90	Data byte received after general call address. ACK transmitted.	Read SMB0DAT. Wait for next byte or STOP.		
	0x98	Data byte received after general call address. NACK transmitted.	Set STO to reset SMBus.		
	0xA0	STOP or repeated START received.	No action necessary.		
	0xA8	Own address + R received. ACK transmitted.	Load SMB0DAT with data to transmit.		
Slave Transmitter	0xB0	Arbitration lost in transmitting SLA + R/W as master. Own address + R received. ACK transmitted.	Save current data for retry when bus is free. Load SMB0DAT with data to transmit.		
Tra	0xB8	Data byte transmitted. ACK received.	Load SMB0DAT with data to transmit.		
ave	0xC0	Data byte transmitted. NACK received.	Wait for STOP.		
SIS	0xC8	Last data byte transmitted (AA=0). ACK received.	Set STO to reset SMBus.		
Slave	0xD0	SCL Clock High Timer per SMB0CR timed out	Set STO to reset SMBus.		
=	0x00	Bus Error (illegal START or STOP)	Set STO to reset SMBus.		
Η	0xF8	Idle	State does not set SI.		





## 20. Enhanced Serial Peripheral Interface (SPI0)

The Enhanced Serial Peripheral Interface (SPI0) provides access to a flexible, full-duplex synchronous serial bus. SPI0 can operate as a master or slave device in both 3-wire or 4-wire modes, and supports multiple masters and slaves on a single SPI bus. The slave-select (NSS) signal can be configured as an input to select SPI0 in slave mode, or to disable Master Mode operation in a multi-master environment, avoiding contention on the SPI bus when more than one master attempts simultaneous data transfers. NSS can also be configured as a chip-select output in master mode, or disabled for 3-wire operation. Additional general purpose port I/O pins can be used to select multiple slave devices in master mode.




Figure 20.1. SPI Block Diagram



### 20.1. Signal Descriptions

The four signals used by SPI0 (MOSI, MISO, SCK, NSS) are described below.

#### 20.1.1. Master Out, Slave In (MOSI)

The master-out, slave-in (MOSI) signal is an output from a master device and an input to slave devices. It is used to serially transfer data from the master to the slave. This signal is an output when SPI0 is operating as a master and an input when SPI0 is operating as a slave. Data is transferred most-significant bit first. When configured as a master, MOSI is driven by the MSB of the shift register in both 3- and 4-wire mode.

#### 20.1.2. Master In, Slave Out (MISO)

The master-in, slave-out (MISO) signal is an output from a slave device and an input to the master device. It is used to serially transfer data from the slave to the master. This signal is an input when SPI0 is operating as a master and an output when SPI0 is operating as a slave. Data is transferred most-significant bit first. The MISO pin is placed in a high-impedance state when the SPI module is disabled and when the SPI operates in 4-wire mode as a slave that is not selected. When acting as a slave in 3-wire mode, MISO is always driven by the MSB of the shift register.

#### 20.1.3. Serial Clock (SCK)

The serial clock (SCK) signal is an output from the master device and an input to slave devices. It is used to synchronize the transfer of data between the master and slave on the MOSI and MISO lines. SPI0 generates this signal when operating as a master. The SCK signal is ignored by a SPI slave when the slave is not selected (NSS = 1) in 4-wire slave mode.

#### 20.1.4. Slave Select (NSS)

The function of the slave-select (NSS) signal is dependent on the setting of the NSSMD1 and NSSMD0 bits in the SPI0CN register. There are three possible modes that can be selected with these bits:

- 1. NSSMD[1:0] = 00: 3-Wire Master or 3-Wire Slave Mode: SPI0 operates in 3-wire mode, and NSS is disabled. When operating as a slave device, SPI0 is always selected in 3-wire mode. Since no select signal is present, SPI0 can be the only slave on the bus in 3-wire mode. This is intended for point-to-point communication between a master and one slave.
- 2. NSSMD[1:0] = 01: 4-Wire Slave or Multi-Master Mode: SPI0 operates in 4-wire mode, and NSS is enabled as an input. When operating as a slave, NSS selects the SPI0 device. When operating as a master, a 1-to-0 transition of the NSS signal disables the master function of SPI0 so that multiple master devices can be used on the same SPI bus.
- 3. NSSMD[1:0] = 1x: 4-Wire Master Mode: SPI0 operates in 4-wire mode, and NSS is enabled as an output. The setting of NSSMD0 determines what logic level the NSS pin will output. This configuration should only be used when operating SPI0 as a master device.

See Figure 20.2, Figure 20.3, and Figure 20.4 for typical connection diagrams of the various operational modes. **Note that the setting of NSSMD bits affects the pinout of the device.** When in 3-wire master or 3-wire slave mode, the NSS pin will not be mapped by the crossbar. In all other modes, the NSS signal will be mapped to a pin on the device. See Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204 for general purpose port I/O and crossbar information.



### 20.2. SPI0 Master Mode Operation

A SPI master device initiates all data transfers on a SPI bus. SPI0 is placed in master mode by setting the Master Enable flag (MSTEN, SPI0CN.6). Writing a byte of data to the SPI0 data register (SPI0DAT) when in master mode writes to the transmit buffer. If the SPI shift register is empty, the byte in the transmit buffer is moved to the shift register, and a data transfer begins. The SPI0 master immediately shifts out the data serially on the MOSI line while providing the serial clock on SCK. The SPIF (SPI0CN.7) flag is set to logic 1 at the end of the transfer. If interrupts are enabled, an interrupt request is generated when the SPIF flag is set. While the SPI0 master transfers data to a slave on the MOSI line, the addressed SPI slave device simultaneously transfers the contents of its shift register to the SPI master on the MISO line in a full-duplex operation. Therefore, the SPIF flag serves as both a transmit-complete and receive-data-ready flag. The data byte received from the slave is transferred MSB-first into the master's shift register. When a byte is fully shifted into the register, it is moved to the receive buffer where it can be read by the processor by reading SPI0DAT.

When configured as a master, SPI0 can operate in one of three different modes: multi-master mode, 3-wire single-master mode, and 4-wire single-master mode. The default, multi-master mode is active when NSSMD1 (SPI0CN.3) = 0 and NSSMD0 (SPI0CN.2) = 1. In this mode, NSS is an input to the device, and is used to disable the master SPI0 when another master is accessing the bus. When NSS is pulled low in this mode, MSTEN (SPI0CN.6) and SPIEN (SPI0CN.0) are set to 0 to disable the SPI master device, and a Mode Fault is generated (MODF, SPI0CN.5 = 1). Mode Fault will generate an interrupt if enabled. SPI0 must be manually re-enabled in software under these circumstances. In multi-master systems, devices will typically default to being slave devices while they are not acting as the system master device. In multi-master mode, slave devices can be addressed individually (if needed) using general-purpose I/O pins. Figure 20.2 shows a connection diagram between two master devices in multiple-master mode.

3-wire single-master mode is active when NSSMD1 (SPI0CN.3) = 0 and NSSMD0 (SPI0CN.2) = 0. In this mode, NSS is not used, and does not get mapped to an external port pin through the crossbar. Any slave devices that must be addressed in this mode should be selected using general-purpose I/O pins. Figure 20.3 shows a connection diagram between a master device in 3-wire master mode and a slave device.

4-wire single-master mode is active when NSSMD1 (SPI0CN.3) = 1. In this mode, NSS is configured as an output pin, and can be used as a slave-select signal for a single SPI device. In this mode, the output value of NSS is controlled (in software) with the bit NSSMD0 (SPI0CN.2). Additional slave devices can be addressed using general-purpose I/O pins. Figure 20.4 shows a connection diagram for a master device in 4-wire master mode and two slave devices.






Figure 20.2. Multiple-Master Mode Connection Diagram




Figure 20.3. 3-Wire Single Master and Slave Mode Connection Diagram




Figure 20.4. 4-Wire Single Master and Slave Mode Connection Diagram



### 20.3. SPI0 Slave Mode Operation

When SPI0 is enabled and not configured as a master, it will operate as a SPI slave. As a slave, bytes are shifted in through the MOSI pin and out through the MISO pin by a master device controlling the SCK signal. A bit counter in the SPI0 logic counts SCK edges. When 8 bits have been shifted through the shift register, the SPIF flag is set to logic 1, and the byte is copied into the receive buffer. Data is read from the receive buffer by reading SPI0DAT. A slave device cannot initiate transfers. Data to be transferred to the master device is pre-loaded into the shift register by writing to SPI0DAT. Writes to SPI0DAT are double-buffered, and are placed in the transmit buffer first. If the shift register is empty, the contents of the transmit buffer will immediately be transferred into the shift register. When the shift register already contains data, the SPI will wait until the byte is transferred before loading it with the transmit buffer's contents.

When configured as a slave, SPI0 can be configured for 4-wire or 3-wire operation. The default, 4-wire slave mode, is active when NSSMD1 (SPI0CN.3) = 0 and NSSMD0 (SPI0CN.2) = 1. In 4-wire mode, the NSS signal is routed to a port pin and configured as a digital input. SPI0 is enabled when NSS is logic 0, and disabled when NSS is logic 1. The bit counter is reset on a falling edge of NSS. Note that the NSS signal must be driven low at least 2 system clocks before the first active edge of SCK for each byte transfer. Figure 20.4 shows a connection diagram between two slave devices in 4-wire slave mode and a master device.

3-wire slave mode is active when NSSMD1 (SPI0CN.3) = 0 and NSSMD0 (SPI0CN.2) = 0. NSS is not used in this mode, and does not get mapped to an external port pin through the crossbar. Since there is no way of uniquely addressing the device in 3-wire slave mode, SPI0 must be the only slave device present on the bus. It is important to note that in 3-wire slave mode there is no external means of resetting the bit counter that determines when a full byte has been received. The bit counter can only be reset by disabling and re-enabling SPI0 with the SPIEN bit. Figure 20.3 shows a connection diagram between a slave device in 3-wire slave mode and a master device.

#### 20.4. SPI0 Interrupt Sources

When SPI0 interrupts are enabled, the following four flags will generate an interrupt when they are set to logic 1:

Note: All of the following interrupt bits must be cleared by software.

- 1. The SPI Interrupt Flag, SPIF (SPI0CN.7) is set to logic 1 at the end of each byte transfer. This flag can occur in all SPI0 modes.
- 2. The Write Collision Flag, WCOL (SPI0CN.6) is set to logic 1 if a write to SPI0DAT is attempted when the transmit buffer has not been emptied to the SPI shift register. When this occurs, the write to SPI0DAT will be ignored, and the transmit buffer will not be written. This flag can occur in all SPI0 modes.
- 3. The Mode Fault Flag MODF (SPI0CN.5) is set to logic 1 when SPI0 is configured as a master, and for multi-master mode and the NSS pin is pulled low. When a Mode Fault occurs, the MSTEN and SPIEN bits in SPI0CN are set to logic 0 to disable SPI0 and allow another master device to access the bus.
- 4. The Receive Overrun Flag RXOVRN (SPI0CN.4) is set to logic 1 when configured as a slave, and a transfer is completed and the receive buffer still holds an unread byte from a previous transfer. The new byte is not transferred to the receive buffer, allowing the previously received data byte to be read. The data byte which caused the overrun is lost.



### 20.5. Serial Clock Timing

As shown in Figure 20.5, four combinations of serial clock phase and polarity can be selected using the clock control bits in the SPI0 Configuration Register (SPI0CFG). The CKPHA bit (SPI0CFG.5) selects one of two clock phases (edge used to latch the data). The CKPOL bit (SPI0CFG.4) selects between an active-high or active-low clock. Both master and slave devices must be configured to use the same clock phase and polarity. Note: SPI0 should be disabled (by clearing the SPIEN bit, SPI0CN.0) when changing the clock phase or polarity.

Note that in master mode, the SPI samples MISO one system clock before the inactive edge of SCK (the edge where MOSI changes state) to provide maximum settling time for the slave device.

The SPI0 Clock Rate Register (SPI0CKR) as shown in SFR Definition 20.3 controls the master mode serial clock frequency. This register is ignored when operating in slave mode. When the SPI is configured as a master, the maximum data transfer rate (bits/sec) is one-half the system clock frequency. When the SPI is configured as a slave, the maximum data transfer rate (bits/sec) for full-duplex operation is 1/10 the system clock frequency, provided that the master issues SCK, NSS (in 4-wire slave mode), and the serial input data synchronously with the system clock. If the master issues SCK, NSS, and the serial input data asynchronously, the maximum data transfer rate (bits/sec) must be less than 1/10 the system clock frequency. In the special case where the master only wants to transmit data to the slave and does not need to receive data from the slave (i.e. half-duplex operation), the SPI slave can receive data at a maximum data transfer rate (bits/sec) of 1/4 the system clock frequency. This is provided that the master issues SCK, NSS, and the serial input data synchronously with the system clock.




Figure 20.5. Data/Clock Timing Diagram



SFR Page: 0

### 20.6. SPI Special Function Registers

SPI0 is accessed and controlled through four special function registers in the system controller: SPI0CN Control Register, SPI0DAT Data Register, SPI0CFG Configuration Register, and SPI0CKR Clock Rate Register. The four special function registers related to the operation of the SPI0 Bus are described in the following definitions.

### SFR Definition 20.1. SPI0CFG: SPI0 Configuration

R	R/W	R/W	R/W	R	R	R	R	Reset Value
SPIBSY	MSTEN	CKPHA	CKPOL	SLVSEL	NSSIN	SRMT	RXBMT	00000111
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_
SFR Address: 0x9A								

Bit 7: SPIBSY: SPI Busy.

This bit is set to logic 1 when a SPI transfer is in progress (Master or slave Mode).

Bit 6: MSTEN: Master Mode Enable.

0: Disable master mode. Operate in slave mode.1: Enable master mode. Operate as a master.

Bit 5: CKPHA: SPI0 Clock Phase.

This bit controls the SPI0 clock phase.

0: Data sampled on first edge of SCK period.

1: Data sampled on second edge of SCK period.

Bit 4: CKPOL: SPI0 Clock Polarity.

This bit controls the SPI0 clock polarity.

0: SCK line low in idle state.

1: SCK line high in idle state.

Bit 3: SLVSEL: Slave Selected Flag.

This bit is set to logic 1 whenever the NSS pin is low indicating SPI0 is the selected slave. It is cleared to logic 0 when NSS is high (slave not selected). This bit does not indicate the instantaneous value at the NSS pin, but rather a de-glitched version of the pin input.

Bit 2: NSSIN: NSS Instantaneous Pin Input.

This bit mimics the instantaneous value that is present on the NSS port pin at the time that the register is read. This input is not de-glitched.

Bit 1: SRMT: Shift Register Empty (Valid in Slave Mode).

This bit will be set to logic 1 when all data has been transferred in/out of the shift register, and there is no new information available to read from the transmit buffer or write to the receive buffer. It returns to logic 0 when a data byte is transferred to the shift register from the transmit buffer or by a transition on SCK.

NOTE: SRMT = 1 when in Master Mode.

Bit 0: RXBMT: Receive Buffer Empty (Valid in Slave Mode).

This bit will be set to logic 1 when the receive buffer has been read and contains no new information. If there is new information available in the receive buffer that has not been read, this bit will return to logic 0.

NOTE: RXBMT = 1 when in Master Mode.



#### SFR Definition 20.2. SPI0CN: SPI0 Control

R/W	R/W	R/W	R/W	R/W	R/W	R	R/W	Reset Value
SPIF	WCOL	MODF	RXOVRN	NSSMD1	NSSMD0	TXBMT	SPIEN	00000110
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0xF8 SFR Page: 0

Bit 7: SPIF: SPI0 Interrupt Flag.

This bit is set to logic 1 by hardware at the end of a data transfer. If interrupts are enabled, setting this bit causes the CPU to vector to the SPI0 interrupt service routine. This bit is not automatically cleared by hardware. It must be cleared by software.

Bit 6: WCOL: Write Collision Flag.

This bit is set to logic 1 by hardware (and generates a SPI0 interrupt) to indicate a write to the SPI0 data register was attempted while a data transfer was in progress. It must be cleared by software.

Bit 5: MODF: Mode Fault Flag.

This bit is set to logic 1 by hardware (and generates a SPI0 interrupt) when a master mode collision is detected (NSS is low, MSTEN = 1, and NSSMD[1:0] = 01). This bit is not automatically cleared by hardware. It must be cleared by software.

Bit 4: RXOVRN: Receive Overrun Flag (Slave Mode only).

This bit is set to logic 1 by hardware (and generates a SPI0 interrupt) when the receive buffer still holds unread data from a previous transfer and the last bit of the current transfer is shifted into the SPI0 shift register. This bit is not automatically cleared by hardware. It must be cleared by software.

Bits 3-2: NSSMD1-NSSMD0: Slave Select Mode.

Selects between the following NSS operation modes:

(See Section "20.2. SPI0 Master Mode Operation" on page 257 and Section "20.3. SPI0 Slave Mode Operation" on page 259).

00: 3-Wire Slave or 3-wire Master Mode. NSS signal is not routed to a port pin.

01: 4-Wire Slave or Multi-Master Mode (Default). NSS is always an input to the device.

1x: 4-Wire Single-Master Mode. NSS signal is mapped as an output from the device and will assume the value of NSSMD0.

Bit 1: TXBMT: Transmit Buffer Empty.

This bit will be set to logic 0 when new data has been written to the transmit buffer. When data in the transmit buffer is transferred to the SPI shift register, this bit will be set to logic 1, indicating that it is safe to write a new byte to the transmit buffer.

Bit 0: SPIEN: SPI0 Enable.

This bit enables/disables the SPI.

0: SPI disabled.

1: SPI enabled.



### SFR Definition 20.3. SPI0CKR: SPI0 Clock Rate

R/W	Reset Value							
SCR7	SCR6	SCR5	SCR4	SCR3	SCR2	SCR1	SCR0	00000000
Rit7	Bit6	Bit5	Rit4	Bit3	Bit2	Rit1	Bit0	<u>—</u>

SFR Address: 0x9D SFR Page: 0

Bits 7-0: SCR7-SCR0: SPI0 Clock Rate

These bits determine the frequency of the SCK output when the SPI0 module is configured for master mode operation. The SCK clock frequency is a divided version of the system clock, and is given in the following equation, where *SYSCLK* is the system clock frequency and *SPI0CKR* is the 8-bit value held in the SPI0CKR register.

$$f_{SCK} = \frac{SYSCLK}{2 \times (SPI0CKR + 1)}$$

for 0 <= SPI0CKR <= 255

Example: If SYSCLK = 2 MHz and SPI0CKR = 0x04,

$$f_{SCK} = \frac{2000000}{2 \times (4+1)}$$

$$f_{SCK} = 200kHz$$



### SFR Definition 20.4. SPI0DAT: SPI0 Data

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
								00000000
 Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_
							0=0 4 1 1	

SFR Address: 0x9B SFR Page: 0

Bits 7-0: SPI0DAT: SPI0 Transmit and Receive Data.

The SPI0DAT register is used to transmit and receive SPI0 data. Writing data to SPI0DAT places the data into the transmit buffer and initiates a transfer when in Master Mode. A read of SPI0DAT returns the contents of the receive buffer.



#### 21. UART0

UART0 is an enhanced serial port with frame error detection and address recognition hardware. UART0 may operate in full-duplex asynchronous or half-duplex synchronous modes, and mutiproccessor communication is fully supported. Receive data is buffered in a holding register, allowing UART0 to start reception of a second incoming data byte before software has finished reading the previous data byte. A Receive Overrun bit indicates when new received data is latched into the receive buffer before the previously received byte has been read.

UART0 is accessed via its associated SFRs, Serial Control (SCON0) and Serial Data Buffer (SBUF0). The single SBUF0 location provides access to both transmit and receive registers. Reading SCON0 accesses the Receive register and writing SCON0 accesses the Transmit register.

UART0 may be operated in polled or interrupt mode. UART0 has two sources of interrupts: a Transmit Interrupt flag, TI0 (SCON0.1) set when transmission of a data byte is complete, and a Receive Interrupt flag, RI0 (SCON0.0) set when reception of a data byte is complete. UART0 interrupt flags are not cleared by hardware when the CPU vectors to the interrupt service routine; they must be cleared manually by software. This allows software to determine the cause of the UART0 interrupt (transmit complete or receive complete).




Figure 21.1. UARTO Block Diagram



### 21.1. UARTO Operational Modes

UART0 provides four operating modes (one synchronous and three asynchronous) selected by setting configuration bits in the SCON0 register. These four modes offer different baud rates and communication protocols. The four modes are summarized in Table 21.1.

Mode	Synchronization	Baud Clock	Data Bits	Start/Stop Bits
0	Synchronous	SYSCLK / 12	8	None
1	Asynchronous	Timer 1, 2, 3, or 4 Overflow	8	1 Start, 1 Stop
2	Asynchronous	SYSCLK / 32 or SYSCLK / 64	9	1 Start, 1 Stop
3	Asynchronous	Timer 1, 2, 3, or 4 Overflow	9	1 Start, 1 Stop

Table 21.1. UARTO Modes

#### 21.1.1. Mode 0: Synchronous Mode

Mode 0 provides synchronous, half-duplex communication. Serial data is transmitted and received on the RX0 pin. The TX0 pin provides the shift clock for both transmit and receive. The MCU must be the master since it generates the shift clock for transmission in both directions (see the interconnect diagram in Figure 21.3).

Data transmission begins when an instruction writes a data byte to the SBUF0 register. Eight data bits are transferred LSB first (see the timing diagram in Figure 21.2), and the TI0 Transmit Interrupt Flag (SCON0.1) is set at the end of the eighth bit time. Data reception begins when the REN0 Receive Enable bit (SCON0.4) is set to logic 1 and the RI0 Receive Interrupt Flag (SCON0.0) is cleared. One cycle after the eighth bit is shifted in, the RI0 flag is set and reception stops until software clears the RI0 bit. An interrupt will occur if enabled when either TI0 or RI0 are set.

The Mode 0 baud rate is SYSCLK/12. RX0 is forced to open-drain in Mode 0, and an external pullup will typically be required.





Figure 21.2. UARTO Mode 0 Timing Diagram





#### Figure 21.3. UARTO Mode 0 Interconnect

#### 21.1.2. Mode 1: 8-Bit UART, Variable Baud Rate

Mode 1 provides standard asynchronous, full-duplex communication using a total of 10 bits per data byte: one start bit, eight data bits (LSB first), and one stop bit. Data are transmitted from the TX0 pin and received at the RX0 pin. On receive, the eight data bits are stored in SBUF0 and the stop bit goes into RB80 (SCON0.2).

Data transmission begins when an instruction writes a data byte to the SBUF0 register. The TI0 Transmit Interrupt Flag (SCON0.1) is set at the end of the transmission (the beginning of the stop-bit time). Data reception can begin any time after the REN0 Receive Enable bit (SCON0.4) is set to logic 1. After the stop bit is received, the data byte will be loaded into the SBUF0 receive register if the following conditions are met: RI0 must be logic 0, and if SM20 is logic 1, the stop bit must be logic 1.

If these conditions are met, the eight bits of data is stored in SBUF0, the stop bit is stored in RB80 and the RI0 flag is set. If these conditions are not met, SBUF0 and RB80 will not be loaded and the RI0 flag will not be set. An interrupt will occur if enabled when either TI0 or RI0 are set.




Figure 21.4. UARTO Mode 1 Timing Diagram

The baud rate generated in Mode 1 is a function of timer overflow, shown in Equation 21.1 and Equation 21.3. UARTO can use Timer 1 operating in 8-Bit Auto-Reload Mode, or Timer 2, 3, or 4 operating in Auto-reload Mode to generate the baud rate (note that the TX and RX clocks are selected separately). On each timer overflow event (a rollover from all ones—0xFF for Timer 1, 0xFFFF for Timers 2, 3 and 4—to zero) a clock is sent to the baud rate logic.

Timers 1, 2, 3, and 4 are selected as the baud rate source with bits in the SSTA0 register (see SFR Definition 21.2). The transmit baud rate clock is selected using the S0TCLK1 and S0TCLK0 bits, and the receive baud rate clock is selected using the S0RCLK1 and S0RCLK0 bits.

The Mode 1 baud rate equations are shown below, where T1M is bit4 of register CKCON, TH1 is the 8-bit reload register for Timer 1, and [RCAPnH, RCAPnL] is the 16-bit reload register for Timer 2, 3, or 4.

#### Equation 21.1. Mode 1 Baud Rate using Timer 1

The Timer 1 overflow rate is determined by the Timer 1 clock source (T1CLK) and reload value (TH1). The frequency of T1CLK is selected as described in **Section "23.1. Timer 0 and Timer 1" on page 287**. The Timer 1 overflow rate is calculated as shown in Equation 21.2.



Timer1\_OverflowRate = T1CLK/(256 - TH1)

#### **Equation 21.2. Timer 1 Overflow Rate**

When Timers 2, 3, or 4 are selected as a baud rate source, the baud rate is generated as shown in Equation 21.3.

 $Mode1_BaudRate = (1/16 \times Timer234_OverflowRate)$ 

### Equation 21.3. Mode 1 Baud Rate using Timer 2, 3, or 4

The overflow rate for Timer 2, 3, or 4 is determined by the clock source for the timer (TnCLK) and the 16-bit reload value stored in the RCAPn register (n = 2, 3, or 4), as shown in Equation 21.4.

 $Timer234\_OverflowRate = TnCLK/(65536 - RCAPn)$ 

Equation 21.4. Timer 2, 3, or 4 Overflow Rate



#### 21.1.3. Mode 2: 9-Bit UART, Fixed Baud Rate

Mode 2 provides asynchronous, full-duplex communication using a total of eleven bits per data byte: a start bit, 8 data bits (LSB first), a programmable ninth data bit, and a stop bit. Mode 2 supports multiprocessor communications and hardware address recognition (see **Section 21.2**). On transmit, the ninth data bit is determined by the value in TB80 (SCON0.3). It can be assigned the value of the parity flag P in the PSW or used in multiprocessor communications. On receive, the ninth data bit goes into RB80 (SCON0.2) and the stop bit is ignored.

Data transmission begins when an instruction writes a data byte to the SBUF0 register. The TI0 Transmit Interrupt Flag (SCON0.1) is set at the end of the transmission (the beginning of the stop-bit time). Data reception can begin any time after the REN0 Receive Enable bit (SCON0.4) is set to logic 1. After the stop bit is received, the data byte will be loaded into the SBUF0 receive register if RI0 is logic 0 and one of the following requirements are met:

- SM20 is logic 0
- SM20 is logic 1, the received 9th bit is logic 1, and the received address matches the UART0 address as described in Section 21.2.

If the above conditions are satisfied, the eight bits of data are stored in SBUF0, the ninth bit is stored in RB80 and the RI0 flag is set. If these conditions are not met, SBUF0 and RB80 will not be loaded and the RI0 flag will not be set. An interrupt will occur if enabled when either TI0 or RI0 are set.

The baud rate in Mode 2 is either SYSCLK / 32 or SYSCLK / 64, according to the value of the SMOD0 bit in register SSTA0.

$$BaudRate = 2^{SMOD0} \times \left(\frac{SYSCLK}{64}\right)$$

#### Equation 21.5. Mode 2 Baud Rate




Figure 21.5. UARTO Modes 2 and 3 Timing Diagram




Figure 21.6. UARTO Modes 1, 2, and 3 Interconnect Diagram



### 21.1.4. Mode 3: 9-Bit UART, Variable Baud Rate

Mode 3 uses the Mode 2 transmission protocol with the Mode 1 baud rate generation. Mode 3 operation transmits 11 bits: a start bit, 8 data bits (LSB first), a programmable ninth data bit, and a stop bit. The baud rate is derived from Timer 1 or Timer 2, 3, or 4 overflows, as defined by Equation 21.1 and Equation 21.3. Multiprocessor communications and hardware address recognition are supported, as described in **Section 21.2**.

#### 21.2. Multiprocessor Communications

Modes 2 and 3 support multiprocessor communication between a master processor and one or more slave processors by special use of the ninth data bit and the built-in UART0 address recognition hardware. When a master processor wants to transmit to one or more slaves, it first sends an address byte to select the target(s). An address byte differs from a data byte in that its ninth bit is logic 1; in a data byte, the ninth bit is always set to logic 0. UART0 will recognize as "valid" (i.e., capable of causing an interrupt) **two** types of addresses: (1) a *masked* address and (2) a *broadcast* address **at any given time**. Both are described below.



### 21.3. Configuration of a Masked Address

The UART0 address is configured via two SFRs: SADDR0 (Serial Address) and SADEN0 (Serial Address Enable). SADEN0 sets the bit mask for the address held in SADDR0: bits set to logic 1 in SADEN0 correspond to bits in SADDR0 that are checked against the received address byte; bits set to logic 0 in SADEN0 correspond to "don't care" bits in SADDR0.

Example 1, S	SLAVE #1	Example 2, S	SLAVE #2	Example 3, S	Example 3, SLAVE #3		
SADDR0	= 00110101	SADDR0	= 00110101	SADDR0	= 00110101		
SADEN0	= 00001111	SADEN0	= 11110011	SADEN0	= 11000000		
UART0 Address	= xxxx0101	UART0 Address	= 0011xx01	UART0 Address	= 00xxxxxx		

Setting the SM20 bit (SCON0.5) configures UART0 such that when a stop bit is received, UART0 will generate an interrupt only if the ninth bit is logic 1 (RB80 = '1') and the received data byte matches the UART0 slave address. Following the received address interrupt, the slave will clear its SM20 bit to enable interrupts on the reception of the following data byte(s). Once the entire message is received, the addressed slave resets its SM20 bit to ignore all transmissions until it receives the next address byte. While SM20 is logic 1, UART0 ignores all bytes that do not match the UART0 address and include a ninth bit that is logic 1

#### 21.4. Broadcast Addressing

Multiple addresses can be assigned to a single slave and/or a single address can be assigned to multiple slaves, thereby enabling "broadcast" transmissions to more than one slave simultaneously. The broadcast address is the logical OR of registers SADDR0 and SADEN0, and '0's of the result are treated as "don't cares". Typically a broadcast address of 0xFF (hexadecimal) is acknowledged by all slaves, assuming "don't care" bits as '1's. The master processor can be configured to receive all transmissions or a protocol can be implemented such that the master/slave role is temporarily reversed to enable half-duplex transmission between the original master and slave(s).

Example 4, S	SLAVE #1	Example 5, S	SLAVE #2	Example 6, SLAVE #3		
SADDR0	= 00110101	SADDR0	= 00110101	SADDR0	= 00110101	
SADEN0	= 00001111	SADEN0	= 11110011	SADEN0	= 11000000	
Broadcast Addres	s = 00111111	Broadcast Address	s = 11110111	Broadcast Addres	s = 11110101	

Where all ZEROES in the Broadcast address are don't cares.

Note in the above examples 4, 5, and 6, each slave would recognize as "valid" an address of 0xFF as a broadcast address. Also note that examples 4, 5, and 6 uses the same SADDR0 and SADEN0 register values as shown in the examples 1, 2, and 3 respectively (slaves #1, 2, and 3). Thus, a master could address each slave device individually using a masked address, and also broadcast to all three slave devices. For example, if a Master were to send an address "11110101", only slave #1 would recognize the address as valid. If a master were to then send an address of "11111111", all three slave devices would recognize the address as a valid broadcast address.






Figure 21.7. UART Multi-Processor Mode Interconnect Diagram

#### 21.5. Frame and Transmission Error Detection

#### All Modes:

The Transmit Collision bit (TXCOL0 bit in register SSTA0) reads '1' if user software writes data to the SBUF0 register while a transmit is in progress.

#### Modes 1, 2, and 3:

The Receive Overrun bit (RXOV0 in register SSTA0) reads '1' if a new data byte is latched into the receive buffer before software has read the previous byte. The Frame Error bit (FE0 in register SSTA0) reads '1' if an invalid (low) STOP bit is detected.



Table 21.2. Oscillator Frequencies for Standard Baud Rates

Oscillator frequency (MHz)	Divide Factor	Timer 1 Reload Value <sup>1</sup>	Timer 2, 3, or 4 Reload Value	Resulting Baud Rate (Hz) <sup>2</sup>
24.0	208	0xF3	0xFFF3	115200 (115384)
22.1184	192	0xF4	0xFFF4	115200
18.432	160	0xF6	0xFFF6	115200
11.0592	96	0xFA	0xFFFA	115200
3.6864	32	0xFE	0xFFFE	115200
1.8432	16	0xFF	0xFFFF	115200
24.0	832	0xCC	0xFFCC	28800 (28846)
22.1184	768	0xD0	0xFFD0	28800
18.432	640	0xD8	0xFFD8	28800
11.0592	348	0xE8	0xFFE8	28800
3.6864	128	0xF8	0xFFF8	28800
1.8432	64	0xFC	0xFFFC	28800
24.0	2496	0x64	0xFF64	9600 (9615)
22.1184	2304	0x70	0xFF70	9600
18.432	1920	0x88	0xFF88	9600
11.0592	1152	0xB8	0xFFB8	9600
3.6864	384	0xE8	0xFFE8	9600
1.8432	192	0xF4	0xFFF4	9600

#### Notes:

- 1. Assumes SMOD0=1 and T1M=1.
- 2. Numbers in parenthesis show the actual baud rate.



### SFR Definition 21.1. SCON0: UART0 Control

R/W	Reset Value							
SM00	SM10	SM20	REN0	TB80	RB80	TI0	RI0	00000000
Rit7	Bit6	Bit5	Rit4	Bit3	Rit2	Rit1	Bit0	

SFR Address: 0x98 SFR Page: 0

Bits7-6: SM00-SM10: Serial Port Operation Mode:

Write:

When written, these bits select the Serial Port Operation Mode as follows:

SM00	SM10	Mode
0	0	Mode 0: Synchronous Mode
0	1	Mode 1: 8-Bit UART, Variable Baud Rate
1	0	Mode 2: 9-Bit UART, Fixed Baud Rate
1	1	Mode 3: 9-Bit UART, Variable Baud Rate

Reading these bits returns the current UART0 mode as defined above.

Bit5: SM20: Multiprocessor Communication Enable.

The function of this bit is dependent on the Serial Port Operation Mode.

Mode 0: No effect

Mode 1: Checks for valid stop bit.

0: Logic level of stop bit is ignored.

1: RIO will only be activated if stop bit is logic level 1.

Mode 2 and 3: Multiprocessor Communications Enable.

0: Logic level of ninth bit is ignored.

1: RI0 is set and an interrupt is generated only when the ninth bit is logic 1 and the received address matches the UART0 address or the broadcast address.

Bit4: REN0: Receive Enable.

This bit enables/disables the UART0 receiver.

0: UART0 reception disabled.

1: UART0 reception enabled.

Bit3: TB80: Ninth Transmission Bit.

The logic level of this bit will be assigned to the ninth transmission bit in Modes 2 and 3. It is not used in Modes 0 and 1. Set or cleared by software as required.

Bit2: RB80: Ninth Receive Bit.

The bit is assigned the logic level of the ninth bit received in Modes 2 and 3. In Mode 1, if SM20 is logic 0, RB80 is assigned the logic level of the received stop bit. RB8 is not used in Mode 0.

Bit1: TI0: Transmit Interrupt Flag.

Set by hardware when a byte of data has been transmitted by UART0 (after the 8th bit in Mode 0, or at the beginning of the stop bit in other modes). When the UART0 interrupt is enabled, setting this bit causes the CPU to vector to the UART0 interrupt service routine. This bit must be cleared manually by software.

Bit0: RI0: Receive Interrupt Flag.

Set by hardware when a byte of data has been received by UART0 (as selected by the SM20 bit). When the UART0 interrupt is enabled, setting this bit causes the CPU to vector to the UART0 interrupt service routine. This bit must be cleared manually by software.



### SFR Definition 21.2. SSTA0: UARTO Status and Clock Selection

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
FE0	RXOV0	TXCOL0	SMOD0	S0TCLK1	S0TCLK0	S0RCLK1	S0RCLK0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	•

SFR Address: 0x91 SFR Page: 0

Bit7: FE0: Frame Error Flag.

This flag indicates if an invalid (low) STOP bit is detected.

0: Frame Error has not been detected

1: Frame Error has been detected.

Bit6: RXOV0: Receive Overrun Flag.

This flag indicates new data has been latched into the receive buffer before software has read the previous byte.

0: Receive overrun has not been detected.

1: Receive Overrun has been detected.

Bit5: TXCOL0: Transmit Collision Flag.

This flag indicates user software has written to the SBUF0 register while a transmission is in progress.

0: Transmission Collision has not been detected.

1: Transmission Collision has been detected.

Bit4: SMOD0: UART0 Baud Rate Doubler Enable.

This bit enables/disables the divide-by-two function of the UART0 baud rate logic for configurations described in the UART0 section.

0: UART0 baud rate divide-by-two enabled.

1: UART0 baud rate divide-by-two disabled.

Bits3-2: UART0 Transmit Baud Rate Clock Selection Bits.

S0TCLK1	S0TCLK0	Serial Transmit Baud Rate Clock Source		
0	0 0 Timer 1 generates UART0 TX B			
0	1	Timer 2 Overflow generates UART0 TX baud rate		
1	0	Timer 3 Overflow generates UART0 TX baud rate		
1	1	Timer 4 Overflow generates UART0 TX baud rate		

Bits1-0: UARTO Receive Baud Rate Clock Selection Bits

S0RCLK1	S0RCLK0	Serial Receive Baud Rate Clock Source
0	0	Timer 1 generates UART0 RX Baud Rate
0	1	Timer 2 Overflow generates UART0 RX baud rate
1	0	Timer 3 Overflow generates UART0 RX baud rate
1	1	Timer 4 Overflow generates UART0 RX baud rate



#### SFR Definition 21.3. SBUF0: UART0 Data Buffer

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
								00000000
 Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0x99 SFR Page: 0

Bits7-0: SBUF0.[7:0]: UART0 Buffer Bits 7-0 (MSB-LSB)

This is actually two registers; a transmit and a receive buffer register. When data is moved to SBUF0, it goes to the transmit buffer and is held for serial transmission. Moving a byte to SBUF0 is what initiates the transmission. When data is moved from SBUF0, it comes from the receive buffer.

#### SFR Definition 21.4. SADDR0: UARTO Slave Address

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<del>_</del>
							OED 4 1.1	- 0 - 10

SFR Address: 0xA9 SFR Page: 0

Bits7-0: SADDR0.[7:0]: UART0 Slave Address

The contents of this register are used to define the UART0 slave address. Register SADEN0 is a bit mask to determine which bits of SADDR0 are checked against a received address: corresponding bits set to logic 1 in SADEN0 are checked; corresponding bits set to logic 0 are "don't cares".

#### SFR Definition 21.5. SADEN0: UARTO Slave Address Enable

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	
							CED Addros	or OvDO

SFR Address: 0xB9 SFR Page: 0

Bits7-0: SADEN0.[7:0]: UART0 Slave Address Enable

Bits in this register enable corresponding bits in register SADDR0 to determine the UART0 slave address.

0: Corresponding bit in SADDR0 is a "don't care".

1: Corresponding bit in SADDR0 is checked against a received address.

Rev. 1.5



276

#### 22. UART1

UART1 is an asynchronous, full duplex serial port offering modes 1 and 3 of the standard 8051 UART. Enhanced baud rate support allows a wide range of clock sources to generate standard baud rates (details in **Section "22.1. Enhanced Baud Rate Generation" on page 278**). Received data buffering allows UART1 to start reception of a second incoming data byte before software has finished reading the previous data byte.

UART1 has two associated SFRs: Serial Control Register 1 (SCON1) and Serial Data Buffer 1 (SBUF1). The single SBUF1 location provides access to both transmit and receive registers. Reading SBUF1 accesses the buffered Receive register; writing SBUF1 accesses the Transmit register.

With UART1 interrupts enabled, an interrupt is generated each time a transmit is completed (TI1 is set in SCON1), or a data byte has been received (RI1 is set in SCON1). The UART1 interrupt flags are not cleared by hardware when the CPU vectors to the interrupt service routine. They must be cleared manually by software, allowing software to determine the cause of the UART1 interrupt (transmit complete or receive complete).




Figure 22.1. UART1 Block Diagram



#### 22.1. Enhanced Baud Rate Generation

278

The UART1 baud rate is generated by Timer 1 in 8-bit auto-reload mode. The TX clock is generated by TL1; the RX clock is generated by a copy of TL1 (shown as RX Timer in Figure 22.2), which is not user-accessible. Both TX and RX Timer overflows are divided by two to generate the TX and RX baud rates. The RX Timer runs when Timer 1 is enabled, and uses the same reload value (TH1). However, an RX Timer reload is forced when a START condition is detected on the RX pin. This allows a receive to begin any time a START is detected, independent of the TX Timer state.




Figure 22.2. UART1 Baud Rate Logic

Timer 1 should be configured for Mode 2, 8-bit auto-reload (see Section "23.1.3. Mode 2: 8-bit Counter/Timer with Auto-Reload" on page 289). The Timer 1 reload value should be set so that overflows will occur at two times the desired baud rate. Note that Timer 1 may be clocked by one of five sources: SYS-CLK, SYSCLK / 12, SYSCLK / 48, or the external oscillator clock / 8. For any given Timer 1 clock source, the UART1 baud rate is determined by Equation 22.1, where  $T1_{CLK}$  is the frequency of the clock supplied to Timer 1, and TH1 is the high byte of Timer 1 (reload value).

$$UartBaudRate = \frac{T1_{CLK}}{(256 - TH1)} \times \frac{1}{2}$$

## **Equation 22.1. UART1 Baud Rate**

Timer 1 clock frequency is selected as described in **Section "23.1. Timer 0 and Timer 1" on page 287.** A quick reference for typical baud rates and system clock frequencies is given in Table 22.1 through Table 22.6. Note that the internal oscillator may still generate the system clock when the external oscillator is driving Timer 1 (see **Section "23.1. Timer 0 and Timer 1" on page 287** for more details).

#### 22.2. Operational Modes

UART1 provides standard asynchronous, full duplex communication. The UART mode (8-bit or 9-bit) is selected by the S1MODE bit (SCON1.7). Typical UART connection options are shown below.




Figure 22.3. UART Interconnect Diagram

#### 22.2.1. 8-Bit UART

8-Bit UART mode uses a total of 10 bits per data byte: one start bit, eight data bits (LSB first), and one stop bit. Data are transmitted LSB first from the TX1 pin and received at the RX1 pin. On receive, the eight data bits are stored in SBUF1 and the stop bit goes into RB81 (SCON1.2).

Data transmission begins when software writes a data byte to the SBUF1 register. The TI1 Transmit Interrupt Flag (SCON1.1) is set at the end of the transmission (the beginning of the stop-bit time). Data reception can begin any time after the REN1 Receive Enable bit (SCON1.4) is set to logic 1. After the stop bit is received, the data byte will be loaded into the SBUF1 receive register if the following conditions are met: RI1 must be logic 0, and if MCE1 is logic 1, the stop bit must be logic 1. In the event of a receive data overrun, the first received 8 bits are latched into the SBUF1 receive register and the following overrun data bits are lost.

If these conditions are met, the eight bits of data is stored in SBUF1, the stop bit is stored in RB81 and the RI1 flag is set. If these conditions are not met, SBUF1 and RB81 will not be loaded and the RI1 flag will not be set. An interrupt will occur if enabled when either TI1 or RI1 is set.




Figure 22.4. 8-Bit UART Timing Diagram



#### 22.2.2. 9-Bit UART

9-bit UART mode uses a total of eleven bits per data byte: a start bit, 8 data bits (LSB first), a programmable ninth data bit, and a stop bit. The state of the ninth transmit data bit is determined by the value in TB81 (SCON1.3), which is assigned by user software. It can be assigned the value of the parity flag (bit P in register PSW) for error detection, or used in multiprocessor communications. On receive, the ninth data bit goes into RB81 (SCON1.2) and the stop bit is ignored.

Data transmission begins when an instruction writes a data byte to the SBUF1 register. The TI1 Transmit Interrupt Flag (SCON1.1) is set at the end of the transmission (the beginning of the stop-bit time). Data reception can begin any time after the REN1 Receive Enable bit (SCON1.4) is set to '1'. After the stop bit is received, the data byte will be loaded into the SBUF1 receive register if the following conditions are met: (1) RI1 must be logic 0, and (2) if MCE1 is logic 1, the 9th bit must be logic 1 (when MCE1 is logic 0, the state of the ninth data bit is unimportant). If these conditions are met, the eight bits of data are stored in SBUF1, the ninth bit is stored in RB81, and the RI1 flag is set to '1'. If the above conditions are not met, SBUF1 and RB81 will not be loaded and the RI1 flag will not be set to '1'. A UART1 interrupt will occur if enabled when either TI1 or RI1 is set to '1'.




Figure 22.5. 9-Bit UART Timing Diagram



### 22.3. Multiprocessor Communications

9-Bit UART mode supports multiprocessor communication between a master processor and one or more slave processors by special use of the ninth data bit. When a master processor wants to transmit to one or more slaves, it first sends an address byte to select the target(s). An address byte differs from a data byte in that its ninth bit is logic 1; in a data byte, the ninth bit is always set to logic 0.

Setting the MCE1 bit (SCON1.5) of a slave processor configures its UART such that when a stop bit is received, the UART will generate an interrupt only if the ninth bit is logic one (RB81 = 1) signifying an address byte has been received. In the UART interrupt handler, software should compare the received address with the slave's own assigned 8-bit address. If the addresses match, the slave should clear its MCE1 bit to enable interrupts on the reception of the following data byte(s). Slaves that weren't addressed leave their MCE1 bits set and do not generate interrupts on the reception of the following data bytes, thereby ignoring the data. Once the entire message is received, the addressed slave should reset its MCE1 bit to ignore all transmissions until it receives the next address byte.

Multiple addresses can be assigned to a single slave and/or a single address can be assigned to multiple slaves, thereby enabling "broadcast" transmissions to more than one slave simultaneously. The master processor can be configured to receive all transmissions or a protocol can be implemented such that the master/slave role is temporarily reversed to enable half-duplex transmission between the original master and slave(s).




Figure 22.6. UART Multi-Processor Mode Interconnect Diagram



#### SFR Definition 22.1. SCON1: Serial Port 1 Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
S1MODE	-	MCE1	REN1	TB81	RB81	TI1	RI1	01000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0x98 SFR Page: 1

Bit7: S1MODE: Serial Port 1 Operation Mode.

This bit selects the UART1 Operation Mode.
0: Mode 0: 8-bit UART with Variable Baud Rate
1: Mode 1: 9-bit UART with Variable Baud Rate

Bit6: UNUSED. Read = 1b. Write = don't care.

Bit5: MCE1: Multiprocessor Communication Enable.

The function of this bit is dependent on the Serial Port 0 Operation Mode.

Mode 0: Checks for valid stop bit.

0: Logic level of stop bit is ignored.

1: RI1 will only be activated if stop bit is logic level 1.

Mode 1: Multiprocessor Communications Enable.

0: Logic level of ninth bit is ignored.

1: RI1 is set and an interrupt is generated only when the ninth bit is logic 1.

Bit4: REN1: Receive Enable.

This bit enables/disables the UART receiver.

0: UART1 reception disabled.1: UART1 reception enabled.

Bit3: TB81: Ninth Transmission Bit.

The logic level of this bit will be assigned to the ninth transmission bit in 9-bit UART Mode. It

is not used in 8-bit UART Mode. Set or cleared by software as required.

Bit2: RB81: Ninth Receive Bit.

RB81 is assigned the value of the STOP bit in Mode 0; it is assigned the value of the 9th

data bit in Mode 1.

Bit1: TI1: Transmit Interrupt Flag.

Set by hardware when a byte of data has been transmitted by UART1 (after the 8th bit in 8-bit UART Mode, or at the beginning of the STOP bit in 9-bit UART Mode). When the UART1 interrupt is enabled, setting this bit causes the CPU to vector to the UART1 interrupt service

routine. This bit must be cleared manually by software.

Bit0: RI1: Receive Interrupt Flag.

Set to '1' by hardware when a byte of data has been received by UART1 (set at the STOP bit sampling time). When the UART1 interrupt is enabled, setting this bit to '1' causes the CPU to vector to the UART1 interrupt service routine. This bit must be cleared manually by software.



### SFR Definition 22.2. SBUF1: Serial (UART1) Port Data Buffer

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0x99 SFR Page: 1

#### Bits7-0: SBUF1[7:0]: Serial Data Buffer Bits 7-0 (MSB-LSB)

This SFR accesses two registers; a transmit shift register and a receive latch register. When data is written to SBUF1, it goes to the transmit shift register and is held for serial transmission. Writing a byte to SBUF1 is what initiates the transmission. A read of SBUF1 returns the contents of the receive latch.



Table 22.1. Timer Settings for Standard Baud Rates Using the Internal 24.5 MHz Oscillator

		Frequency: 24.5 MHz										
	Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select)*	T1M*	Timer 1 Reload Value (hex)					
	230400	-0.32%	106	SYSCLK	XX	1	0xCB					
	115200	-0.32%	212	SYSCLK	XX	1	0x96					
	57600	0.15%	426	SYSCLK	XX	1	0x2B					
from sc.	28800	-0.32%	848	SYSCLK / 4	01	0	0x96					
( fro	14400	0.15%	1704	SYSCLK / 12	00	0	0xB9					
	9600	-0.32%	2544	SYSCLK / 12	00	0	0x96					
SYSCL <sub>F</sub> Internal	2400	-0.32%	10176	SYSCLK / 48	10	0	0x96					
SY Int	1200	0.15%	20448	SYSCLK / 48	10	0	0x2B					

X = Don't care

\*Note: SCA1-SCA0 and T1M bit definitions can be found in Section 23.1.

Table 22.2. Timer Settings for Standard Baud Rates Using an External 25.0 MHz Oscillator

	Frequency: 25.0 MHz									
	Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select)*	T1M*	Timer 1 Reload Value (hex)			
	230400	-0.47%	108	SYSCLK	XX	1	0xCA			
	115200	0.45%	218	SYSCLK	XX	1	0x93			
	57600	-0.01%	434	SYSCLK	XX	1	0x27			
from Osc.	28800	0.45%	872	SYSCLK / 4	01	0	0x93			
ξő	14400	-0.01%	1736	SYSCLK / 4	01	0	0x27			
)     na	9600	0.15%	2608	EXTCLK / 8	11	0	0x5D			
SYSCLK External (	2400	0.45%	10464	SYSCLK / 48	10	0	0x93			
SY Ex	1200	-0.01%	20832	SYSCLK / 48	10	0	0x27			
from Sc.	57600	-0.47%	432	EXTCLK / 8	11	0	0xE5			
	28800	-0.47%	864	EXTCLK / 8	11	0	0xCA			
SYSCLK Internal C	14400	0.45%	1744	EXTCLK / 8	11	0	0x93			
SY: Inte	9600	0.15%	2608	EXTCLK / 8	11	0	0x5D			

X = Don't care

\*Note: SCA1-SCA0 and T1M bit definitions can be found in Section 23.1.



Table 22.3. Timer Settings for Standard Baud Rates Using an External 22.1184 MHz Oscillator

	Frequency: 22.1184 MHz									
	Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select) <sup>*</sup>	T1M*	Timer 1 Reload Value (hex)			
	230400	0.00%	96	SYSCLK	XX	1	0xD0			
	115200	0.00%	192	SYSCLK	XX	1	0xA0			
	57600	0.00%	384	SYSCLK	XX	1	0x40			
from Osc.	28800	0.00%	768	SYSCLK / 12	00	0	0xE0			
ξő	14400	0.00%	1536	SYSCLK / 12	00	0	0xC0			
SYSCLK External 0	9600	0.00%	2304	SYSCLK / 12	00	0	0xA0			
'SC ter	2400	0.00%	9216	SYSCLK / 48	10	0	0xA0			
S X	1200	0.00%	18432	SYSCLK / 48	10	0	0x40			
	230400	0.00%	96	EXTCLK / 8	11	0	0xFA			
from )sc.	115200	0.00%	192	EXTCLK / 8	11	0	0xF4			
K froi Osc.	57600	0.00%	384	EXTCLK / 8	11	0	0xE8			
Z.K	28800	0.00%	768	EXTCLK / 8	11	0	0xD0			
SYSCLK Internal C	14400	0.00%	1536	EXTCLK / 8	11	0	0xA0			
S) Int	9600	0.00%	2304	EXTCLK / 8	11	0	0x70			

X = Don't care

\*Note: SCA1-SCA0 and T1M bit definitions can be found in Section 23.1.

Table 22.4. Timer Settings for Standard Baud Rates Using an External 18.432 MHz Oscillator

			Freque	ncy: 18.432	MHz		
	Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select)*	T1M <sup>*</sup>	Timer 1 Reload Value (hex)
	230400	0.00%	80	SYSCLK	XX	1	0xD8
	115200	0.00%	160	SYSCLK	XX	1	0xB0
	57600	0.00%	320	SYSCLK	XX	1	0x60
from Osc.	28800	0.00%	640	SYSCLK / 4	01	0	0xB0
from Osc.	14400	0.00%	1280	SYSCLK / 4	01	0	0x60
SYSCLK External	9600	0.00%	1920	SYSCLK / 12	00	0	0xB0
'SC teri	2400	0.00%	7680	SYSCLK / 48	10	0	0xB0
SYS	1200	0.00%	15360	SYSCLK / 48	10	0	0x60
	230400	0.00%	80	EXTCLK / 8	11	0	0xFB
from )sc.	115200	0.00%	160	EXTCLK / 8	11	0	0xF6
	57600	0.00%	320	EXTCLK / 8	11	0	0xEC
ار اعاد	28800	0.00%	640	EXTCLK / 8	11	0	0xD8
SYSCLK Internal C	14400	0.00%	1280	EXTCLK / 8	11	0	0xB0
SY Int	9600	0.00%	1920	EXTCLK / 8	11	0	0x88



Table 22.4. Timer Settings for Standard Baud Rates Using an External 18.432 MHz
Oscillator

	Frequency: 18.432 MHz									
Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select)*	T1M*	Timer 1 Reload Value (hex)				

X = Don't care

\*Note: SCA1-SCA0 and T1M bit definitions can be found in Section 23.1.



Table 22.5. Timer Settings for Standard Baud Rates Using an External 11.0592 MHz Oscillator

Target		riequei	1CV. 11.U39Z	IVI 🗆 /					
Target		Frequency: 11.0592 MHz							
Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select) <sup>*</sup>	T1M <sup>*</sup>	Timer 1 Reload Value (hex)			
230400	0.00%	48	SYSCLK	XX	1	0xE8			
115200	0.00%	96	SYSCLK	XX	1	0xD0			
57600	0.00%	192	SYSCLK	XX	1	0xA0			
28800	0.00%	384	SYSCLK	XX	1	0x40			
14400	0.00%	768	SYSCLK / 12	00	0	0xE0			
9600	0.00%	1152	SYSCLK / 12	00	0	0xD0			
2400	0.00%	4608	SYSCLK / 12	00	0	0x40			
1200	0.00%	9216	SYSCLK / 48	10	0	0xA0			
230400	0.00%	48	EXTCLK / 8	11	0	0xFD			
115200	0.00%	96	EXTCLK / 8	11	0	0xFA			
57600	0.00%	192	EXTCLK / 8	11	0	0xF4			
28800	0.00%	384	EXTCLK / 8	11	0	0xE8			
14400	0.00%	768	EXTCLK / 8	11	0	0xD0			
9600	0.00%	1152	EXTCLK / 8	11	0	0xB8			
	230400 115200 57600 28800 14400 9600 2400 1200 230400 115200 57600 28800 14400	Baud Rate (bps)         % Error           230400         0.00%           115200         0.00%           57600         0.00%           28800         0.00%           14400         0.00%           2400         0.00%           1200         0.00%           230400         0.00%           115200         0.00%           57600         0.00%           28800         0.00%           14400         0.00%	Baud Rate (bps)         % Error (bps)         Divide Factor           230400         0.00%         48           115200         0.00%         96           57600         0.00%         192           28800         0.00%         384           14400         0.00%         768           9600         0.00%         4608           1200         0.00%         9216           230400         0.00%         48           115200         0.00%         96           57600         0.00%         192           28800         0.00%         384           14400         0.00%         768           9600         0.00%         1152	Baud Rate (bps)         % Error (bps)         Divide Factor         Source Source           230400         0.00%         48         SYSCLK           115200         0.00%         96         SYSCLK           57600         0.00%         192         SYSCLK           28800         0.00%         384         SYSCLK / 12           9600         0.00%         768         SYSCLK / 12           2400         0.00%         4608         SYSCLK / 12           1200         0.00%         9216         SYSCLK / 48           230400         0.00%         48         EXTCLK / 8           115200         0.00%         96         EXTCLK / 8           57600         0.00%         192         EXTCLK / 8           28800         0.00%         384         EXTCLK / 8           14400         0.00%         768         EXTCLK / 8           9600         0.00%         1152         EXTCLK / 8	Baud Rate (bps)         % Error (bps)         Divide Factor         Source select)*         (pre-scale select)*           230400         0.00%         48         SYSCLK         XX           115200         0.00%         96         SYSCLK         XX           57600         0.00%         192         SYSCLK         XX           28800         0.00%         384         SYSCLK         XX           14400         0.00%         768         SYSCLK / 12         00           9600         0.00%         1152         SYSCLK / 12         00           2400         0.00%         4608         SYSCLK / 12         00           1200         0.00%         9216         SYSCLK / 48         10           230400         0.00%         48         EXTCLK / 8         11           15200         0.00%         96         EXTCLK / 8         11           28800         0.00%         384         EXTCLK / 8         11           14400         0.00%         768         EXTCLK / 8         11           9600         0.00%         1152         EXTCLK / 8         11	Baud Rate (bps)         % Error (bps)         Divide Factor         Source select)*         (pre-scale select)*           230400         0.00%         48         SYSCLK         XX         1           115200         0.00%         96         SYSCLK         XX         1           57600         0.00%         192         SYSCLK         XX         1           28800         0.00%         384         SYSCLK         XX         1           14400         0.00%         768         SYSCLK / 12         00         0           9600         0.00%         1152         SYSCLK / 12         00         0           2400         0.00%         4608         SYSCLK / 12         00         0           1200         0.00%         9216         SYSCLK / 48         10         0           230400         0.00%         48         EXTCLK / 8         11         0           115200         0.00%         96         EXTCLK / 8         11         0           28800         0.00%         384         EXTCLK / 8         11         0           14400         0.00%         768         EXTCLK / 8         11         0           9600			

X = Don't care

\*Note: SCA1-SCA0 and T1M bit definitions can be found in Section 23.1.

Table 22.6. Timer Settings for Standard Baud Rates Using an External 3.6864 MHz
Oscillator

	Frequency: 3.6864 MHz							
	Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select)*	T1M*	Timer 1 Reload Value (hex)	
	230400	0.00%	16	SYSCLK	XX	1	0xF8	
	115200	0.00%	32	SYSCLK	XX	1	0xF0	
	57600	0.00%	64	SYSCLK	XX	1	0xE0	
from Osc.	28800	0.00%	128	SYSCLK	XX	1	0xC0	
	14400	0.00%	256	SYSCLK	XX	1	0x80	
SYSCLK External	9600	0.00%	384	SYSCLK	XX	1	0x40	
'SC teri	2400	0.00%	1536	SYSCLK / 12	00	0	0xC0	
S EX	1200	0.00%	3072	SYSCLK / 12	00	0	0x80	
	230400	0.00%	16	EXTCLK / 8	11	0	0xFF	
from )sc.	115200	0.00%	32	EXTCLK / 8	11	0	0xFE	
	57600	0.00%	64	EXTCLK / 8	11	0	0xFC	
	28800	0.00%	128	EXTCLK / 8	11	0	0xF8	
SYSCL  Internal	14400	0.00%	256	EXTCLK / 8	11	0	0xF0	
SY Inte	9600	0.00%	384	EXTCLK / 8	11	0	0xE8	



Table 22.6. Timer Settings for Standard Baud Rates Using an External 3.6864 MHz
Oscillator

Frequency: 3.6864 MHz							
Target Baud Rate (bps)	Baud Rate % Error	Oscillator Divide Factor	Timer Clock Source	SCA1-SCA0 (pre-scale select)*	T1M*	Timer 1 Reload Value (hex)	

X = Don't care

\*Note: SCA1-SCA0 and T1M bit definitions can be found in Section 23.1.



#### 23. Timers

Each MCU includes 5 counter/timers: Timer 0 and Timer 1 are 16-bit counter/timers compatible with those found in the standard 8051. Timer 2, Timer 3, and Timer 4 are 16-bit auto-reload and capture counter/timers for use with the ADC, DAC's, square-wave generation, or for general-purpose use. These timers can be used to measure time intervals, count external events and generate periodic interrupt requests. Timer 0 and Timer 1 are nearly identical and have four primary modes of operation. Timers 2, 3, and 4 are identical, and offer not only 16-bit auto-reload and capture, but have the ability to produce a 50% duty-cycle square-wave (toggle output) at an external port pin.

Timer 0 and Timer 1 Modes:	Timer 2, 3, and 4 Modes:
13-bit counter/timer	16-bit counter/timer with auto-reload
16-bit counter/timer	16-bit counter/timer with capture
8-bit counter/timer with auto-reload	Toggle Output
Two 8-bit counter/timers (Timer 0 only)	

Timers 0 and 1 may be clocked by one of five sources, determined by the Timer Mode Select bits (T1M-T0M) and the Clock Scale bits (SCA1-SCA0). The Clock Scale bits define a pre-scaled clock by which Timer 0 and/or Timer 1 may be clocked (See SFR Definition 23.3 for pre-scaled clock selection). Timer 0/1 may then be configured to use this pre-scaled clock signal or the system clock. Timers 2, 3, and 4 may be clocked by the system clock, the system clock divided by 12, or the external oscillator clock source divided by 8.

Timer 0 and Timer 1 may also be operated as counters. When functioning as a counter, a counter/timer register is incremented on each high-to-low transition at the selected input pin. Events with a frequency of up to one-fourth the system clock's frequency can be counted. The input signal need not be periodic, but it should be held at a given logic level for at least two full system clock cycles to ensure the level is properly sampled.

#### 23.1. Timer 0 and Timer 1

Each timer is implemented as 16-bit register accessed as two separate bytes: a low byte (TL0 or TL1) and a high byte (TH0 or TH1). The Counter/Timer Control register (TCON) is used to enable Timer 0 and Timer 1 as well as indicate their status. Timer 0 interrupts can be enabled by setting the ET0 bit in the IE register (Section "12.3.5. Interrupt Register Descriptions" on page 156); Timer 1 interrupts can be enabled by setting the ET1 bit in the IE register (Section 12.3.5). Both counter/timers operate in one of four primary modes selected by setting the Mode Select bits T1M1-T0M0 in the Counter/Timer Mode register (TMOD). Each timer can be configured independently.

#### 23.1.1. Mode 0: 13-bit Counter/Timer

Timer 0 and Timer 1 operate as 13-bit counter/timers in Mode 0. The following describes the configuration and operation of Timer 0. However, both timers operate identically, and Timer 1 is configured in the same manner as described for Timer 0.

The TH0 register holds the eight MSBs of the 13-bit counter/timer. TL0 holds the five LSBs in bit positions TL0.4-TL0.0. The three upper bits of TL0 (TL0.7-TL0.5) are indeterminate and should be masked out or ignored when reading. As the 13-bit timer register increments and overflows from 0x1FFF (all ones) to 0x0000, the timer overflow flag TF0 (TCON.5) is set and an interrupt will occur if Timer 0 interrupts are enabled.



The C/T0 bit (TMOD.2) selects the counter/timer's clock source. When C/T0 is set to logic 1, high-to-low transitions at the selected Timer 0 input pin (T0) increment the timer register (Refer to **Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204** for information on selecting and configuring external I/O pins). Clearing C/T0 selects the clock defined by the T0M bit (CKCON.3). When T0M is set, Timer 0 is clocked by the system clock. When T0M is cleared, Timer 0 is clocked by the source selected by the Clock Scale bits in CKCON (see SFR Definition 23.3).

Setting the TR0 bit (TCON.4) enables the timer when either GATE0 (TMOD.3) is logic 0 or the input signal /INT0 is logic-level 1. Setting GATE0 to '1' allows the timer to be controlled by the external input signal / INT0 (see Section "12.3.5. Interrupt Register Descriptions" on page 156), facilitating pulse width measurements.

TR0	GATE0	/INT0	Counter/Timer						
0	Х	Х	Disabled						
1	0	Х	Enabled						
1	1	0	Disabled						
1	1	1	Enabled						
Note: X = Don't Care									

Setting TR0 does not force the timer to reset. The timer registers should be loaded with the desired initial value before the timer is enabled.

TL1 and TH1 form the 13-bit register for Timer 1 in the same manner as described above for TL0 and TH0. Timer 1 is configured and controlled using the relevant TCON and TMOD bits just as with Timer 0. The input signal /INT1 is used with Timer 1.




Figure 23.1. T0 Mode 0 Block Diagram

#### 23.1.2. Mode 1: 16-bit Counter/Timer

Mode 1 operation is the same as Mode 0, except that the counter/timer registers use all 16 bits. The counter/timers are enabled and configured in Mode 1 in the same manner as for Mode 0.



#### 23.1.3. Mode 2: 8-bit Counter/Timer with Auto-Reload

Mode 2 configures Timer 0 and Timer 1 to operate as 8-bit counter/timers with automatic reload of the start value. TL0 holds the count and TH0 holds the reload value. When the counter in TL0 overflows from 0xFF to 0x00, the timer overflow flag TF0 (TCON.5) is set and the counter in TL0 is reloaded from TH0. If Timer 0 interrupts are enabled, an interrupt will occur when the TF0 flag is set. The reload value in TH0 is not changed. TL0 must be initialized to the desired value before enabling the timer for the first count to be correct. When in Mode 2, Timer 1 operates identically to Timer 0.

Both counter/timers are enabled and configured in Mode 2 in the same manner as Mode 0. Setting the TR0 bit (TCON.4) enables the timer when either GATE0 (TMOD.3) is logic 0 or when the input signal /INT0 is low.




Figure 23.2. T0 Mode 2 Block Diagram



#### 23.1.4. Mode 3: Two 8-bit Counter/Timers (Timer 0 Only)

In Mode 3, Timer 0 is configured as two separate 8-bit counter/timers held in TL0 and TH0. The counter/timer in TL0 is controlled using the Timer 0 control/status bits in TCON and TMOD: TR0, C/T0, GATE0 and TF0. TL0 can use either the system clock or an external input signal as its timebase. The TH0 register is restricted to a timer function sourced by the system clock or prescaled clock. TH0 is enabled using the Timer 1 run control bit TR1. TH0 sets the Timer 1 overflow flag TF1 on overflow and thus controls the Timer 1 interrupt.

Timer 1 is inactive in Mode 3. When Timer 0 is operating in Mode 3, Timer 1 can be operated in Modes 0, 1 or 2, but cannot be clocked by external signals nor set the TF1 flag and generate an interrupt. However, the Timer 1 overflow can be used to generate baud rates for the SMBus and/or UART, and/or initiate ADC conversions. While Timer 0 is operating in Mode 3, Timer 1 run control is handled through its mode settings. To run Timer 1 while Timer 0 is in Mode 3, set the Timer 1 Mode as 0, 1, or 2. To disable Timer 1, configure it for Mode 3.




Figure 23.3. T0 Mode 3 Block Diagram



#### SFR Definition 23.1. TCON: Timer Control

R/W	Reset Value							
TF1	TR1	TF0	TR0	IE1	IT1	IE0	IT0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: 0x88 SFR Page: 0

Bit7: TF1: Timer 1 Overflow Flag.

Set by hardware when Timer 1 overflows. This flag can be cleared by software but is automatically cleared when the CPU vectors to the Timer 1 interrupt service routine.

0: No Timer 1 overflow detected.

1: Timer 1 has overflowed.

Bit6: TR1: Timer 1 Run Control.

0: Timer 1 disabled.

1: Timer 1 enabled.

Bit5: TF0: Timer 0 Overflow Flag.

Set by hardware when Timer 0 overflows. This flag can be cleared by software but is automatically cleared when the CPU vectors to the Timer 0 interrupt service routine.

0: No Timer 0 overflow detected.

1: Timer 0 has overflowed.

Bit4: TR0: Timer 0 Run Control.

0: Timer 0 disabled.

1: Timer 0 enabled.

Bit3: IE1: External Interrupt 1.

This flag is set by hardware when an edge/level of type defined by IT1 is detected. It can be cleared by software but is automatically cleared when the CPU vectors to the External Interrupt 1 service routine if IT1 = 1. This flag is the inverse of the /INT1 signal.

Bit2: IT1: Interrupt 1 Type Select.

This bit selects whether the configured /INT1 interrupt will be falling-edge sensitive or active-low.

0: /INT1 is level triggered, active-low.

1: /INT1 is edge triggered, falling-edge.

Bit1: IE0: External Interrupt 0.

This flag is set by hardware when an edge/level of type defined by IT0 is detected. It can be cleared by software but is automatically cleared when the CPU vectors to the External Interrupt 0 service routine if IT0 = 1. This flag is the inverse of the /INT0 signal.

Bit0: IT0: Interrupt 0 Type Select.

This bit selects whether the configured /INT0 interrupt will be falling-edge sensitive or active-low

0: /INT0 is level triggered, active logic-low.

1: /INT0 is edge triggered, falling-edge.



#### SFR Definition 23.2. TMOD: Timer Mode

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
GATE1	C/T1	T1M1	T1M0	GATE0	C/T0	T0M1	T0M0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>

SFR Address: 0x89 SFR Page: 0

Bit7: GATE1: Timer 1 Gate Control.

0: Timer 1 enabled when TR1 = 1 irrespective of /INT1 logic level.

1: Timer 1 enabled only when TR1 = 1 AND /INT1 = logic 1.

Bit6: C/T1: Counter/Timer 1 Select.

0: Timer Function: Timer 1 incremented by clock defined by T1M bit (CKCON.4).

1: Counter Function: Timer 1 incremented by high-to-low transitions on external input pin

(T1).

Bits5-4: T1M1-T1M0: Timer 1 Mode Select.

These bits select the Timer 1 operation mode.

T1M1	T1M0	Mode					
0	0	Mode 0: 13-bit counter/timer					
0	1	Mode 1: 16-bit counter/timer					
1	0	Mode 2: 8-bit counter/timer with auto-reload					
1	1	Mode 3: Timer 1 inactive					

Bit3: GATE0: Timer 0 Gate Control.

0: Timer 0 enabled when TR0 = 1 irrespective of /INT0 logic level.

1: Timer 0 enabled only when TR0 = 1 AND /INT0 = logic 1.

Bit2: C/T0: Counter/Timer Select.

0: Timer Function: Timer 0 incremented by clock defined by T0M bit (CKCON.3).

1: Counter Function: Timer 0 incremented by high-to-low transitions on external input pin

(T0).

Bits1-0: T0M1-T0M0: Timer 0 Mode Select.

These bits select the Timer 0 operation mode.

T0M1	TOMO	Mode
0	0	Mode 0: 13-bit counter/timer
0	1	Mode 1: 16-bit counter/timer
1	0	Mode 2: 8-bit counter/timer with auto-reload
1	1	Mode 3: Two 8-bit counter/timers



#### SFR Definition 23.3. CKCON: Clock Control

R/W	Reset Value							
-	-	-	T1M	TOM	-	SCA1	SCA0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>

SFR Address: 0x8E SFR Page: 0

Bits7-5: UNUSED. Read = 000b, Write = don't care.

Bit4: T1M: Timer 1 Clock Select.

This select the clock source supplied to Timer 1. T1M is ignored when C/T1 is set to logic 1.

0: Timer 1 uses the clock defined by the prescale bits, SCA1-SCA0.

1: Timer 1 uses the system clock.

Bit3: T0M: Timer 0 Clock Select.

This bit selects the clock source supplied to Timer 0. T0M is ignored when C/T0 is set to

logic 1.

0: Counter/Timer 0 uses the clock defined by the prescale bits, SCA1-SCA0.

1: Counter/Timer 0 uses the system clock.

Bit2: UNUSED. Read = 0b, Write = don't care.

Bits1-0: SCA1-SCA0: Timer 0/1 Prescale Bits

These bits control the division of the clock supplied to Timer 0 and/or Timer 1 if configured to use prescaled clock inputs.

SCA1							
0	0	System clock divided by 12					
0	System clock divided by 4						
1	0	System clock divided by 48					
1	1	External clock divided by 8					

#### SFR Definition 23.4. TL0: Timer 0 Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0x8A SFR Page: 0

Bits 7-0: TL0: Timer 0 Low Byte.

The TL0 register is the low byte of the 16-bit Timer 0.



## SFR Definition 23.5. TL1: Timer 1 Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Rit4	Bit3	Rit2	Rit1	Bit0	

SFR Address: 0x8B SFR Page: 0

Bits 7-0: TL1: Timer 1 Low Byte.

The TL1 register is the low byte of the 16-bit Timer 1.

## SFR Definition 23.6. TH0: Timer 0 High Byte

	R/W	Reset Value							
									00000000
-	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: 0x8C SFR Page: 0

Bits 7-0: TH0: Timer 0 High Byte.

The TH0 register is the high byte of the 16-bit Timer 0.

## SFR Definition 23.7. TH1: Timer 1 High Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0x8D SFR Page: 0

Bits 7-0: TH1: Timer 1 High Byte.

The TH1 register is the high byte of the 16-bit Timer 1.



#### 23.2. Timer 2, Timer 3, and Timer 4

Timers n are 16-bit counter/timers, each formed by two 8-bit SFRs: TMRnL (low byte) and TMRnH (high byte) where n = 2, 3, and 4 for timers 2, 3, and 4 respectively. These timers feature auto-reload, capture, and toggle output modes with the ability to count up or down. Capture Mode and Auto-reload mode are selected using bits in the Timer n Control registers (TMRnCN). Toggle output mode is selected using the Timer 2, 3, and 4 Configuration registers (TMRnCF). These timers may also be used to generate a square-wave at an external pin. As with Timers 0 and 1, Timers n can use either the system clock (divided by one, two, or twelve), external clock (divided by eight) or transitions on an external input pin as its clock source. The Counter/Timer Select bit C/Tn (TMRnCN.1) configures the peripheral as a counter or timer. Clearing C/Tn configures the Timer to be in a timer mode (i.e., the system clock or external clock as input for the timer). When C/Tn is set to 1, the timer is configured as a counter (i.e., high-to-low transitions at the Tn input pin increment (or decrement) the counter/timer register). Refer to Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204 for information on selecting and configuring external I/O pins for digital peripherals, such as the Tn pin. Timer 2 and 3 can be used to start an ADC Data Conversion and Timers 2, 3, and 4 can schedule DAC outputs. Only Timer 1 can be used to generate baud rates for UART 1, and Timers 1, 2, 3, or 4 may be used to generate baud rates for UART 0.

Timer n can use either SYSCLK, SYSCLK divided by 2, SYSCLK divided by 12, an external clock divided by 8, or high-to-low transitions on the Tn input pin as its clock source when operating in Counter/Timer with Capture mode. Clearing the C/Tn bit (TMRnCN.1) selects the system clock/external clock as the input for the timer. The Timer Clock Select bits TnM0 and TnM1 in TMRnCF can be used to select the system clock undivided, system clock divided by two, system clock divided by 12, or an external clock provided at the XTAL1/XTAL2 pins divided by 8 (see SFR Definition 23.9). When C/Tn is set to logic 1, a high-to-low transition at the Tn input pin increments the counter/timer register (i.e., configured as a counter).

#### 23.2.1. Configuring Timer 2, 3, and 4 to Count Down

Timers 2, 3, and 4 have the ability to count down. When the timer's respective Decrement Enable Bit (DCEN) in the Timer Configuration Register (See SFR Definition 23.9) is set to '1', the timer can then count *up* or *down*. When DCEN = 1, the direction of the timer's count is controlled by the TnEX pin's logic level. When TnEX = 1, the counter/timer will count up; when TnEX = 0, the counter/timer will count down. To use this feature, TnEX must be enabled in the digital crossbar and configured as a digital input.

Note: When DCEN = 1, other functions of the TnEX input (i.e., capture and auto-reload) are not available. TnEX will only control the direction of the timer when DCEN = 1.



#### 23.2.2. Capture Mode

In Capture Mode, Timer n will operate as a 16-bit counter/timer with capture facility. When the Timer External Enable bit (found in the TMRnCN register) is set to '1', a high-to-low transition on the TnEX input pin causes the 16-bit value in the associated timer (TMRnH, TMRnL) to be loaded into the capture registers (RCAPnH, RCAPnL). If a capture is triggered in the counter/timer, the Timer External Flag (TMRnCN.6) will be set to '1' and an interrupt will occur if the interrupt is enabled. See **Section "12.3. Interrupt Handler" on page 153** for further information concerning the configuration of interrupt sources.

As the 16-bit timer register increments and overflows TMRnH:TMRnL, the TFn Timer Overflow/Underflow Flag (TMRnCN.7) is set to '1' and an interrupt will occur if the interrupt is enabled. The timer can be configured to count down by setting the Decrement Enable Bit (TMRnCF.0) to '1'. This will cause the timer to decrement with every timer clock/count event and underflow when the timer transitions from 0x0000 to 0xFFFF. Just as in overflows, the Overflow/Underflow Flag (TFn) will be set to '1', and an interrupt will occur if enabled.

Counter/Timer with Capture mode is selected by setting the Capture/Reload Select bit CP/RLn (TMRnCN.0) and the Timer n Run Control bit TRn (TMRnCN.2) to logic 1. The Timer n respective External Enable EXENn (TMRnCN.3) must also be set to logic 1 to enable captures. If EXENn is cleared, transitions on TnEX will be ignored.




Figure 23.4. Tn Capture Mode Block Diagram



#### 23.2.3. Auto-Reload Mode

In Auto-Reload Mode, the counter/timer can be configured to count up or down and cause an interrupt/flag to occur upon an overflow/underflow event. When counting up, the counter/timer will set its overflow/underflow flag (TFn) and cause an interrupt (if enabled) upon overflow/underflow, the values in the Reload/Capture Registers (RCAPnH and RCAPnL) are loaded into the timer, and the timer is restarted. When the Timer External Enable Bit (EXENn) bit is set to '1' and the Decrement Enable Bit (DCEN) is '0', a '1'-to-'0' transition on the TnEX pin (configured as an input in the digital crossbar) will cause a timer reload (in addition to timer overflows causing auto-reloads). When DCEN is set to '1', the state of the TnEX pin controls whether the counter/timer counts *up* (increments) or *down* (decrements), and will not cause an auto-reload or interrupt event. See Section 23.2.1 for information concerning configuration of a timer to count down.

When counting down, the counter/timer will set its overflow/underflow flag (TFn) and cause an interrupt (if enabled) when the value in the timer (TMRnH and TMRnL registers) matches the 16-bit value in the Reload/Capture Registers (RCAPnH and RCAPnL). This is considered an underflow event, and will cause the timer to load the value 0xFFFF. The timer is automatically restarted when an underflow occurs.

Counter/Timer with Auto-Reload mode is selected by clearing the CP/RLn bit. Setting TRn to logic 1 enables and starts the timer.

In Auto-Reload Mode, the External Flag (EXFn) toggles upon every overflow or underflow and does not cause an interrupt. The EXFn flag can be thought of as the most significant bit (MSB) of a 17-bit counter.




Figure 23.5. Tn Auto-reload Mode and Toggle Mode Block Diagram



#### 23.2.4. Toggle Output Mode

Timer n have the capability to toggle the state of their respective output port pins (T2, T3, or T4) to produce a 50% duty cycle waveform output. The port pin state will change upon the overflow or underflow of the respective timer (depending on whether the timer is counting *up* or *down*). The toggle frequency is determined by the clock source of the timer and the values loaded into RCAPnH and RCAPnL. When counting DOWN, the auto-reload value for the timer is 0xFFFF, and underflow will occur when the value in the timer matches the value stored in RCAPnH:RCAPnL. When counting UP, the auto-reload value for the timer is RCAPnH:RCAPnL, and overflow will occur when the value in the timer transitions from 0xFFFF to the reload value.

To output a square wave, the timer is placed in reload mode (the Capture/Reload Select Bit in TMRnCN and the Timer/Counter Select Bit in TMRnCN are cleared to '0'). The timer output is enabled by setting the Timer Output Enable Bit in TMRnCF to '1'. The timer should be configured via the timer clock source and reload/underflow values such that the timer overflow/underflows at 1/2 the desired output frequency. The port pin assigned by the crossbar as the timer's output pin should be configured as a digital output (see Section "17. Port Input/Output" on page 203). Setting the timer's Run Bit (TRn) to '1' will start the toggle of the pin. A Read/Write of the Timer's Toggle Output State Bit (TMRnCF.2) is used to read the state of the toggle output, or to force a value of the output. This is useful when it is desired to start the toggle of a pin in a known state, or to force the pin into a desired state when the toggle mode is halted.

$$F_{sq} = \frac{F_{TCLK}}{2 \times (65536 - RCAPn)}$$

### **Equation 23.1. Square Wave Frequency**

Equation 23.1 applies regardless of whether the timer is configured to count up or down.



#### SFR Definition 23.8. TMRnCN: Timer n Control

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
TFn	EXFn	-	-	EXENn	TRn	C/Tn	CP/RLn	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: TMR2CN:0xC8;TMR3CN:0xC8;TMR4CN:0xC8 SFR Page: TMR2CN: page 0;TMR3CN: page 1;TMR4CN: page 2

Bit7: TFn: Timer n Overflow/Underflow Flag.

Set by hardware when either the Timer overflows from 0xFFFF to 0x0000, underflows from the value placed in RCAPnH:RCAPnL to 0xFFFF (in Auto-reload Mode), or underflows from 0x0000 to 0xFFFF (in Capture Mode). When the Timer interrupt is enabled, setting this bit causes the CPU to vector to the Timer interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit6: EXFn: Timer 2, 3, or 4 External Flag.

Set by hardware when either a capture or reload is caused by a high-to-low transition on the TnEX input pin and EXENn is logic 1. When the Timer interrupt is enabled, setting this bit causes the CPU to vector to the Timer Interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit5-4: Reserved.

Bit3: EXENn: Timer n External Enable.

Enables high-to-low transitions on TnEX to trigger captures, reloads, and control the direction of the timer/counter (up or down count). If DECEN = 1, TnEX will determine if the timer counts up or down when in Auto-reload Mode. If EXENn = 1, TnEX should be configured as a digital input.

0: Transitions on the TnEX pin are ignored.

1: Transitions on the TnEX pin cause capture, reload, or control the direction of timer count (up or down) as follows:

<u>Capture Mode</u>: '1'-to-'0' Transition on TnEX pin causes RCAPnH:RCAPnL to capture timer value.

Auto-Reload Mode:

DCEN = 0: '1'-to-'0' transition causes reload of timer and sets the EXFn Flag.

DCEN = 1: TnEX logic level controls direction of timer (up or down).

Bit2: TRn: Timer n Run Control.

This bit enables/disables the respective Timer.

0: Timer disabled.

1: Timer enabled and running/counting.

Bit1: C/Tn: Counter/Timer Select.

0: Timer Function: Timer incremented by clock defined by TnM1:TnM0

(TMRnCF.4:TMRnCF.3).

1: Counter Function: Timer incremented by high-to-low transitions on external input pin.

Bit0: CP/RLn: Capture/Reload Select.

This bit selects whether the Timer functions in capture or auto-reload mode.

0: Timer is in Auto-Reload Mode.

1: Timer is in Capture Mode.



### SFR Definition 23.9. TMRnCF: Timer n Configuration

				R/W	R/W	R/W	R/W	R/W	Reset Value
ſ	-	-	-	TnM1	TnM0	TOGn	TnOE	DCEN	00000000
_	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	Bit Addressable

SFR Address: TMR2CF:0xC9;TMR3CF:0xC9;TMR4CF:0xC9 SFR Page TMR2CF: page 0;TMR3CF: page 1;TMR4CF: page 2

Bit7-5: Reserved.

Bit4-3: TnM1 and TnM0: Timer Clock Mode Select Bits.

Bits used to select the Timer clock source. The sources can be the System Clock (SYSCLK), SYSCLK divided by 2 or 12, or an external clock signal routed to Tn (port pin)

divided by 8. Clock source is selected as follows:

00: SYSCLK/12 01: SYSCLK

10: EXTERNAL CLOCK/8

11: SYSCLK/2

Bit2: TOGn: Toggle output state bit.

When timer is used to toggle a port pin, this bit can be used to read the state of the output, or

can be written to in order to force the state of the output.

Bit1: TnOE: Timer output enable bit.

This bit enables the timer to output a 50% duty cycle output to the timer's assigned external

port pin.

<u>NOTE</u>: A timer is configured for Square Wave Output as follows:

CP/RLn = 0 C/Tn = 0TnOE = 1

Load RCAPnH:RCAPnL (See Section "Equation 23.1. Square Wave Frequency" on page 298).

Configure Port Pin for output (See Section "17. Port Input/Output" on page 203).

0: Output of toggle mode not available at Timers' assigned port pin.

1: Output of toggle mode available at Timers' assigned port pin.

Bit0: DCEN: Decrement Enable Bit.

This bit enables the timer to count up or down as determined by the state of TnEX.

0: Timer will count up, regardless of the state of TnEX.

1: Timer will count up or down depending on the state of TnEX as follows:

if TnEX = 0, the timer counts DOWN if TnEX = 1, the timer counts UP.



### SFR Definition 23.10. RCAPnL: Timer n Capture Register Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: RCAP2L: 0xCA; RCAP3L: 0xCA; RCAP4L: 0xCA SFR Page: RCAP2L: page 0; RCAP3L: page 1; RCAP4L: page 2

Bits 7-0: RCAPnL: Timer n Capture Register Low Byte.

The RCAPnL register captures the low byte of Timer n when Timer n is configured in capture mode. When Timer n is configured in auto-reload mode, it holds the low byte of the reload value.

### SFR Definition 23.11. RCAPnH: Timer n Capture Register High Byte

	R/W	Reset Value							
									00000000
-	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

SFR Address: RCAP2H: 0xCB; RCAP3H: 0xCB; RCAP4H: 0xCB SFR Page: RCAP2H: page 0; RCAP3H: page 1; RCAP4H: page 2

Bits 7-0: RCAPnH: Timer n Capture Register High Byte.

The RCAPnH register captures the high byte of Timer n when Timer n is configured in capture mode. When Timer n is configured in auto-reload mode, it holds the high byte of the reload value.

#### SFR Definition 23.12. TMRnL: Timer n Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u> </u>

SFR Address: TMR2L: 0xCC; TMR3L: 0xCC; TMR4L: 0xCC SFR Page: TMR2L: page 0; TMR3L: page 1; TMR4L: page 2

Bits 7-0: TMRnL: Timer n Low Byte.

The TMRnL register contains the low byte of the 16-bit Timer n



## SFR Definition 23.13. TMRnH Timer n High Byte

	R/W	Reset Value							
									00000000
_	Rit7	Bit6	Bit5	Rit4	Bit3	Rit2	Rit1	Bit0	

SFR Address: TMR2H: 0xCD; TMR3H: 0xCD; TMR4H: 0xCD SFR Page: TMR2H: page 0; TMR3H: page 1; TMR4H: page 2

Bits 7-0: TMRnH: Timer n High Byte.

The TMRnH register contains the high byte of the 16-bit Timer n



## 24. Programmable Counter Array

The Programmable Counter Array (PCA0) provides enhanced timer functionality while requiring less CPU intervention than the standard 8051 counter/timers. PCA0 consists of a dedicated 16-bit counter/timer and six 16-bit capture/compare modules. Each capture/compare module has its own associated I/O line (CEXn) which is routed through the Crossbar to Port I/O when enabled (See Section "17.1. Ports 0 through 3 and the Priority Crossbar Decoder" on page 204). The counter/timer is driven by a programmable timebase that can select between six inputs as its source: system clock, system clock divided by four, system clock divided by twelve, the external oscillator clock source divided by 8, Timer 0 overflow, or an external clock signal on the ECI line. Each capture/compare module may be configured to operate independently in one of six modes: Edge-Triggered Capture, Software Timer, High-Speed Output, Frequency Output, 8-Bit PWM, or 16-Bit PWM (each is described in Section 24.2). The PCA is configured and controlled through the system controller's Special Function Registers. The basic PCA block diagram is shown in Figure 24.1.




Figure 24.1. PCA Block Diagram



#### 24.1. PCA Counter/Timer

The 16-bit PCA counter/timer consists of two 8-bit SFRs: PCA0L and PCA0H. PCA0H is the high byte (MSB) of the 16-bit counter/timer and PCA0L is the low byte (LSB). Reading PCA0L automatically latches the value of PCA0H into a "snapshot" register; the following PCA0H read accesses this "snapshot" register. Reading the PCA0L Register first guarantees an accurate reading of the entire 16-bit PCA0 counter. Reading PCA0H or PCA0L does not disturb the counter operation. The CPS2-CPS0 bits in the PCA0MD register select the timebase for the counter/timer as shown in Table 24.1. Note that in 'External oscillator source divided by 8' mode, the external oscillator source is synchronized with the system clock, and must have a frequency less than or equal to the system clock.

When the counter/timer overflows from 0xFFFF to 0x0000, the Counter Overflow Flag (CF) in PCA0MD is set to logic 1 and an interrupt request is generated if CF interrupts are enabled. Setting the ECF bit in PCA0MD to logic 1 enables the CF flag to generate an interrupt request. The CF bit is not automatically cleared by hardware when the CPU vectors to the interrupt service routine, and must be cleared by software (Note: PCA0 interrupts must be globally enabled before CF interrupts are recognized. PCA0 interrupts are globally enabled by setting the EA bit (IE.7) and the EPCA0 bit in EIE1 to logic 1). Clearing the CIDL bit in the PCA0MD register allows the PCA to continue normal operation while the CPU is in Idle mode.

CPS2	CPS1	CPS0	Timebase
0	0	0	System clock divided by 12
0	0	1	System clock divided by 4
0	1	0	Timer 0 overflow
0	1	1	High-to-low transitions on ECI <sup>1</sup> (max rate = system clock divided by 4)
1	0	0	System clock
1	0	1	External clock divided by 8 <sup>2</sup>

**Table 24.1. PCA Timebase Input Options** 

#### Notes:

- 1. The minimum high or low time for the ECI input signal is at least 2 system clock cycles.
- 2. External oscillator source divided by 8 is synchronized with the system clock.




Figure 24.2. PCA Counter/Timer Block Diagram

#### 24.2. Capture/Compare Modules

Each module can be configured to operate independently in one of six operation modes: Edge-triggered Capture, Software Timer, High Speed Output, Frequency Output, 8-Bit Pulse Width Modulator, or 16-Bit Pulse Width Modulator. Each module has Special Function Registers (SFRs) associated with it in the CIP-51 system controller. These registers are used to exchange data with a module and configure the module's mode of operation.

Table 24.2 summarizes the bit settings in the PCA0CPMn registers used to select the PCA0 capture/compare module's operating modes. Setting the ECCFn bit in a PCA0CPMn register enables the module's CCFn interrupt. Note: PCA0 interrupts must be globally enabled before individual CCFn interrupts are recognized. PCA0 interrupts are globally enabled by setting the EA bit (IE.7) and the EPCA0 bit (EIE1.3) to logic 1. See Figure 24.3 for details on the PCA interrupt configuration.

PWM16	ECOM	CAPP	CAPN	MAT	TOG	PWM	ECCF	Operation Mode
Х	Х	1	0	0	0	0	Х	Capture triggered by positive edge on CEXn
Х	Х	0	1	0	0	0	Х	Capture triggered by negative edge on CEXn
Х	Х	1	1	0	0	0	Х	Capture triggered by transition on CEXn
Х	1	0	0	1	0	0	Х	Software Timer
Х	1	0	0	1	1	0	Х	High-Speed Output
Х	1	0	0	0	1	1	Х	Frequency Output
0	1	0	0	0	0	1	0	8-Bit Pulse Width Modulator
1	1	0	0	0	0	1	0	16-Bit Pulse Width Modulator

X = Don't Care




Figure 24.3. PCA Interrupt Block Diagram



#### 24.2.1. Edge-triggered Capture Mode

In this mode, a valid transition on the CEXn pin causes PCA0 to capture the value of the PCA0 counter/ timer and load it into the corresponding module's 16-bit capture/compare register (PCA0CPLn and PCA0CPHn). The CAPPn and CAPNn bits in the PCA0CPMn register are used to select the type of transition that triggers the capture: low-to-high transition (positive edge), high-to-low transition (negative edge), or either transition (positive or negative edge). When a capture occurs, the Capture/Compare Flag (CCFn) in PCA0CN is set to logic 1 and an interrupt request is generated if CCF interrupts are enabled. The CCFn bit is not automatically cleared by hardware when the CPU vectors to the interrupt service routine, and must be cleared by software.

**Note**: The signal at the CEXn pin must be logic high or low for at least two system clock cycles in order for it to be recognized as valid by the hardware.




Figure 24.4. PCA Capture Mode Diagram



#### 24.2.2. Software Timer (Compare) Mode

In Software Timer mode, the PCA0 counter/timer is compared to the module's 16-bit capture/compare register (PCA0CPHn and PCA0CPLn). When a match occurs, the Capture/Compare Flag (CCFn) in PCA0CN is set to logic 1 and an interrupt request is generated if CCF interrupts are enabled. The CCFn bit is not automatically cleared by hardware when the CPU vectors to the interrupt service routine, and must be cleared by software. Setting the ECOMn and MATn bits in the PCA0CPMn register enables Software Timer mode.

**Important Note About Capture/Compare Registers:** When writing a 16-bit value to the PCA0 Capture/Compare registers, the low byte should always be written first. Writing to PCA0CPLn clears the ECOMn bit to '0'; writing to PCA0CPHn sets ECOMn to '1'.




Figure 24.5. PCA Software Timer Mode Diagram



#### 24.2.3. High-Speed Output Mode

In High-Speed Output mode, a module's associated CEXn pin is toggled each time a match occurs between the PCA Counter and the module's 16-bit capture/compare register (PCA0CPHn and PCA0CPLn). Setting the TOGn, MATn, and ECOMn bits in the PCA0CPMn register enables the High-Speed Output mode.

**Important Note About Capture/Compare Registers:** When writing a 16-bit value to the PCA0 Capture/Compare registers, the low byte should always be written first. Writing to PCA0CPLn clears the ECOMn bit to '0'; writing to PCA0CPHn sets ECOMn to '1'.




Figure 24.6. PCA High-Speed Output Mode Diagram



#### 24.2.4. Frequency Output Mode

Frequency Output Mode produces a programmable-frequency square wave on the module's associated CEXn pin. The capture/compare module high byte holds the number of PCA clocks to count before the output is toggled. The frequency of the square wave is then defined by Equation 24.1, where  $F_{PCA}$  is the frequency of the clock selected by the CPS2-0 bits in the PCA mode register, PCA0MD.

### **Equation 24.1. Square Wave Frequency Output**

$$F_{sqr} = \frac{F_{PCA}}{2 \times PCA0CPHn}$$

Note: A value of 0x00 in the PCA0CPHn register is equal to 256 for this equation.

The lower byte of the capture/compare module is compared to the PCA0 counter low byte; on a match, CEXn is toggled and the offset held in the high byte is added to the matched value in PCA0CPLn. Frequency Output Mode is enabled by setting the ECOMn, TOGn, and PWMn bits in the PCA0CPMn register.




Figure 24.7. PCA Frequency Output Mode



#### 24.2.5. 8-Bit Pulse Width Modulator Mode

Each module can be used independently to generate pulse width modulated (PWM) outputs on its associated CEXn pin. The frequency of the output is dependent on the timebase for the PCA0 counter/timer. The duty cycle of the PWM output signal is varied using the module's PCA0CPLn capture/compare register. When the value in the low byte of the PCA0 counter/timer (PCA0L) is equal to the value in PCA0CPLn, the output on the CEXn pin will be high. When the count value in PCA0L overflows, the CEXn output will be low (see Figure 24.8). Also, when the counter/timer low byte (PCA0L) overflows from 0xFF to 0x00, PCA0CPLn is reloaded automatically with the value stored in the counter/timer's high byte (PCA0H) without software intervention. Setting the ECOMn and PWMn bits in the PCA0CPMn register enables 8-Bit Pulse Width Modulator mode. The duty cycle for 8-Bit PWM Mode is given by Equation 24.2.

**Important Note About Capture/Compare Registers:** When writing a 16-bit value to the PCA0 Capture/Compare registers, the low byte should always be written first. Writing to PCA0CPLn clears the ECOMn bit to '0'; writing to PCA0CPHn sets ECOMn to '1'.

$$DutyCycle = \frac{(256 - PCA0CPHn)}{256}$$

### **Equation 24.2. 8-Bit PWM Duty Cycle**




Figure 24.8. PCA 8-Bit PWM Mode Diagram



#### 24.2.6. 16-Bit Pulse Width Modulator Mode

Each PCA0 module may also be operated in 16-Bit PWM mode. In this mode, the 16-bit capture/compare module defines the number of PCA0 clocks for the low time of the PWM signal. When the PCA0 counter matches the module contents, the output on CEXn is asserted high; when the counter overflows, CEXn is asserted low. To output a varying duty cycle, new value writes should be synchronized with PCA0 CCFn match interrupts. 16-Bit PWM Mode is enabled by setting the ECOMn, PWMn, and PWM16n bits in the PCA0CPMn register. For a varying duty cycle, CCFn should also be set to logic 1 to enable match interrupts. The duty cycle for 16-Bit PWM Mode is given by Equation 24.3.

**Important Note About Capture/Compare Registers:** When writing a 16-bit value to the PCA0 Capture/Compare registers, the low byte should always be written first. Writing to PCA0CPLn clears the ECOMn bit to '0'; writing to PCA0CPHn sets ECOMn to '1'.

$$DutyCycle = \frac{(65536 - PCA0CPn)}{65536}$$

## Equation 24.3. 16-Bit PWM Duty Cycle




Figure 24.9. PCA 16-Bit PWM Mode



#### 24.3. Register Descriptions for PCA0

Following are detailed descriptions of the special function registers related to the operation of PCA0.

#### SFR Definition 24.1. PCA0CN: PCA Control

R/W	Reset Value							
CF	CR	CCF5	CCF4	CCF3	CCF2	CCF1	CCF0	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xD8 SFR Page: 0

Bit7: CF: PCA Counter/Timer Overflow Flag.

Set by hardware when the PCA0 Counter/Timer overflows from 0xFFFF to 0x0000. When the Counter/Timer Overflow (CF) interrupt is enabled, setting this bit causes the CPU to vector to the CF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit6: CR: PCA0 Counter/Timer Run Control.

This bit enables/disables the PCA0 Counter/Timer.

0: PCA0 Counter/Timer disabled.1: PCA0 Counter/Timer enabled.

Bit5: CCF5: PCA0 Module 5 Capture/Compare Flag.

This bit is set by hardware when a match or capture occurs. When the CCF interrupt is enabled, setting this bit causes the CPU to vector to the CCF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit4: CCF4: PCA0 Module 4 Capture/Compare Flag.

This bit is set by hardware when a match or capture occurs. When the CCF interrupt is enabled, setting this bit causes the CPU to vector to the CCF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit3: CCF3: PCA0 Module 3 Capture/Compare Flag.

This bit is set by hardware when a match or capture occurs. When the CCF interrupt is enabled, setting this bit causes the CPU to vector to the CCF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit2: CCF2: PCA0 Module 2 Capture/Compare Flag.

This bit is set by hardware when a match or capture occurs. When the CCF interrupt is enabled, setting this bit causes the CPU to vector to the CCF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit1: CCF1: PCA0 Module 1 Capture/Compare Flag.

This bit is set by hardware when a match or capture occurs. When the CCF interrupt is enabled, setting this bit causes the CPU to vector to the CCF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.

Bit0: CCF0: PCA0 Module 0 Capture/Compare Flag.

This bit is set by hardware when a match or capture occurs. When the CCF interrupt is enabled, setting this bit causes the CPU to vector to the CCF interrupt service routine. This bit is not automatically cleared by hardware and must be cleared by software.



#### SFR Definition 24.2. PCA0MD: PCA0 Mode

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
CIDL	_	_	_	CPS2	CPS1	CPS0	ECF	00000000
Rit7	Rit6	Rit5	Rit/I	Rit3	Rit2	Rit1	Rit∩	

SFR Address: 0xD9 SFR Page: 0

Bit7: CIDL: PCA0 Counter/Timer Idle Control.

Specifies PCA0 behavior when CPU is in Idle Mode.

0: PCA0 continues to function normally while the system controller is in Idle Mode.

1: PCA0 operation is suspended while the system controller is in Idle Mode.

Bits6-4: UNUSED. Read = 000b, Write = don't care.

Bits3-1: CPS2-CPS0: PCA0 Counter/Timer Pulse Select.

These bits select the timebase source for the PCA0 counter

CPS2	CPS1	CPS0	Timebase
0	0	0	System clock divided by 12
0	0	1	System clock divided by 4
0	1	0	Timer 0 overflow
0	1	1	High-to-low transitions on ECI <sup>1</sup> (max rate = system clock divided by 4)
1	0	0	System clock
1	0	1	External clock divided by 8 <sup>2</sup>
1	1	0	Reserved
1	1	1	Reserved

#### Notes:

- 1. The minimum high or low time for the ECI input signal is at least 2 system clock cycles.
- 2. External oscillator source divided by 8 is synchronized with the system clock.

Bit0: ECF: PCA Counter/Timer Overflow Interrupt Enable.

This bit sets the masking of the PCA0 Counter/Timer Overflow (CF) interrupt.

0: Disable the CF interrupt.

1: Enable a PCA0 Counter/Timer Overflow interrupt request when CF (PCA0CN.7) is set.



### SFR Definition 24.3. PCA0CPMn: PCA0 Capture/Compare Mode

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value
PWM16n	ECOMn	CAPPn	CAPNn	MATn	TOGn	PWMn	ECCFn	00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	_

PCA0CPM0: 0xDA, PCA0CPM1: 0xDB, PCA0CPM2: 0xDC, PCA0CPM3: 0xDD, PCA0CPM4: 0xDE, PCA0CPM5: SFR Address: 0xDF

PCA0CPM0: page 0, PCA0CPM1: page 0, PCA0CPM2: page 0, PCA0CPM3: page 0, PCA0CPM4: page 0, SFR Page: PCA0CPM5: page 0

Bit7: PWM16n: 16-bit Pulse Width Modulation Enable

This bit selects 16-bit mode when Pulse Width Modulation mode is enabled (PWMn = 1).

0: 8-bit PWM selected.

1: 16-bit PWM selected.

Bit6: ECOMn: Comparator Function Enable.

This bit enables/disables the comparator function for PCA0 module n.

0: Disabled.

1: Enabled.

Bit5: CAPPn: Capture Positive Function Enable.

This bit enables/disables the positive edge capture for PCA0 module n.

0: Disabled.

1: Enabled.

Bit4: CAPNn: Capture Negative Function Enable.

This bit enables/disables the negative edge capture for PCA0 module n.

0: Disabled.

1: Enabled.

Bit3: MATn: Match Function Enable.

> This bit enables/disables the match function for PCA0 module n. When enabled, matches of the PCA0 counter with a module's capture/compare register cause the CCFn bit in PCA0MD register to be set to logic 1.

0: Disabled.

1: Enabled.

Bit2: TOGn: Toggle Function Enable.

> This bit enables/disables the toggle function for PCA0 module n. When enabled, matches of the PCA0 counter with a module's capture/compare register cause the logic level on the CEXn pin to toggle. If the PWMn bit is also set to logic 1, the module operates in Frequency Output Mode.

0: Disabled.

1: Enabled.

PWMn: Pulse Width Modulation Mode Enable. Bit1:

> This bit enables/disables the PWM function for PCA0 module n. When enabled, a pulse width modulated signal is output on the CEXn pin. 8-bit PWM is used if PWM16n is logic 0; 16-bit mode is used if PWM16n logic 1. If the TOGn bit is also set, the module operates in Frequency Output Mode.

0: Disabled.

1: Enabled.

Bit0: ECCFn: Capture/Compare Flag Interrupt Enable.

This bit sets the masking of the Capture/Compare Flag (CCFn) interrupt.

0: Disable CCFn interrupts.

1: Enable a Capture/Compare Flag interrupt request when CCFn is set.

## SFR Definition 24.4. PCA0L: PCA0 Counter/Timer Low Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	

SFR Address: 0xF9 SFR Page: 0

Bits 7-0: PCA0L: PCA0 Counter/Timer Low Byte.

The PCA0L register holds the low byte (LSB) of the 16-bit PCA0 Counter/Timer.

## SFR Definition 24.5. PCA0H: PCA0 Counter/Timer High Byte

R/W	Reset Value							
								00000000
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0	<u>—</u>

SFR Address: 0xFA SFR Page: 0

Bits 7-0: PCA0H: PCA0 Counter/Timer High Byte.

The PCA0H register holds the high byte (MSB) of the 16-bit PCA0 Counter/Timer.



## SFR Definition 24.6. PCA0CPLn: PCA0 Capture Module Low Byte

R/W R/W R/W R/W R/W R/W R/W R/W Reset Value 00000000 Bit7 Bit6 Bit5 Bit4 Bit3 Bit2 Bit1 Bit0 PCA0CPL0: 0xFB, PCA0CPL1: 0xFD, PCA0CPL2: 0xE9, PCA0CPL3: 0xEB, PCA0CPL4: 0xED, PCA0CPL5: SFR Address: 0xE1 PCA0CPL0: page 0, PCA0CPL1: page 0, PCA0CPL2: page 0, PCA0CPL3: page 0, PCA0CPL4: page 0, SFR Page: PCA0CPL5: page 0 Bits7-0: PCA0CPLn: PCA0 Capture Module Low Byte. The PCA0CPLn register holds the low byte (LSB) of the 16-bit capture module n.

## SFR Definition 24.7. PCA0CPHn: PCA0 Capture Module High Byte

R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	Reset Value			
								00000000			
Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0				
SFR Address: PCA0CPH0: 0xFC, PCA0CPH1: 0xFE, PCA0CPH2: 0xEA, PCA0CPH3: 0xEC, PCA0CPH4: 0xEE, PCA0CPH5: 0xE2											
SFR Page: PCA0CPH0: page 0, PCA0CPH1: page 0, PCA0CPH2: page 0, PCA0CPH3: page 0, PCA0CPH4: page 0, PCA0CPH5: page 0											
Bits7-0: PCA0CPHn: PCA0 Capture Module High Byte. The PCA0CPHn register holds the high byte (MSB) of the 16-bit capture module n.											



## 25. JTAG (IEEE 1149.1)

Each MCU has an on-chip JTAG interface and logic to support boundary scan for production and in-system testing, Flash read/write operations, and non-intrusive in-circuit debug. The JTAG interface is fully compliant with the IEEE 1149.1 specification. Refer to this specification for detailed descriptions of the Test Interface and Boundary-Scan Architecture. Access of the JTAG Instruction Register (IR) and Data Registers (DR) are as described in the Test Access Port and Operation of the IEEE 1149.1 specification.

The JTAG interface is accessed via four dedicated pins on the MCU: TCK, TMS, TDI, and TDO.

Through the 16-bit JTAG Instruction Register (IR), any of the seven instructions shown in Figure 25.1 can be commanded. There are three DRs associated with JTAG Boundary-Scan, and four associated with Flash read/write operations on the MCU.

### JTAG Register Definition 25.1. IR: JTAG Instruction Register

					Reset Value
					0x0000
Bit15				Bit0	_

IR Value	Instruction	Description
0x0000	EXTEST	Selects the Boundary Data Register for control and observability of all device pins
0x0002	SAMPLE/ PRELOAD	Selects the Boundary Data Register for observability and presetting the scan-path latches
0x0004	IDCODE	Selects device ID Register (DEVICEID)
0xFFFF	BYPASS	Selects Bypass Data Register
0x0082	Flash Control	Selects FLASHCON Register to control how the interface logic responds to reads and writes to the FLASHDAT Register
0x0083	Flash Data	Selects FLASHDAT Register for reads and writes to the Flash memory
0x0084	Flash Address	Selects FLASHADR Register which holds the address of all Flash read, write, and erase operations



## 25.1. Boundary Scan

The DR in the Boundary Scan path is an 134-bit shift register. The Boundary DR provides control and observability of all the device pins as well as the SFR bus and Weak Pullup feature via the EXTEST and SAMPLE commands.

Table 25.1. Boundary Data Register Bit Definitions

EXTEST provides access to both capture and update actions, while Sample only performs a capture.

Bit Action Target  Capture Reset Enable from MCU Update Reset Enable to /RST pin  Capture Reset input from /RST pin Update Reset output to /RST pin	
1 Capture Reset input from /RST pin Update Reset output to /RST pin	
Update Reset output to /RST pin	
2 Capture Reset Enable from MCU	
Update Reset Enable to /RST pin	
3 Capture Reset input from /RST pin	
Update Reset output to /RST pin	
4 Capture CANRX output enable to pin	
Update CANRX output enable to pin	
5 Capture CANRX input from pin	
Update CANRX output to pin	
6 Capture CANTX output enable to pin	
Update CANTX output enable to pin	
7 Capture CANTX input from pin	
Update CANTX output to pin	
8 Capture External Clock from XTAL1 pin	
Update Not used	
9 Capture Weak pullup enable from MCU	
Update Weak pullup enable to Port Pins	
10, 12, 14, 16, 18, Capture P0.n output enable from MCU (e.g. Bit6=P0.0, Bit8=P0.1, etc.)	
20, 22, 24 Update P0.n output enable to pin (e.g. Bit6=P0.0oe, Bit8=P0.1oe, etc.	)
11, 13, 15, 17, 19, Capture P0.n input from pin (e.g. Bit7=P0.0, Bit9=P0.1, etc.)	
21, 23, 25 Update P0.n output to pin (e.g. Bit7=P0.0, Bit9=P0.1, etc.)	
26, 28, 30, 32, 34, Capture P1.n output enable from MCU	
36, 38, 40 Update P1.n output enable to pin	
27, 29, 31, 33, 35, Capture P1.n input from pin	
37, 39, 41 Update P1.n output to pin	
42, 44, 46, 48, 50, Capture P2.n output enable from MCU	
52, 54, 56 Update P2.n output enable to pin	
43, 45, 47, 49, 51, Capture P2.n input from pin	
53, 55, 57 Update P2.n output to pin	
58, 60, 62, 64, 66, Capture P3.n output enable from MCU	
68, 70, 72 Update P3.n output enable to pin	
59, 61, 63, 65, 67, Capture P3.n input from pin	
69, 71, 73 Update P3.n output to pin	
74, 76, 78, 80, 82, Capture P4.n output enable from MCU	
84, 86, 88 Update P4.n output enable to pin	



### Table 25.1. Boundary Data Register Bit Definitions (Continued)

EXTEST provides access to both capture and update actions, while Sample only performs a capture.

Bit	Action	Target
75, 77, 79, 81, 83,	Capture	P4.n input from pin
85, 87, 89	Update	P4.n output to pin
90, 92, 94, 96, 98,	Capture	P5.n output enable from MCU
100, 102, 104	Update	P5.n output enable to pin
91, 93, 95, 97, 99,	Capture	P5.n input from pin
101, 103, 105	Update	P5.n output to pin
106, 108, 110, 112,	Capture	P6.n output enable from MCU
114, 116, 118, 120	Update	P6.n output enable to pin
107, 109, 111, 113,	Capture	P6.n input from pin
115, 117, 119, 121	Update	P6.n output to pin
122, 124, 126, 128,	Capture	P7.n output enable from MCU
130, 132, 134, 136	Update	P7.n output enable to pin
123, 125, 127, 129,	Capture	P7.n input from pin
131, 133, 135, 137	Update	P7.n output to pin

#### 25.1.1. EXTEST Instruction

The EXTEST instruction is accessed via the IR. The Boundary DR provides control and observability of all the device pins as well as the Weak Pullup feature. All inputs to on-chip logic are set to logic 1.

#### 25.1.2. SAMPLE Instruction

The SAMPLE instruction is accessed via the IR. The Boundary DR provides observability and presetting of the scan-path latches.

#### 25.1.3. BYPASS Instruction

The BYPASS instruction is accessed via the IR. It provides access to the standard JTAG Bypass data register.

#### 25.1.4. IDCODE Instruction

The IDCODE instruction is accessed via the IR. It provides access to the 32-bit Device ID register.



## JTAG Register Definition 25.2. DEVICEID: JTAG Device ID Register

Version		Part Nu	mber	M	lanufacturer ID	1	1	Reset Value 0xn0005243				
Bit31	Bit28	Bit27	Bit12	Bit11		Bit1	Bit0	ı				
Version = 0000b												
Part Number = 0000 0000 0000 0101b (C8051F040/1/2/3/4/5/6/7)												
Manufacturer ID = 0010 0100 001b (Silicon Labs)												

#### 25.2. Flash Programming Commands

The Flash memory can be programmed directly over the JTAG interface using the Flash Control, Flash Data, Flash Address, and Flash Scale registers. These Indirect Data Registers are accessed via the JTAG Instruction Register. Read and write operations on indirect data registers are performed by first setting the appropriate DR address in the IR register. Each read or write is then initiated by writing the appropriate Indirect Operation Code (IndOpCode) to the selected data register. Incoming commands to this register have the following format:

19:18	17:0
IndOpCode	WriteData

IndOpCode: These bit set the operation to perform according to the following table:

IndOpCode	Operation
0x	Poll
10	Read
11	Write

The Poll operation is used to check the Busy bit as described below. Although a Capture-DR is performed, no Update-DR is allowed for the Poll operation. Since updates are disabled, polling can be accomplished by shifting in/out a single bit.

The Read operation initiates a read from the register addressed by the DRAddress. Reads can be initiated by shifting only 2 bits into the indirect register. After the read operation is initiated, polling of the Busy bit must be performed to determine when the operation is complete.

The write operation initiates a write of WriteData to the register addressed by DRAddress. Registers of any width up to 18 bits can be written. If the register to be written contains fewer than 18 bits, the data in Write-Data should be left-justified, i.e. its MSB should occupy bit 17 above. This allows shorter registers to be written in fewer JTAG clock cycles. For example, an 8-bit register could be written by shifting only 10 bits. After a Write is initiated, the Busy bit should be polled to determine when the next operation can be initiated. The contents of the Instruction Register should not be altered while either a read or write operation is busy.

Outgoing data from the indirect Data Register has the following format:

19	18:1	0	
0	ReadData	Busy	

The Busy bit indicates that the current operation is not complete. It goes high when an operation is initiated and returns low when complete. Read and Write commands are ignored while Busy is high. In fact, if polling for Busy to be low will be followed by another read or write operation, JTAG writes of the next operation can be made while checking for Busy to be low. They will be ignored until Busy is read low, at which time the new operation will initiate. This bit is placed ate bit 0 to allow polling by single-bit shifts. When waiting for a Read to complete and Busy is 0, the following 18 bits can be shifted out to obtain the resulting data. ReadData is always right-justified. This allows registers shorter than 18 bits to be read using a reduced number of shifts. For example, the results from a byte-read requires 9 bit shifts (Busy + 8 bits).



### JTAG Register Definition 25.3. FLASHCON: JTAG Flash Control Register

Reset Value **SFLE** WRMD2 WRMD1 WRMD0 RDMD3 RDMD2 RDMD1 RDMD0 0000000 Bit7 Bit3 Bit6 Bit5 Bit4 Bit2 Bit1 Bit0

This register determines how the Flash interface logic will respond to reads and writes to the FLASHDAT Register.

Bit 7: SFLE: Scratchpad Flash Memory Access Enable

When this bit is set, Flash reads and writes from user software are directed to the 128-byte scratchpad Flash sector. When accessing the scratchpad, Flash accesses out of the address range 0x00-0x7F should not be attempted. Reads/Writes outside of this range will yield undefined results.

0: Flash access is directed to the Program/Data Flash sector.

1: Flash access is directed to the 128-byte scratchpad sector.

Bits6-4: WRMD2-0: Write Mode Select Bits.

The Write Mode Select Bits control how the interface logic responds to writes to the FLASH-DAT Register per the following values:

000: A FLASHDAT write replaces the data in the FLASHDAT register, but is otherwise ignored.

001: A FLASHDAT write initiates a write of FLASHDAT into the memory address by the FLASHADR register. FLASHADR is incremented by one when complete.

010: A FLASHDAT write initiates an erasure (sets all bytes to 0xFF) of the Flash page containing the address in FLASHADR. The data written must be 0xA5 for the erase to occur. FLASHADR is not affected. If FLASHADR targets the Read Lock Byte or the Write/Erase Lock Byte, the entire user space will be erased (i.e. entire Flash memory except for the Reserved area (See Section "15. Flash Memory" on page 179).

(All other values for WRMD2-0 are reserved.)

Bits3-0: RDMD3-0: Read Mode Select Bits.

The Read Mode Select Bits control how the interface logic responds to reads to the FLASH-DAT Register per the following values:

0000: A FLASHDAT read provides the data in the FLASHDAT register, but is otherwise ignored.

0001: A FLASHDAT read initiates a read of the byte addressed by the FLASHADR register if no operation is currently active. This mode is used for block reads.

0010: A FLASHDAT read initiates a read of the byte addressed by FLASHADR only if no operation is active and any data from a previous read has already been read from FLASHDAT. This mode allows single bytes to be read (or the last byte of a block) without initiating an extra read.

(All other values for RDMD3-0 are reserved.)

## JTAG Register Definition 25.4. FLASHDAT: JTAG Flash Data

						Reset Value
ſ						000000000
	Bit9				Bit0	_

This register is used to read or write data to the Flash memory across the JTAG interface.

Bits9-2: DATA7-0: Flash Data Byte.

Bit1: FAIL: Flash Fail Bit.

0: Previous Flash memory operation was successful.

1: Previous Flash memory operation failed. Usually indicates the associated memory loca-

tion was locked.

Bit0: BUSY: Flash Busy Bit.

0: Flash interface logic is not busy.

1: Flash interface logic is processing a request. Reads or writes while BUSY = 1 will not

initiate another operation.

## JTAG Register Definition 25.5. FLASHADR: JTAG Flash Address

Bit15							Bit0	Reset Value 0x0000		
This register holds the address for all JTAG Flash read, write, and erase operations. This register auto-increments after each read or write, regardless of whether the operation succeeded or failed.  Bits15-0: Flash Operation 16-bit Address.										



## 25.3. Debug Support

Each MCU has on-chip JTAG and debug logic that provides non-intrusive, full speed, in-circuit debug support using the production part installed in the end application, via the four pin JTAG I/F. Silicon Labs' debug system supports inspection and modification of memory and registers, breakpoints, and single stepping. No additional target RAM, program memory, or communications channels are required. All the digital and analog peripherals are functional and work correctly (remain synchronized) while debugging. The Watchdog Timer (WDT) is disabled when the MCU is halted during single stepping or at a breakpoint.

The C8051F040DK is a development kit with all the hardware and software necessary to develop application code and perform in-circuit debug with each MCU in the C8051F04x family. Each kit includes an Integrated Development Environment (IDE) which has a debugger and integrated 8051 assembler. The kit also includes a JTAG interface module referred to as the Serial Adapter. There is also a target application board with a C8051F040 installed. The required cables and wall-mount power supply are also included.



## **DOCUMENT CHANGE LIST**

#### **Revision 1.4 to Revision 1.5**

- High Voltage Difference Amplifier Electrical Characteristics Tables: Corrected Common Mode Rejection Ratio MIN and TYP specifications.
- Flash Memory Chapter: Corrected text reference to "C8051F12x and C8051F13x"; Changed to "C8051F04x".
- 10 and 12-bit ADC0 Track and Conversion Example Timing Figures: Corrected bit name text from "AD0STM" to "AD0CM".
- ADC0 Chapters (10 and 12-bit): Updated analog multiplexer figure to represent correct connection of HVREF to AIN- in differential HVDA configuration.
- ADC0 Chapters (10 and 12-bit): Updated HVDA section text to clarify usage of HVREF pin.
- ADC0 Chapters (10 and 12-bit): Added differential HVDA options to AMUX Selection Chart Table.
- Product Selection Guide Table: Added RoHS-compliant ordering information.
- Global DC Electrical Characteristics Table: Corrected units for "Analog Supply Current with Analog Subsystems Inactive" to "µA".
- Pin Definitions Table: Corrected HVAIN- pin description to "High Voltage Difference Amplifier Negative Signal Input."
- Interrupt Summary Table: Added "SFRPAGE" column and SFRPAGE value for each interrupt source.
- Interrupt Summary Table: Corrected "T4CON" to "TMR4CN".
- Interrupt Summary Table: Corrected "T2CON" to "TMR2CN".
- Interrupt Summary Table: Corrected "ADWINT" to "AD0WINT".
- SFR Memory Map Table: Corrected SFR Page for ADC2CN from page 1 to page 2.
- Oscillators Chapter: Corrected steps for enabling external crystal oscillator.
- PCA0CPHn SFR Definition: Corrected SFR address of PCA0CPH1 from "0xFD" to "0xFE".



## **CONTACT INFORMATION**

Silicon Laboratories Inc.

4635 Boston Lane Austin, TX 78735

Email: MCUinfo@silabs.com Internet: www.silabs.com

The information in this document is believed to be accurate in all respects at the time of publication but is subject to change without notice. Silicon Laboratories assumes no responsibility for errors and omissions, and disclaims responsibility for any consequences resulting from the use of information included herein. Additionally, Silicon Laboratories assumes no responsibility for the functioning of undescribed features or parameters. Silicon Laboratories reserves the right to make changes without further notice. Silicon Laboratories makes no warranty, representation or guarantee regarding the suitability of its products for any particular purpose, nor does Silicon Laboratories assume any liability arising out of the application or use of any product or circuit, and specifically disclaims any and all liability, including without limitation consequential or incidental damages. Silicon Laboratories products are not designed, intended, or authorized for use in applications intended to support or sustain life, or for any other application in which the failure of the Silicon Laboratories product could create a situation where personal injury or death may occur. Should Buyer purchase or use Silicon Laboratories products for any such unintended or unauthorized application, Buyer shall indemnify and hold Silicon Laboratories harmless against all claims and damages.

Silicon Laboratories and Silicon Labs are trademarks of Silicon Laboratories Inc.

Other products or brandnames mentioned herein are trademarks or registered trademarks of their respective holders



# **Mouser Electronics**

**Authorized Distributor** 

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

## Silicon Laboratories:

<u>C8051F041</u> <u>C8051F044</u> <u>C8051F040</u> <u>C8051F046</u> <u>C8051F042</u> <u>C8051F043</u> <u>C8051F045</u> <u>C8051F047</u> <u>C8051F047R</u> <u>C8051F041R</u> <u>C8051F046R</u> <u>C8051F043R</u> <u>C8051F042R</u> <u>C8051F040R</u> <u>C8051F044R</u>