

# MX25L3273F

# 3V, 32M-BIT [x 1/x 2/x 4] CMOS MXSMIO® (SERIAL MULTI I/O) FLASH MEMORY

# **Key Features**

- Multi I/O Support Single I/O, Dual I/O and Quad I/O
- Auto Erase and Auto Program Algorithms
- Program Suspend/Resume & Erase Suspend/Resume
- Permanently fixed QE bit, QE=1; and 4 I/O mode is enabled

P/N: PM2163 REV. 1.2, October 21, 2016



# **Contents**

1.	<b>FEATU</b>	RES	4
2.	GENER	AL DESCRIPTION	5
3.	PIN CO	NFIGURATION	6
4.	PIN DE	SCRIPTION	6
5.	BLOCK	DIAGRAM	7
		ROTECTION	
		Table 1. Protected Area Sizes	
		Table 2. 4K-bit Secured OTP Definition	
7.	MEMOF	RY ORGANIZATION	
		Table 3. Memory Organization	11
8.	DEVICE	OPERATION	
		AND DESCRIPTION	
		Table 4. Command Sets	13
	9-1.	Write Enable (WREN)	
	9-2.	Write Disable (WRDI)	
	9-3.	Read Identification (RDID)	
	9-4.	Read Status Register (RDSR)	19
	9-5.	Read Configuration Register (RDCR)	20
	9-6.	Write Status Register (WRSR)	23
		Table 5. Protection Modes	24
	9-7.	Read Data Bytes (READ)	
	9-8.	Read Data Bytes at Higher Speed (FAST_READ)	
	9-9.	Dual Read Mode (DREAD)	
	9-10.	2 x I/O Read Mode (2READ)	
	9-11.	Quad Read Mode (QREAD)	
	9-12.	,	
		Performance Enhance Mode	
	9-14.		
	9-15.	Sector Erase (SE)	
	9-16.	Block Erase (BE)	
	9-17.	Block Erase (BE32K)	
		Chip Erase (CE)	
		4 x I/O Page Program (4PP)	
		Deep Power-down (DP)	
	9-21. 9-22.	Release from Deep Power-down (RDP), Read Electronic Signature (RES)	
	9-23.	Read Electronic Manufacturer ID & Device ID (REMS)	
	0 20.	Table 6. ID Definitions	
	9-24.	Enter Secured OTP (ENSO)	
		Exit Secured OTP (EXSO)	
		Read Security Register (RDSCUR)	
		Table 7. Security Register Definition	
	9-27.	, •	
	9-28.	Program Suspend and Erase Suspend	51
		Table 8. Readable Area of Memory While a Program or Erase Operation is Suspended	51
		Table 9. Acceptable Commands During Suspend after tPSL/tESL	51
		Table 10. Acceptable Commands During Suspend (tPSL/tESL not required)	52





	9-29.	Program Resume and Erase Resume	
	9-30.	No Operation (NOP)	54
	9-31.	Software Reset (Reset-Enable (RSTEN) and Reset (RST))	54
	9-32.	Read SFDP Mode (RDSFDP)	55
		Table 11. Signature and Parameter Identification Data Values	56
		Table 12. Parameter Table (0): JEDEC Flash Parameter Tables	57
		Table 13. Parameter Table (1): Macronix Flash Parameter Tables	
10.	POWE	R-ON STATE	
11.	Electri	cal Specifications	62
		Absolute Maximum Ratings	
		Capacitance TA = 25°C, f = 1.0 MHz	
		Table 14. DC Characteristics	
		Table 15. AC Characteristics	65
12.	TIMIN	G ANALYSIS	67
13.	OPER	ATING CONDITIONS	68
		Table 16. Power-Up/Down Voltage and Timing	70
	13-1.	Initial Delivery State	
14.		E AND PROGRAMMING PERFORMANCE	
15.	DATA	RETENTION	71
		1-UP CHARACTERISTICS	
		RING INFORMATION	
		NAME DESCRIPTION	
		AGE INFORMATION	
		ION HISTORY	
<b>۷</b> ٠.	KEVIO		13





# 32M-BIT [x 1 / x 2 / x 4] CMOS MXSMIO<sup>®</sup> (SERIAL MULTI I/O) FLASH MEMORY

#### 1. FEATURES

#### **GENERAL**

- Supports Serial Peripheral Interface -- Mode 0 and Mode 3
- 33,554,432 x 1 bit structure or 16,777,216 x 2 bits (two I/O read mode) structure or 8,388,608 x 4 bits (four I/O mode) structure
- · 1024 Equal Sectors with 4K bytes each
  - Any Sector can be erased individually
- 128 Equal Blocks with 32K bytes each
  - Any Block can be erased individually
- · 64 Equal Blocks with 64K bytes each
  - Any Block can be erased individually
- · Power Supply Operation
  - $2.65 \sim 3.6$  volt for read, erase, and program operations
- Latch-up protected to 100mA from -1V to Vcc +1V
- Permanently fixed QE bit, QE=1 and 4 I/O mode is enabled

#### **PERFORMANCE**

- High Performance VCC = 2.65~3.6V
  - Normal read
    - 50MHz
  - Fast read
  - FAST\_READ, DREAD, QREAD: 133MHz with 8 dummy cycles
  - 2READ: 104MHz with 4 dummy cycle, 133MHz with 8 dummy cycle
  - 4READ: 104MHz with 6 dummy cycle, 133MHz with 10 dummy cycle
  - Configurable dummy cycle number for 2READ and 4READ operation
  - 8/16/32/64 byte Wrap-Around Burst Read Mode
- · Low Power Consumption
- Typical 100,000 erase/program cycles
- 20 years data retention

#### SOFTWARE FEATURES

- · Input Data Format
  - 1-byte Command code
- Advanced Security Features
  - Block Lock Protection

The BP0-BP3 and T/B status bits define the site of the area to be protected against program and erase instructions.

- · Additional 4K bits secured OTP
  - Features unique identifier
  - Factory locked identifiable and customer lockable
- · Auto Erase and Auto Program Algorithms
- Automatically erases and verifies data at selected sector
- Automatically programs and verifies data at selected page by an internal algorithm that automatically times the program pulse width (Any page to be programmed should have page in the erased state first.)
- Status Register Feature
- Command Reset
- Program/Erase Suspend
- Program/Erase Resume
- Electronic Identification
- JEDEC 1-byte Manufacturer ID and 2-byte Device ID
- RES command for 1-byte Device ID
- Support Serial Flash Discoverable Parameters (SFDP) mode

#### HARDWARE FEATURES

- SCLK Input Serial clock input
- SI/SIO0 Serial Data Input or Serial Data Input/Output for 2 x I/O mode or Serial Data Input/Output for 4 x I/O mode
- SO/SIO1 Serial Data Output or Serial Data Input/Output for 2 x I/O mode or Serial Data Input/Output for 4 x I/O mode
- SIO2 Serial data Input/Output for 4 x I/O mode
- SIO3 Serial data Input/Output for 4 x I/O mode
- PACKAGE
  - 8-pin SOP (200mil)
- All devices are RoHS Compliant and Halogen-free





#### 2. GENERAL DESCRIPTION

MX25L3273F is 32Mb bits serial Flash memory, which is configured as 4,194,304 x 8 internally. When it is in four I/O mode, the structure becomes 8,388,608 bits x 4. When it is in two I/O mode, the structure becomes 16,777,216 bits x 2. MX25L3273F feature a serial peripheral interface and software protocol allowing operation on a simple 3-wire bus while it is in single I/O mode. The three bus signals are a clock input (SCLK), a serial data input (SI), and a serial data output (SO). Serial access to the device is enabled by CS# input.

MX25L3273F, MXSMIO® (Serial Multi I/O) flash memory, provides sequential read operation on the whole chip and multi-I/O features.

When it is in quad I/O mode, the SI pin, SO pin, become SIO0 pin, SIO1 pin, SIO2 pin and SIO3 pin for address/dummy bits input and data Input/Output.

After program/erase command is issued, auto program/erase algorithms which program/erase and verify the specified page or sector/block locations will be executed. Program command is executed on byte basis, or page (256 bytes) basis, and erase command is executed on 4K-byte sector, 32K-byte/64K-byte block, or whole chip basis.

To provide user with ease of interface, a status register is included to indicate the status of the chip. The status read command can be issued to detect completion status of a program or erase operation via WIP bit.

When the device is not in operation and CS# is high, it is put in standby mode.


The MX25L3273F utilizes Macronix's proprietary memory cell, which reliably stores memory contents even after 100,000 program and erase cycles.





# 3. PIN CONFIGURATION

# 8-PIN SOP (200mil)




# 4. PIN DESCRIPTION

SYMBOL	DESCRIPTION
CS#	Chip Select
SI/SIO0	Serial Data Input (for 1xI/O)/ Serial Data Input & Output (for 2xI/O mode and 4xI/O mode)
SO/SIO1	Serial Data Output (for 1xI/O)/Serial Data Input & Output (for 2xI/O mode and 4xI/O mode)
SCLK	Clock Input
SIO2	Serial Data Input & Output (for 4xI/O mode)
SIO3	Serial Data Input & Output (for 4xI/O mode)
VCC	+ 3.0V Power Supply
GND	Ground
NC	No Connection



# 5. BLOCK DIAGRAM







#### 6. DATA PROTECTION

During power transition, there may be some false system level signals which result in inadvertent erasure or programming. The device is designed to protect itself from these accidental write cycles.

The state machine will be reset as standby mode automatically during power up. In addition, the control register architecture of the device constrains that the memory contents can only be changed after specific command sequences have completed successfully.

In the following, there are several features to protect the system from the accidental write cycles during VCC power-up and power-down or from system noise.

- Valid command length checking: The command length will be checked whether it is at byte base and completed on byte boundary.
- Write Enable (WREN) command: WREN command is required to set the Write Enable Latch bit (WEL) before other command to change data.
- Deep Power Down Mode: By entering deep power down mode, the flash device also is under protected from writing all commands except Release from Deep Power Down mode command (RDP) and Read Electronic Signature command (RES).

#### I. Block lock protection

- The Software Protected Mode (SPM) uses (TB, BP3, BP2, BP1, BP0) bits to allow part of memory to be protected as read only. The protected area definition is shown as table of "Table 1. Protected Area Sizes", the protected areas are more flexible which may protect various areas by setting value of TB, BP0-BP3 bits.



Table 1. Protected Area Sizes
Protected Area Sizes (TB bit = 0)

_	State	us bit	•	Protect Level		
BP3 BP2 BP1 BP0			BP0	32Mb		
0	0	0	0	0 (none)		
0	0	0	1	1 (1block, block 63rd)		
0	0	1	0	2 (2blocks, block 62nd-63rd)		
0	0	1	1	3 (4blocks, block 60th-63rd)		
0	1	0	0	4 (8blocks, block 56th-63rd)		
0	1	0	1	5 (16blocks, block 48th-63rd)		
0	1	1	0	6 (32blocks, block 32nd-63rd)		
0	1	1	1	7 (64blocks, protect all)		
1	0	0	0	8 (64blocks, protect all)		
1	0	0	1	9 (64blocks, protect all)		
1	0	1	0	10 (64blocks, protect all)		
1	0	1	1	11 (64blocks, protect all)		
1	1	0	0	12 (64blocks, protect all)		
1	1	0	1	13 (64blocks, protect all)		
1	1	1	0	14 (64blocks, protect all)		
1	1	1	1	15 (64blocks, protect all)		

# Protected Area Sizes (TB bit = 1)

	Statu	ıs bit		Protect Level
BP3	BP2	BP1	BP0	32Mb
0	0	0	0	0 (none)
0	0	0	1	1 (1block, block 0th)
0	0	1	0	2 (2blocks, block 0th-1st)
0	0	1	1	3 (4blocks, block 0th-3rd)
0	1	0	0	4 (8blocks, block 0th-7th)
0	1	0	1	5 (16blocks, block 0th-15th)
0	1	1	0	6 (32blocks, block 0th-31st)
0	1	1	1	7 (64blocks, protect all)
1	0	0	0	8 (64blocks, protect all)
1	0	0	1	9 (64blocks, protect all)
1	0	1	0	10 (64blocks, protect all)
1	0	1	1	11 (64blocks, protect all)
1	1	0	0	12 (64blocks, protect all)
1	1	0	1	13 (64blocks, protect all)
1	1	1	0	14 (64blocks, protect all)
1	1	1	1	15 (64blocks, protect all)

**Note:** The device is ready to accept a Chip Erase instruction if, and only if, all Block Protect (BP3, BP2, BP1, BP0) are 0.





- **II. Additional 4K-bit secured OTP** for unique identifier: to provide 4K-bit One-Time Program area for setting device unique serial number Which may be set by factory or system maker.
  - Security register bit 0 indicates whether the chip is locked by factory or not.
  - To program the 4K-bit secured OTP by entering 4K-bit secured OTP mode (with ENSO command), and going through normal program procedure, and then exiting 4K-bit secured OTP mode by writing EXSO command.
  - Customer may lock-down the customer lockable secured OTP by writing WRSCUR(write security register) command to set customer lock-down bit1 as "1". Please refer to "Table 7. Security Register Definition" for security register bit definition and "Table 2. 4K-bit Secured OTP Definition" for address range definition.

**Note:** Once lock-down whatever by factory or customer, it cannot be changed any more. While in 4K-bit Secured OTP mode, array access is not allowed.

Table 2. 4K-bit Secured OTP Definition

Address range	Size	Standard Factory Lock	Customer Lock
xxx000~xxx1FF	4096-bit	Determined by Factory	Determined by customer



# 7. MEMORY ORGANIZATION

# **Table 3. Memory Organization**

Block(64K-byte)	Block(32K-byte)	Sector (4K-byte)	Address	s Range
		1023	3FF000h	3FFFFFh
	127	:		
63		1016	3F8000h	3F8FFFh
		1015	3F7000h	3F7FFFh
	126	:		
		1008	3F0000h	3F0FFFh
		1007	3EF000h	3EFFFFh
	125	:		
62		1000	3E8000h	3E8FFFh
02	124	999	3E7000h	3E7FFFh
		:		
		992	3E0000h	3E0FFFh
		991	3DF000h	3DFFFFh
	123	:		
61		984	3D8000h	3D8FFFh
01		983	3D7000h	3D7FFFh
	122	:		
		976	3D0000h	3D0FFFh



			2252221	22555
		47	02F000h	02FFFFh
	5	:		
2		40	028000h	028FFFh
		39	027000h	027FFFh
	4	i i		
		32	020000h	020FFFh
		31	01F000h	01FFFFh
	3	:		
1		24	018000h	018FFFh
'	2	23	017000h	017FFFh
		:		
		16	010000h	010FFFh
		15	00F000h	00FFFFh
	1	:		
		8	008000h	008FFFh
0	0	7	007000h	007FFFh
		0	000000h	000FFFh



#### 8. DEVICE OPERATION

- 1. Before a command is issued, status register should be checked to ensure device is ready for the intended operation.
- 2. When incorrect command is inputted to this device, it enters standby mode and remains in standby mode until next CS# falling edge. In standby mode, SO pin of the device is High-Z.
- 3. When correct command is inputted to this device, it enters active mode and remains in active mode until next CS# rising edge.
- 4. For standard single data rate serial mode, input data is latched on the rising edge of Serial Clock(SCLK) and data is shifted out on the falling edge of SCLK. The difference of Serial mode 0 and mode 3 is shown as "Figure 1. Serial Modes Supported (for Normal Serial mode)".
- 5. For the following instructions: RDID, RDSR, RDSCUR, READ, FAST\_READ, RDSFDP, 4READ, QREAD, 2READ, DREAD, RDCR, RES, and REMS the shifted-in instruction sequence is followed by a data-out sequence. After any bit of data being shifted out, the CS# can be high. For the following instructions: WREN, WRDI, WRSR, SE, BE, BE32K, CE, PP, 4PP, Suspend, Resume, NOP, RSTEN, RST, ENSO, EXSO, WRSCUR, the CS# must go high exactly at the byte boundary; otherwise, the instruction will be rejected and not executed.
- 6. While a Write Status Register, Program, or Erase operation is in progress, access to the memory array is neglected and will not affect the current operation of Write Status Register, Program, Erase.




Figure 1. Serial Modes Supported (for Normal Serial mode)

#### Note:

CPOL indicates clock polarity of Serial master, CPOL=1 for SCLK high while idle, CPOL=0 for SCLK low while not transmitting. CPHA indicates clock phase. The combination of CPOL bit and CPHA bit decides which Serial mode is supported.



# 9. COMMAND DESCRIPTION

# **Table 4. Command Sets**

## **Read Commands**

I/O	1	1	2	2	4	4
Command	READ (normal read)	FAST READ (fast read data)	2READ (2 x I/O read command)	DREAD (1I / 2O read command)	4READ (4 x I/O read command)	QREAD (1I/4O read command)
1st byte	03 (hex)	0B (hex)	BB (hex)	3B (hex)	EB (hex)	6B (hex)
2nd byte	ADD1(8)	ADD1(8)	ADD1	ADD1	ADD1(2)	ADD1(8)
3rd byte	ADD2(8)	ADD2(8)	ADD2	ADD2	ADD2(2)	ADD2(8)
4th byte	ADD3(8)	ADD3(8)	ADD3	ADD3	ADD3(2)	ADD3(8)
5th byte		Dummy(8)	Dummy*	Dummy(8)	Dummy*	Dummy(8)
Action	n bytes read out until CS# goes high	n bytes read out until CS# goes high	n bytes read out by 2 x I/O until CS# goes high	n bytes read out by Dual Output until CS# goes high	Quad I/O read with configurable dummy cycles	

**Note:** \*Dummy cycle number will be different, depending on the bit6 (DC) setting of Configuration Register. Please refer to "Configuration Register" Table.





# **Other Commands**

Command	WREN (write enable)	WRDI (write disable)	RDSR (read status register)	RDCR (read configuration register)	WRSR (write status/ configuration register)	4PP (quad page program)	SE (sector erase)
1st byte	06 (hex)	04 (hex)	05 (hex)	15 (hex)	01 (hex)	38 (hex)	20 (hex)
2nd byte					Values	ADD1	ADD1
3rd byte					Values	ADD2	ADD2
4th byte						ADD3	ADD3
Action	sets the (WEL) write enable latch bit	resets the (WEL) write enable latch bit	to read out the values of the status register	to read out the values of the configuration register	to write new values of the configuration/ status register	quad input to program the selected page	to erase the selected sector

Command	BE 32K (block erase 32KB)	BE (block erase 64KB)	CE (chip erase)	PP (page program)	DP (Deep power down)	RDP (Release from deep power down)	PGM/ERS Suspend (Suspends Program/ Erase)
1st byte	52 (hex)	D8 (hex)	60 or C7 (hex)	02 (hex)	B9 (hex)	AB (hex)	75/B0 (hex)
2nd byte	ADD1	ADD1		ADD1			
3rd byte	ADD2	ADD2		ADD2			
4th byte	ADD3	ADD3		ADD3			
Action	to erase the selected 32KB block	to erase the selected 64KB block		to program the selected page	enters deep power down mode	release from deep power down mode	program/erase operation is interrupted by suspend command

Command	PGM/ERS Resume (Resumes Program/ Erase)	RDID (read identific- ation)	RES (read electronic ID)	REMS (read electronic manufacturer & device ID)	ENSO (enter secured OTP)
1st byte	7A/30 (hex)	9F (hex)	AB (hex)	90 (hex)	B1 (hex)
2nd byte			Х	х	
3rd byte			Х	Х	
4th byte			Х	ADD	
Action	to continue performing the suspended program/erase sequence	ID: 1-byte	to read out 1-byte Device ID	output the Manufacturer ID & Device ID	to enter the 4K-bit secured OTP mode



# MX25L3273F

Command (byte)	EXSO (exit secured OTP)	RDSCUR (read security register)	WRSCUR (write security register)	RSTEN (Reset Enable)	RST (Reset Memory)	RDSFDP	SBL (Set Burst Length)
1st byte	C1 (hex)	2B (hex)	2F (hex)	66 (hex)	99 (hex)	5A (hex)	C0/ 77 (hex)
2nd byte						ADD1(8)	
3rd byte						ADD2(8)	Value
4th byte						ADD3(8)	
5th byte						Dummy(8)	
Action	to exit the 4K-bit secured OTP mode	to read value of security register	to set the lock- down bit as "1" (once lock- down, cannot be update)			n bytes read out until CS# goes high	to set Burst length

Command (byte)	NOP (No Operation)
1st byte	00 (hex)
2nd byte	
3rd byte	
4th byte	
5th byte	
Action	

Note 1: It is not recommended to adopt any other code not in the command definition table, which will potentially enter the hidden mode.

Note 2: Before executing RST command, RSTEN command must be executed. If there is any other command to interfere, the reset operation will be disabled.




# 9-1. Write Enable (WREN)

The Write Enable (WREN) instruction is for setting Write Enable Latch (WEL) bit. For those instructions like PP, 4PP, SE, BE, BE32K, CE, and WRSR which are intended to change the device content, should be set every time after the WREN instruction setting the WEL bit.

The sequence of issuing WREN instruction is: CS# goes low $\rightarrow$  sending WREN instruction code $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.

Figure 2. Write Enable (WREN) Sequence (Command 06)





# 9-2. Write Disable (WRDI)


The Write Disable (WRDI) instruction is for resetting Write Enable Latch (WEL) bit.

The sequence of issuing WRDI instruction is: CS# goes low→ sending WRDI instruction code→ CS# goes high.

The WEL bit is reset by following situations:

- Power-up
- WRDI command completion
- WRSR command completion
- PP command completion
- 4PP command completion
- SE command completion
- BE32K command completion
- BE command completion
- CE command completion
- PGM/ERS Suspend command completion
- Softreset command completion
- WRSCUR command completion

Figure 3. Write Disable (WRDI) Sequence (Command 04)






# 9-3. Read Identification (RDID)

The RDID instruction is for reading the manufacturer ID of 1-byte and followed by Device ID of 2-byte. The Macronix Manufacturer ID and Device ID are listed as table of "Table 6. ID Definitions".

The sequence of issuing RDID instruction is: CS# goes low $\rightarrow$  sending RDID instruction code  $\rightarrow$  24-bits ID data out on SO $\rightarrow$  to end RDID operation can use CS# to high at any time during data out.

While Program/Erase operation is in progress, it will not decode the RDID instruction, so there's no effect on the cycle of program/erase operation which is currently in progress. When CS# goes high, the device is at standby stage.

Figure 4. Read Identification (RDID) Sequence (Command 9F)



P/N: PM2163 REV. 1.2, October 21, 2016




# 9-4. Read Status Register (RDSR)

The RDSR instruction is for reading Status Register. The Read Status Register can be read at any time (even in program/erase/write status register condition) and continuously. It is recommended to check the Write in Progress (WIP) bit before sending a new instruction when a program, erase, or write status register operation is in progress.

The sequence of issuing RDSR instruction is: CS# goes low→ sending RDSR instruction code→ Status Register data out on SO.

The SIO[3:1] are don't care.

Figure 5. Read Status Register (RDSR) Sequence (Command 05)






# 9-5. Read Configuration Register (RDCR)

The RDCR instruction is for reading Configuration Register Bits. The Read Configuration Register can be read at any time (even in program/erase/write configuration register condition). It is recommended to check the Write in Progress (WIP) bit before sending a new instruction when a program, erase, or write configuration register operation is in progress.

The sequence of issuing RDCR instruction is: CS# goes low→ sending RDCR instruction code→ Configuration Register data out on SO.

The SIO[3:1] are don't care.

Figure 6. Read Configuration Register (RDCR) Sequence





# **Status Register**

The definition of the status register bits is as below:

**WIP bit.** The Write in Progress (WIP) bit, a volatile bit, indicates whether the device is busy in program/erase/ write status register progress. When WIP bit sets to 1, which means the device is busy in program/erase/write status register progress. When WIP bit sets to 0, which means the device is not in progress of program/erase/ write status register cycle.

**WEL bit.** The Write Enable Latch (WEL) bit, a volatile bit, indicates whether the device is set to internal write enable latch. When WEL bit sets to "1", which means the internal write enable latch is set, the device can accept program/erase/write status register instruction. When WEL bit sets to 0, which means no internal write enable latch; the device will not accept program/erase/write status register instruction. The program/erase command will be ignored and will reset WEL bit if it is applied to a protected memory area. To ensure both WIP bit & WEL bit are both set to 0 and available for next program/erase/operations, WIP bit needs to be confirm to be 0 before polling WEL bit. After WIP bit confirmed, WEL bit needs to be confirm to be 0.

**BP3, BP2, BP1, BP0 bits.** The Block Protect (BP3, BP2, BP1, BP0) bits, non-volatile bits, indicate the protected area (as defined in *"Table 1. Protected Area Sizes"*) of the device to against the program/erase instruction without hardware protection mode being set. To write the Block Protect (BP3, BP2, BP1, BP0) bits requires the Write Status Register (WRSR) instruction to be executed. Those bits define the protected area of the memory to against Page Program (PP), Sector Erase (SE), Block Erase (BE) and Chip Erase (CE) instructions (only if all Block Protect bits set to 0, the CE instruction can be executed). The BP3, BP2, BP1, BP0 bits are "0" as default. Which is un-protected.

**QE bit.** The Quad Enable (QE) bit, OTP bit, which is permanently set to "1". The flash always performs Quad I/O mode.

#### Status Register

bit7	bit6	bit5	bit4	bit3	bit2	bit1	bit0
Reserved	QE (Quad Enable)	BP3 (level of protected block)	BP2 (level of protected block)	BP1 (level of protected block)	BP0 (level of protected block)	WEL (write enable latch)	WIP (write in progress bit)
Reserved	1= Quad Enable	(note)	(note)	(note)	(note)	1=write enable 0=not write enable	1=write operation 0=not in write operation
Reserved	OTP bit	Non-volatile bit	Non-volatile bit	Non-volatile bit	Non-volatile bit	volatile bit	volatile bit

Note: see the "Table 1. Protected Area Sizes".



### **Configuration Register**

The Configuration Register is able to change the default status of Flash memory. Flash memory will be configured after the CR bit is set.

#### ODS bit

The output driver strength ODS bit are volatile bits, which indicate the output driver level of the device. The Output Driver Strength is defaulted=1 when delivered from factory. To write the ODS bit requires the Write Status Register (WRSR) instruction to be executed.

#### TB bit

The Top/Bottom (TB) bit is a OTP bit. The Top/Bottom (TB) bit is used to configure the Block Protect area by BP bit (BP3, BP2, BP1, BP0), starting from TOP or Bottom of the memory array. The TB bit is defaulted as "0", which means Top area protect. When it is set as "1", the protect area will change to Bottom area of the memory device. To write the TB bit requires the Write Status Register (WRSR) instruction to be executed.

# **Configuration Register**

bit7	bit6	bit5	bit4	bit3	bit2	bit1	bit0
Reserved	DC (Dummy Cycle)	Reserved	Reserved	TB (top/bottom selected)	Reserved	Reserved	ODS
х	2READ/ 4READ Dummy Cycle	х	х	0=Top area protect 1=Bottom area protect (Default=0)	х	х	0,Output driver strength=1 1,Output driver strength=1/4 (Default=0)
х	volatile	х	х	ОТР	х	х	volatile

Note: See "Dummy Cycle and Frequency Table", with "Don't Care" on other Reserved Configuration Registers.

#### **Dummy Cycle and Frequency Table**

	DC	Numbers of Dummy Cycles	Freq. (MHz)
2READ	0 (default)	4	104
	1	8	133
4READ	0 (default)	6	104
	1	10	133




# 9-6. Write Status Register (WRSR)

The WRSR instruction is for changing the values of Status Register Bits and Configuration Register Bits. Before sending WRSR instruction, the Write Enable (WREN) instruction must be decoded and executed to set the Write Enable Latch (WEL) bit in advance. The WRSR instruction can change the value of Block Protect (BP3, BP2, BP1, BP0) bits to define the protected area of memory (as shown in "Table 1. Protected Area Sizes").

The sequence of issuing WRSR instruction is: CS# goes low $\rightarrow$  sending WRSR instruction code $\rightarrow$  Status Register data on SI $\rightarrow$  CS# goes high.

Figure 7. Write Status Register (WRSR) Sequence (Command 01)





The CS# must go high exactly at the byte boundary; otherwise, the instruction will be rejected and not executed. The self-timed Write Status Register cycle time (tW) is initiated as soon as Chip Select (CS#) goes high. The Write in Progress (WIP) bit still can be checked out during the Write Status Register cycle is in progress. The WIP sets 1 during the tW timing, and sets 0 when Write Status Register Cycle is completed, and the Write Enable Latch (WEL) bit is reset.

**Table 5. Protection Modes** 

Mode	Status register condition	Memory
Software protection mode (SPM)	Status register can be written in (WEL bit is set to "1") and the BP0-BP3 bits can be changed	The protected area cannot be programmed or erased.


**Note:** As defined by the values in the Block Protect (BP3, BP2, BP1, BP0, TB) bits of the Status Register, as shown in "Table 1. Protected Area Sizes".

## Software Protected Mode (SPM):

- The WREN instruction may set the WEL bit and can change the values of BP3, BP2, BP1, BP0. The protected area, which is defined by BP3, BP2, BP1, BP0, is at software protected mode (SPM).



Figure 8. WRSR flow






# 9-7. Read Data Bytes (READ)

The read instruction is for reading data out. The address is latched on rising edge of SCLK, and data shifts out on the falling edge of SCLK at a maximum frequency fR. The first address byte can be at any location. The address is automatically increased to the next higher address after each byte data is shifted out, so the whole memory can be read out at a single READ instruction. The address counter rolls over to 0 when the highest address has been reached.

The sequence of issuing READ instruction is: CS# goes low $\rightarrow$  sending READ instruction code $\rightarrow$ 3-byte address on SI  $\rightarrow$ data out on SO $\rightarrow$  to end READ operation can use CS# to high at any time during data out.








# 9-8. Read Data Bytes at Higher Speed (FAST\_READ)

The FAST\_READ instruction is for quickly reading data out. The address is latched on rising edge of SCLK, and data of each bit shifts out on the falling edge of SCLK at a maximum frequency fC. The first address byte can be at any location. The address is automatically increased to the next higher address after each byte data is shifted out, so the whole memory can be read out at a single FAST\_READ instruction. The address counter rolls over to 0 when the highest address has been reached.

**Read on SPI Mode** The sequence of issuing FAST\_READ instruction is: CS# goes low $\rightarrow$  sending FAST\_READ instruction code $\rightarrow$  3-byte address on SI $\rightarrow$ 1-dummy byte (default) address on SI $\rightarrow$  data out on SO $\rightarrow$  to end FAST\_READ operation can use CS# to high at any time during data out. (Please refer to "Figure 10. Read at Higher Speed (FAST\_READ) Sequence (Command 0B)")

While Program/Erase/Write Status Register cycle is in progress, FAST\_READ instruction is rejected without any impact on the Program/Erase/Write Status Register current cycle.

Figure 10. Read at Higher Speed (FAST\_READ) Sequence (Command 0B)





# 9-9. Dual Read Mode (DREAD)

The DREAD instruction enable double throughput of Serial Flash in read mode. The address is latched on rising edge of SCLK, and data of every two bits (interleave on 2 I/O pins) shift out on the falling edge of SCLK at a maximum frequency fT. The first address byte can be at any location. The address is automatically increased to the next higher address after each byte data is shifted out, so the whole memory can be read out at a single DREAD instruction. The address counter rolls over to 0 when the highest address has been reached. Once writing DREAD instruction, the following data out will perform as 2-bit instead of previous 1-bit.

The sequence of issuing DREAD instruction is: CS# goes low  $\rightarrow$  sending DREAD instruction  $\rightarrow$  3-byte address on SI  $\rightarrow$  8-bit dummy cycle  $\rightarrow$  data out interleave on SIO1 & SIO0  $\rightarrow$  to end DREAD operation can use CS# to high at any time during data out.

While Program/Erase/Write Status Register cycle is in progress, DREAD instruction is rejected without any impact on the Program/Erase/Write Status Register current cycle.




Figure 11. Dual Read Mode Sequence (Command 3B)



# 9-10. 2 x I/O Read Mode (2READ)

The 2READ instruction enables Double Transfer Rate of Serial Flash in read mode. The address is latched on rising edge of SCLK, and data of every two bits (interleave on 2 I/O pins) shift out on the falling edge of SCLK at a maximum frequency fT. The first address byte can be at any location. The address is automatically increased to the next higher address after each byte data is shifted out, so the whole memory can be read out at a single 2READ instruction. The address counter rolls over to 0 when the highest address has been reached. Once writing 2READ instruction, the following address/dummy/data out will perform as 2-bit instead of previous 1-bit.

The sequence of issuing 2READ instruction is: CS# goes low $\rightarrow$  sending 2READ instruction $\rightarrow$  24-bit address interleave on SIO1 & SIO0 $\rightarrow$  4 dummy cycles(default) on SIO1 & SIO0 $\rightarrow$  data out interleave on SIO1 & SIO0 $\rightarrow$  to end 2READ operation can use CS# to high at any time during data out.

While Program/Erase/Write Status Register cycle is in progress, 2READ instruction is rejected without any impact on the Program/Erase/Write Status Register current cycle.




Figure 12. 2 x I/O Read Mode Sequence (Command BB)

**Note:** SI/SIO0 or SO/SIO1 should be kept "0h" or "Fh" in the first two dummy cycles. In other words, P2=P0 or P3=P1 is necessary.



### 9-11. Quad Read Mode (QREAD)

The QREAD instruction enable quad throughput of Serial Flash in read mode. The address is latched on rising edge of SCLK, and data of every four bits (interleave on 4 I/O pins) shift out on the falling edge of SCLK at a maximum frequency fQ. The first address byte can be at any location. The address is automatically increased to the next higher address after each byte data is shifted out, so the whole memory can be read out at a single QREAD instruction. The address counter rolls over to 0 when the highest address has been reached. Once writing QREAD instruction, the following data out will perform as 4-bit instead of previous 1-bit.

The sequence of issuing QREAD instruction is: CS# goes low $\rightarrow$  sending QREAD instruction  $\rightarrow$  3-byte address on SI  $\rightarrow$  8-bit dummy cycle  $\rightarrow$  data out interleave on SIO3, SIO2, SIO1 & SIO0 $\rightarrow$  to end QREAD operation can use CS# to high at any time during data out.

While Program/Erase/Write Status Register cycle is in progress, QREAD instruction is rejected without any impact on the Program/Erase/Write Status Register current cycle.




Figure 13. Quad Read Mode Sequence (Command 6B)

P/N: PM2163 REV. 1.2, October 21, 2016



### 9-12. 4 x I/O Read Mode (4READ)

The 4READ instruction enables quad throughput of Serial Flash in read mode. The address is latched on rising edge of SCLK, and data of every four bits (interleave on 4 I/O pins) shift out on the falling edge of SCLK at a maximum frequency fQ. The first address byte can be at any location. The address is automatically increased to the next higher address after each byte data is shifted out, so the whole memory can be read out at a single 4READ instruction. The address counter rolls over to 0 when the highest address has been reached. Once writing 4READ instruction, the following address/dummy/data out will perform as 4-bit instead of previous 1-bit.

**4 x I/O Read on SPI Mode (4READ)** The sequence of issuing 4READ instruction is: CS# goes low→ sending 4READ instruction→ 24-bit address interleave on SIO3, SIO2, SIO1 & SIO0→2+4 dummy cycles (default) →data out interleave on SIO3, SIO2, SIO1 & SIO0→ to end 4READ operation can use CS# to high at any time during data out. (Please refer to figure below)




Figure 14. 4 x I/O Read Mode Sequence (Command EB)

#### Note:

- 1. Hi-impedance is inhibited for the two clock cycles.
- 2.  $P7 \neq P3$ ,  $P6 \neq P2$ ,  $P5 \neq P1$  &  $P4 \neq P0$  (Toggling) is inhibited.
- 3. The Configurable Dummy Cycle is set by Configuration Register Bit. Please see "Dummy Cycle and Frequency Table"

P/N: PM2163 REV. 1.2, October 21, 2016





Another sequence of issuing 4READ instruction especially useful in random access is : CS# goes low $\rightarrow$  sending 4READ instruction $\rightarrow$  3-bytes address interleave on SIO3, SIO2, SIO1 & SIO0  $\rightarrow$ performance enhance toggling bit P[7:0] $\rightarrow$  4 dummy cycles  $\rightarrow$  data out until CS# goes high  $\rightarrow$  CS# goes low (reduce 4READ instruction)  $\rightarrow$  24-bit random access address (Please refer to "Figure 15. 4 x I/O Read enhance performance Mode Sequence (Command EB) (SPI Mode)").

In the performance-enhancing mode (Notes of "Figure 15. 4 x I/O Read enhance performance Mode Sequence (Command EB) (SPI Mode)"), P[7:4] must be toggling with P[3:0]; likewise P[7:0]=A5h, 5Ah, F0h or 0Fh can make this mode continue and reduce the next 4READ instruction. Once P[7:4] is no longer toggling with P[3:0]; likewise P[7:0]=FFh, 00h, AAh or 55h. These commands will reset the performance enhance mode. And afterwards CS# is raised and then lowered, the system then will return to normal operation.

While Program/Erase/Write Status Register cycle is in progress, 4READ instruction is rejected without any impact on the Program/Erase/Write Status Register current cycle.



#### 9-13. Performance Enhance Mode

The device could waive the command cycle bits if the two cycle bits after address cycle toggles. (Please note "Figure 15. 4 x I/O Read enhance performance Mode Sequence (Command EB) (SPI Mode)")

Performance enhance mode is supported for 4READ mode. "EBh" commands support enhance mode.

After entering enhance mode, following CS# go high, the device will stay in the read mode and treat CS# go low of the first clock as address instead of command cycle.

To exit enhance mode, a new fast read command whose first two dummy cycles is not toggle then exit. Or issue "FFh" data cycles to exit enhance mode.

CS# SCLK data bit4, bit0, bit4 EBh SI/SIO0 High Impedance address bit21, bit17..bit1 SO/SIO1 High Impedance data bit6 bit2, bit6 bit22, bit18..bit2 SIO2 High Impedance address bit23, bit19..bit3 SIO3 CS# SCLK Data Output address bit20, bit16..bit0 SI/SIO0 address bit21, bit17..bit1 SO/SIO1 data bit6 bit2, bit6 bit22, bit18..bit2 SIO<sub>2</sub> address bit23, bit19..bit3 SIO3

Figure 15. 4 x I/O Read enhance performance Mode Sequence (Command EB) (SPI Mode)

#### Note:

- 1. Performance enhance mode, if P7≠P3 & P6≠P2 & P5≠P1 & P4≠P0 (Toggling), ex: A5, 5A, 0F, if not using performance enhance recommend to keep 1 or 0 in performance enhance indicator.

  Reset the performance enhance mode, if P7=P3 or P6=P2 or P5=P1 or P4=P0, ex: AA, 00, FF
- The Configurable Dummy Cycle is set by Configuration Register Bit. Please see "Dummy Cycle and Frequency Table"

P/N: PM2163 REV. 1.2, October 21, 2016 33



#### 9-14. Burst Read


To set the Burst length, following command operation is required Issuing command: "77h" in the first Byte (8-clocks), following 4 clocks defining wrap around enable with "0h" and disable with "1h".

Next 4 clocks is to define wrap around depth. Definition as following table:

Data	Wrap Around	Wrap Depth
00h	Yes	8-byte
01h	Yes	16-byte
02h	Yes	32-byte
03h	Yes	64-byte
1xh	No	X

The wrap around unit is defined within the wrap-around depth specified region. For example, if it is set to 32-byte wrap depth, then address above A5 will be kept, it will read wrap around within A[21:A5] specified page. To exit wrap around, it is required to issue another "77" command in which data='1xh". Otherwise, wrap around status will be retained until power down or reset command. To change wrap around depth, it is required to issue another "77" command in which data="0xh". SPI "EBh" support wrap around feature after wrap around enable. The Device ID default without Burst read.

#### **SPI Mode**





### 9-15. Sector Erase (SE)


The Sector Erase (SE) instruction is for erasing the data of the chosen sector to be "1". The instruction is used for any 4K-byte sector. A Write Enable (WREN) instruction must be executed to set the Write Enable Latch (WEL) bit before sending the Sector Erase (SE). Any address of the sector (see "Table 3. Memory Organization") is a valid address for Sector Erase (SE) instruction. The CS# must go high exactly at the byte boundary (the least significant bit of the address has been latched-in); otherwise, the instruction will be rejected and not executed.

The sequence of issuing SE instruction is: CS# goes low  $\rightarrow$  sending SE instruction code $\rightarrow$  3-byte address on SI  $\rightarrow$ CS# goes high.

The SIO[3:1] are don't care.

The self-timed Sector Erase Cycle time (tSE) is initiated as soon as Chip Select (CS#) goes high. The Write in Progress (WIP) bit still can be checked while the Sector Erase cycle is in progress. The WIP sets during the tSE timing, and clears when Sector Erase Cycle is completed, and the Write Enable Latch (WEL) bit is cleared. If the sector is protected by BP3~0, the array data will be protected (no change) and the WEL bit still be reset.

Figure 16. Sector Erase (SE) Sequence (Command 20)





### 9-16. Block Erase (BE)


The Block Erase (BE) instruction is for erasing the data of the chosen block to be "1". The instruction is used for 64K-byte block erase operation. A Write Enable (WREN) instruction must be executed to set the Write Enable Latch (WEL) bit before sending the Block Erase (BE). Any address of the block (see "Table 3. Memory Organization") is a valid address for Block Erase (BE) instruction. The CS# must go high exactly at the byte boundary (the least significant bit of address byte has been latched-in); otherwise, the instruction will be rejected and not executed.

The sequence of issuing BE instruction is: CS# goes low  $\rightarrow$  sending BE instruction code  $\rightarrow$  3-byte address on SI  $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.

The self-timed Block Erase Cycle time (tBE) is initiated as soon as Chip Select (CS#) goes high. The Write in Progress (WIP) bit still can be checked while the Sector Erase cycle is in progress. The WIP sets during the tBE timing, and clears when Sector Erase Cycle is completed, and the Write Enable Latch (WEL) bit is cleared. If the block is protected by BP3~0, the array data will be protected (no change) and the WEL bit still be reset.

Figure 17. Block Erase (BE) Sequence (Command D8)





#### 9-17. Block Erase (BE32K)


The Block Erase (BE32K) instruction is for erasing the data of the chosen block to be "1". The instruction is used for 32K-byte block erase operation. A Write Enable (WREN) instruction must be executed to set the Write Enable Latch (WEL) bit before sending the Block Erase (BE32K). Any address of the block (see "Table 3. Memory Organization") is a valid address for Block Erase (BE32K) instruction. The CS# must go high exactly at the byte boundary (the least significant bit of address byte has been latched-in); otherwise, the instruction will be rejected and not executed.

The sequence of issuing BE32K instruction is: CS# goes low  $\rightarrow$  sending BE32K instruction code  $\rightarrow$  3-byte address on SI  $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.

The self-timed Block Erase Cycle time (tBE32K) is initiated as soon as Chip Select (CS#) goes high. The Write in Progress (WIP) bit still can be checked while the Sector Erase cycle is in progress. The WIP sets during the tBE32K timing, and clears when Sector Erase Cycle is completed, and the Write Enable Latch (WEL) bit is cleared. If the block is protected by BP3~0, the array data will be protected (no change) and the WEL bit still be reset.

Figure 18. Block Erase 32KB (BE32K) Sequence (Command 52)





## 9-18. Chip Erase (CE)


The Chip Erase (CE) instruction is for erasing the data of the whole chip to be "1". A Write Enable (WREN) instruction must be executed to set the Write Enable Latch (WEL) bit before sending the Chip Erase (CE). The CS# must go high exactly at the byte boundary; otherwise, the instruction will be rejected and not executed.

The sequence of issuing CE instruction is: CS# goes low  $\rightarrow$  sending CE instruction code  $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.

The self-timed Chip Erase Cycle time (tCE) is initiated as soon as Chip Select (CS#) goes high. The Write in Progress (WIP) bit still can be checked while the Chip Erase cycle is in progress. The WIP sets during the tCE timing, and clears when Chip Erase Cycle is completed, and the Write Enable Latch (WEL) bit is cleared. If the chip is protected the Chip Erase (CE) instruction will not be executed, but WEL will be reset.

Figure 19. Chip Erase (CE) Sequence (Command 60 or C7)





#### 9-19. Page Program (PP)

The Page Program (PP) instruction is for programming the memory to be "0". A Write Enable (WREN) instruction must be executed to set the Write Enable Latch (WEL) bit before sending the Page Program (PP). The device programs only the last 256 data bytes sent to the device. The last address byte (the eight least significant address bits, A7-A0) should be set to 0 for 256 bytes page program. If A7-A0 are not all zero, transmitted data that exceed page length are programmed from the starting address (24-bit address that last 8 bit are all 0) of currently selected page. If the data bytes sent to the device exceeds 256, the last 256 data byte is programmed at the requested page and previous data will be disregarded. If the data bytes sent to the device has not exceeded 256, the data will be programmed at the request address of the page. There will be no effort on the other data bytes of the same page.


The sequence of issuing PP instruction is: CS# goes low→ sending PP instruction code→ 3-byte address on  $SI \rightarrow at least 1-byte on data on <math>SI \rightarrow CS\# goes high.$ 

The CS# must be kept to low during the whole Page Program cycle; The CS# must go high exactly at the byte boundary (the latest eighth bit of data being latched in), otherwise, the instruction will be rejected and will not be executed.

The self-timed Page Program Cycle time (tPP) is initiated as soon as Chip Select (CS#) goes high. The Write in Progress (WIP) bit still can be checked while the Page Program cycle is in progress. The WIP sets during the tPP timing, and clears when Page Program Cycle is completed, and the Write Enable Latch (WEL) bit is cleared. If the page is protected by BP3~0, the array data will be protected (no change) and the WEL bit will still be reset.

The SIO[3:1] are don't care.









## 9-20. 4 x I/O Page Program (4PP)

The Quad Page Program (4PP) instruction is for programming the memory to be "0". instruction must be executed to set the Write Enable Latch (WEL) bit to "1" before sending the Quad Page Program (4PP). The Quad Page Programming takes four pins: SIO0, SIO1, SIO2, and SIO3, which can raise programmer performance and the effectiveness of application of lower clock less than 133MHz. For system with faster clock, the Quad page program cannot provide more performance, because the required internal page program time is far more than the time data flows in. Therefore, we suggest that while executing this command (especially during sending data), user can slow the clock speed down to 133MHz below. The other function descriptions are as same as standard page program.

The sequence of issuing 4PP instruction is: CS# goes low $\rightarrow$  sending 4PP instruction code $\rightarrow$  3-byte address on SIO[3:0] $\rightarrow$  at least 1-byte on data on SIO[3:0] $\rightarrow$  CS# goes high.

If the page is protected by BP3~0, the array data will be protected (no change) and the WEL bit will still be reset.







The Program/Erase function instruction function flow is as follows:

Figure 22. Program/Erase Flow(1) with read array data







Figure 23. Program/Erase Flow(2) without read array data






## 9-21. Deep Power-down (DP)


The Deep Power-down (DP) instruction places the device into a minimum power consumption state, Deep Power-down mode, in which the quiescent current is reduced from ISB1 to ISB2.

The sequence of issuing DP instruction: CS# goes low→ send DP instruction code→ CS# goes high. The CS# must go high at the byte boundary (after exactly eighth bits of the instruction code have been latched-in); otherwise the instruction will not be executed. SIO[3:1] are "don't care".

After CS# goes high there is a delay of tDP before the device transitions from Stand-by mode to Deep Powerdown mode and before the current reduces from ISB1 to ISB2. Once in Deep Power-down mode, all instructions will be ignored except Release from Deep Power-down (RDP).

The device exits Deep Power-down mode and returns to Stand-by mode if it receives a Release from Deep Power-down (RDP) instruction, power-cycle, or reset.







## 9-22. Release from Deep Power-down (RDP), Read Electronic Signature (RES)

The Release from Deep Power-down (RDP) instruction is completed by driving Chip Select (CS#) High. When Chip Select (CS#) is driven High, the device is put in the standby Power mode. If the device was not previously in the Deep Power-down mode, the transition to the standby Power mode is immediate. If the device was previously in the Deep Power-down mode, though, the transition to the standby Power mode is delayed by tRES2, and Chip Select (CS#) must remain High for at least tRES2(max), as specified in "Table 15. AC Characteristics". Once in the standby mode, the device waits to be selected, so that it can receive, decode and execute instructions.

RES instruction is for reading out the old style of 8-bit Electronic Signature, whose values are shown as "Table 6. ID Definitions". This is not the same as RDID instruction. It is not recommended to use for new design. For new design, please use RDID instruction. Even in Deep power-down mode, the RDP and RES are also allowed to be executed, only except the device is in progress of program/erase/write cycles; there's no effect on the current program/erase/write cycles in progress.

The SIO[3:1] are don't care in this mode.

The RES instruction is ended by CS# goes high after the ID been read out at least once. The ID outputs repeatedly if continuously send the additional clock cycles on SCLK while CS# is at low. If the device was not previously in Deep Power-down mode, the device transition to standby mode is immediate. If the device was previously in Deep Power-down mode, there's a delay of tRES2 to transit to standby mode, and CS# must remain to high at least tRES2(max). Once in the standby mode, the device waits to be selected, so it can receive, decode, and execute instruction.

The RDP instruction is for releasing from Deep Power-down Mode.





Figure 25. Read Electronic Signature (RES) Sequence (Command AB)

P/N: PM2163 REV. 1.2, October 21, 2016



Figure 26. Release from Deep Power-down (RDP) Sequence






## 9-23. Read Electronic Manufacturer ID & Device ID (REMS)

The REMS instruction returns both the JEDEC assigned manufacturer ID and the device ID. The Device ID values are listed in "Table 6. ID Definitions".

The REMS instruction is initiated by driving the CS# pin low and sending the instruction code "90h" followed by two dummy bytes and one address byte (A7~A0). After which the manufacturer ID for Macronix (C2h) and the device ID are shifted out on the falling edge of SCLK with the most significant bit (MSB) first. If the address byte is 00h, the manufacturer ID will be output first, followed by the device ID. If the address byte is 01h, then the device ID will be output first, followed by the manufacturer ID. While CS# is low, the manufacturer and device IDs can be read continuously, alternating from one to the other. The instruction is completed by driving CS# high.

Figure 27. Read Electronic Manufacturer & Device ID (REMS) Sequence



#### Note:

(1) ADD=00H will output the manufacturer's ID first and ADD=01H will output device ID first.

P/N: PM2163 REV. 1.2, October 21, 2016



#### **Table 6. ID Definitions**

Command Type	MX25L3273F					
RDID	Manufactory ID	Memory type	Memory density			
טוטא	C2	20	16			
DEC	Electronic ID					
RES	15					
DEMO	Manufactory ID	ctory ID Device ID				
REMS	C2	15				

## 9-24. Enter Secured OTP (ENSO)

The ENSO instruction is for entering the additional 4K-bit Secured OTP mode. While the device is in 4K-bit Secured OTP mode, array access is not available. The additional 4K-bit Secured OTP is independent from main array, and may be used to store unique serial number for system identifier. After entering the Secured OTP mode, follow standard read or program procedure to read out the data or update data. The Secured OTP data cannot be updated again once it is lock-down.

The sequence of issuing ENSO instruction is: CS# goes low→ sending ENSO instruction to enter Secured OTP mode→ CS# goes high.

The SIO[3:1] are don't care.

Please note that WRSR/WRSCUR/CE/BE/SE/BE32K commands are not acceptable during the access of secure OTP region, once Security OTP is locked down, only read related commands are valid.

#### 9-25. Exit Secured OTP (EXSO)

The EXSO instruction is for exiting the additional 4K-bit Secured OTP mode.

The sequence of issuing EXSO instruction is: CS# goes low $\rightarrow$  sending EXSO instruction to exit Secured OTP mode $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.




#### 9-26. Read Security Register (RDSCUR)

The RDSCUR instruction is for reading the value of Security Register. The Read Security Register can be read at any time (even in program/erase/write status register/write security register condition) and continuously.

The sequence of issuing RDSCUR instruction is : CS# goes low $\rightarrow$  sending RDSCUR instruction  $\rightarrow$  Security Register data out on SO $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.

Figure 28. Read Security Register (RDSCUR) Sequence (Command 2B)



The definition of the Security Register is as below:

**Secured OTP Indicator bit.** The Secured OTP indicator bit shows the chip is locked by factory or not. When it is "0", it indicates non-factory lock; "1" indicates factory-lock.

**Lock-down Secured OTP (LDSO) bit.** By writing WRSCUR instruction, the LDSO bit may be set to "1" for customer lock-down purpose. However, once the bit is set to "1" (lock-down), the LDSO bit and the 4K-bit Secured OTP area cannot be updated any more.

**Program Suspend Status bit.** Program Suspend Bit (PSB) indicates the status of Program Suspend operation. Users may use PSB to identify the state of flash memory. After the flash memory is suspended by Program Suspend command, PSB is set to "1". PSB is cleared to "0" after program operation resumes.

**Erase Suspend Status bit.** Erase Suspend Bit (ESB) indicates the status of Erase Suspend operation. Users may use ESB to identify the state of flash memory. After the flash memory is suspended by Erase Suspend command, ESB is set to "1". ESB is cleared to "0" after erase operation resumes.

P/N: PM2163 REV. 1.2, October 21, 2016





**Program Fail Flag bit.** While a program failure happened, the Program Fail Flag bit would be set. If the program operation fails on a protected memory region or locked OTP region, this bit will also be set. This bit can be the failure indication of one or more program operations. This fail flag bit will be cleared automatically after the next successful program operation.

**Erase Fail Flag bit.** While an erase failure happened, the Erase Fail Flag bit would be set. If the erase operation fails on a protected memory region or locked OTP region, this bit will also be set. This bit can be the failure indication of one or more erase operations. This fail flag bit will be cleared automatically after the next successful erase operation.

**Table 7. Security Register Definition** 

bit7	bit6	bit5	bit4	bit3	bit2	bit1	bit0
Reserved	E_FAIL	P_FAIL	Reserved	ESB (Erase Suspend status)	PSB (Program Suspend status)	LDSO (lock-down 4K-bit Secured OTP)	Secured OTP Indicator bit (2 <sup>nd</sup> 4K-bit Secured OTP)
Reserved	0=normal Erase succeed 1=indicate Erase failed (default=0)	0=normal Program succeed  1=indicate Program failed (default=0)	Reserved	0=Erase is not suspended 1=Erase is suspended (default=0)	0=Program is not suspended 1=Program is suspended (default=0)	0 = not lockdown 1 = lock-down (cannot program/ erase OTP)	0 = nonfactory lock 1 = factory lock
non-volatile bit	volatile bit	volatile bit	volatile bit	volatile bit	volatile bit	non-volatile bit	non-volatile bit
Reserved	Read Only	Read Only		Read Only	Read Only	ОТР	Read Only



## 9-27. Write Security Register (WRSCUR)


The WRSCUR instruction is for changing the values of Security Register Bits. Unlike write status register, the WREN instruction is required before sending WRSCUR instruction. The WRSCUR instruction may change the values of bit1 (LDSO bit) for customer to lock-down the 4K-bit Secured OTP area. Once the LDSO bit is set to "1", the Secured OTP area cannot be updated any more.

The sequence of issuing WRSCUR instruction is :CS# goes low $\rightarrow$  sending WRSCUR instruction  $\rightarrow$  CS# goes high.

The SIO[3:1] are don't care.

The CS# must go high exactly at the boundary; otherwise, the instruction will be rejected and not executed.

Figure 29. Write Security Register (WRSCUR) Sequence (Command 2F) (SPI mode)





#### 9-28. Program Suspend and Erase Suspend

The Suspend instruction interrupts a Page Program, Sector Erase, or Block Erase operation to allow access to the memory array. After the program or erase operation has entered the suspended state, the memory array can be read except for the page being programmed or the sector or block being erased ("Table 8. Readable Area of Memory While a Program or Erase Operation is Suspended").

Table 8. Readable Area of Memory While a Program or Erase Operation is Suspended

Suspended Operation	Readable Region of Memory Array
Page Program	All but the Page being programmed
Sector Erase (4KB)	All but the 4KB Sector being erased
Block Erase (32KB)	All but the 32KB Block being erased
Block Erase (64KB)	All but the 64KB Block being erased

When the serial flash receives the Suspend instruction, there is a latency of tPSL or tESL ("Figure 30. Suspend to Read Latency") before the Write Enable Latch (WEL) bit clears to "0" and the PSB or ESB sets to "1", after which the device is ready to accept one of the commands listed in "Table 9. Acceptable Commands During Suspend after tPSL/tESL" (e.g. FAST READ). Refer to "Table 15. AC Characteristics" for tPSL and tESL timings. "Table 10. Acceptable Commands During Suspend (tPSL/tESL not required)" lists the commands for which the tPSL and tESL latencies do not apply. For example, RDSR, RDSCUR, RSTEN, and RST can be issued at any time after the Suspend instruction.

Security Register bit 2 (PSB) and bit 3 (ESB) can be read to check the suspend status. The PSB (Program Suspend Bit) sets to "1" when a program operation is suspended. The ESB (Erase Suspend Bit) sets to "1" when an erase operation is suspended. The PSB or ESB clears to "0" when the program or erase operation is resumed.

Table 9. Acceptable Commands During Suspend after tPSL/tESL

		Suspen	d Type
Command Name	Command Code	Program Suspend	Erase Suspend
READ	03h	•	•
FAST READ	0Bh	•	•
DREAD	3Bh	•	•
QREAD	6Bh	•	•
2READ	BBh	•	•
4READ	EBh	•	•
RDSFDP	5Ah	•	•
RDID	9Fh	•	•
REMS	90h	•	•
ENSO	B1h	•	•
EXSO	C1h	•	•
WREN	06h		•
RESUME	7Ah or 30h	•	•
PP	02h		•
4PP	38h		•



Table 10. Acceptable Commands During Suspend (tPSL/tESL not required)

			d Type
Command Name	Command Code	Program Suspend	Erase Suspend
WRDI	04h	•	•
RDSR	05h	•	•
RDCR	15h	•	•
RDSCUR	2Bh	•	•
RES	ABh	•	•
RSTEN	66h	•	•
RST	99h	•	•
NOP	00h	•	•

Figure 30. Suspend to Read Latency





Figure 31. Resume to Suspend Latency






#### 9-28-1. Erase Suspend to Program

The "Erase Suspend to Program" feature allows Page Programming while an erase operation is suspended. Page Programming is permitted in any unprotected memory except within the sector of a suspended Sector Erase operation or within the block of a suspended Block Erase operation. The Write Enable (WREN) instruction must be issued before any Page Program instruction.

A Page Program operation initiated within a suspended erase cannot itself be suspended and must be allowed to finish before the suspended erase can be resumed. The Status Register can be polled to determine the status of the Page Program operation. The WEL and WIP bits of the Status Register will remain "1" while the Page Program operation is in progress and will both clear to "0" when the Page Program operation completes.

Figure 32. Suspend to Program Latency



#### 9-29. Program Resume and Erase Resume

The Resume instruction resumes a suspended Page Program, Sector Erase, or Block Erase operation. Before issuing the Resume instruction to restart a suspended erase operation, make sure that there is no Page Program operation in progress.

Immediately after the serial flash receives the Resume instruction, the WEL and WIP bits are set to "1" and the PSB or ESB is cleared to "0". The program or erase operation will continue until finished ("Figure 33. Resume to Read Latency") or until another Suspend instruction is received. A resume-to-suspend latency of tPRS or tERS must be observed before issuing another Suspend instruction ("Figure 31. Resume to Suspend Latency").

Please note that the Resume instruction will be ignored if the serial flash is in "Performance Enhance Mode". Make sure the serial flash is not in "Performance Enhance Mode" before issuing the Resume instruction.

Figure 33. Resume to Read Latency





## 9-30. No Operation (NOP)

The "No Operation" command is only able to terminate the Reset Enable (RSTEN) command and will not affect any other command.

## 9-31. Software Reset (Reset-Enable (RSTEN) and Reset (RST))


The Software Reset operation combines two instructions: Reset-Enable (RSTEN) command and Reset (RST) command. It returns the device to a standby mode. All the volatile bits and settings will be cleared then, which makes the device return to the default status as power on.

To execute Reset command (RST), the Reset-Enable (RSTEN) command must be executed first to perform the Reset operation. If there is any other command to interrupt after the Reset-Enable command, the Reset-Enable will be invalid.

If the Reset command is executed during program or erase operation, the operation will be disabled, the data under processing could be damaged or lost.

The reset time is different depending on the last operation. Longer latency time is required to recover from a program operation than from other operations.

Figure 34. Software Reset Recovery






## 9-32. Read SFDP Mode (RDSFDP)

The Serial Flash Discoverable Parameter (SFDP) standard provides a consistent method of describing the functional and feature capabilities of serial flash devices in a standard set of internal parameter tables. These parameter tables can be interrogated by host system software to enable adjustments needed to accommodate divergent features from multiple vendors. The concept is similar to the one found in the Introduction of JEDEC Standard, JESD68 on CFI.

The sequence of issuing RDSFDP instruction is CS# goes low $\rightarrow$ send RDSFDP instruction (5Ah) $\rightarrow$ send 3 address bytes on SI pin $\rightarrow$ send 1 dummy byte on SI pin $\rightarrow$ read SFDP code on SO $\rightarrow$ to end RDSFDP operation can use CS# to high at any time during data out.

SFDP is a JEDEC Standard, JESD216.

Figure 35. Read Serial Flash Discoverable Parameter (RDSFDP) Sequence



P/N: PM2163 REV. 1.2, October 21, 2016



## **Table 11. Signature and Parameter Identification Data Values**

SFDP Table (JESD216) below is for MX25L3273FM2I-08G and MX25L3273FM2I-08Q

Description	Comment	Add (h) (Byte)	DW Add (Bit)	Data (h/b) (Note1)	Data (h)
		00h	07:00	53h	53h
SEDD Signatura	Fixed: 50444653h	01h	15:08	46h	46h
SFDP Signature	Fixed: 5044405511	02h	23:16	44h	44h
		03h	31:24	50h	50h
SFDP Minor Revision Number	Start from 00h	04h	07:00	00h	00h
SFDP Major Revision Number	Start from 01h	05h	15:08	01h	01h
Number of Parameter Headers	This number is 0-based. Therefore, 0 indicates 1 parameter header.	06h	23:16	01h	01h
Unused		07h	31:24	FFh	FFh
ID number (JEDEC)	00h: it indicates a JEDEC specified header.	08h	07:00	00h	00h
Parameter Table Minor Revision Number	Start from 00h	09h	15:08	00h	00h
Parameter Table Major Revision Number	Start from 01h	0Ah	23:16	01h	01h
Parameter Table Length (in double word)	How many DWORDs in the Parameter table	0Bh	31:24	09h	09h
		0Ch	07:00	30h	30h
Parameter Table Pointer (PTP)	First address of JEDEC Flash Parameter table	0Dh	15:08	00h	00h
	r drameter table	0Eh	23:16	00h	00h
Unused		0Fh	31:24	FFh	FFh
ID number (Macronix manufacturer ID)	it indicates Macronix manufacturer ID	10h	07:00	C2h	C2h
Parameter Table Minor Revision Number	Start from 00h	11h	15:08	00h	00h
Parameter Table Major Revision Number	Start from 01h	12h	23:16	01h	01h
Parameter Table Length (in double word)	How many DWORDs in the Parameter table	13h	31:24	04h	04h
		14h	07:00	60h	60h
Parameter Table Pointer (PTP)	First address of Macronix Flash Parameter table	15h	15:08	00h	00h
	. E. E. Motor (abio	16h	23:16	00h	00h
Unused		17h	31:24	FFh	FFh



## Table 12. Parameter Table (0): JEDEC Flash Parameter Tables

SFDP Table below is for MX25L3273FM2I-08G and MX25L3273FM2I-08Q

Description	Comment	Add (h) (Byte)	DW Add (Bit)	Data (h/b) (Note1)	Data (h)
Block/Sector Erase sizes	00: Reserved, 01: 4KB erase, 10: Reserved, 11: not support 4KB erase		01:00	01b	
Write Granularity	0: 1Byte, 1: 64Byte or larger		02	1b	
Write Enable Instruction Required for Writing to Volatile Status Registers	0: not required 1: required 00h to be written to the status register	30h	03	0b	E5h
Write Enable Opcode Select for Writing to Volatile Status Registers	0: use 50h opcode, 1: use 06h opcode Note: If target flash status register is nonvolatile, then bits 3 and 4 must be set to 00b.		04	0b	
Unused	Contains 111b and can never be changed		07:05	111b	
4KB Erase Opcode		31h	15:08	20h	20h
(1-1-2) Fast Read (Note2)	0=not support 1=support		16	1b	
Address Bytes Number used in addressing flash array	00: 3Byte only, 01: 3 or 4Byte, 10: 4Byte only, 11: Reserved		18:17	00b	F1h
Double Transfer Rate (DTR) Clocking	0=not support 1=support		19	0b	
(1-2-2) Fast Read	0=not support 1=support	32h	20	1b	
(1-4-4) Fast Read	0=not support 1=support		21	1b	
(1-1-4) Fast Read	0=not support 1=support		22	1b	
Unused			23	1b	
Unused		33h	31:24	FFh	FFh
Flash Memory Density		37h:34h	31:00	01FF F	FFFh
states (Note3)	0 0000b: Not supported; 0 0100b: 4 0 0110b: 6; 0 1000b: 8	- 38h	04:00	0 0100b	44h
(1-4-4) Fast Read Number of Mode Bits (Note4)	Mode Bits: 000b: Not supported; 010b: 2 bits	3011	07:05	010b	<del>44</del> 11
(1-4-4) Fast Read Opcode		39h	15:08	EBh	EBh
-1-4) Fast Read Number of Wait 0 0000b: Not supported; 0 0100 ates 0 0110b: 6; 0 1000b: 8		3Ah	20:16	0 1000b	08h
(1-1-4) Fast Read Number of Mode Bits	Mode Bits: 000b: Not supported; 010b: 2 bits	0/311	23:21	000b	
(1-1-4) Fast Read Opcode		3Bh	31:24	6Bh	6Bh





## SFDP Table below is for MX25L3273FM2I-08G and MX25L3273FM2I-08Q

Description	Comment	Add (h) (Byte)	DW Add (Bit)	Data (h/b) (Note1)	Data (h)	
(1-1-2) Fast Read Number of Wait states	0 0000b: Not supported; 0 0100b: 4 0 0110b: 6; 0 1000b: 8	3Ch	04:00	0 1000b	08h	
(1-1-2) Fast Read Number of Mode Bits	Mode Bits: 000b: Not supported; 010b: 2 bits	3011	07:05	000b	UOII	
(1-1-2) Fast Read Opcode		3Dh	15:08	3Bh	3Bh	
(1-2-2) Fast Read Number of Wait states	0 0000b: Not supported; 0 0100b: 4 0 0110b: 6; 0 1000b: 8	3Eh	20:16	0 0100b	04h	
(1-2-2) Fast Read Number of Mode Bits	Mode Bits: 000b: Not supported; 010b: 2 bits	JEII	23:21	000b	U <del>-1</del> 11	
(1-2-2) Fast Read Opcode		3Fh	31:24	BBh	BBh	
(2-2-2) Fast Read	0=not support 1=support		00	0b		
Unused		40h	03:01	111b	FFh	
(4-4-4) Fast Read	0=not support 1=support	40h	04	0b	EEh	
Unused			07:05	111b		
Unused		43h:41h	31:08	FFh	FFh	
Unused		45h:44h	15:00	FFh	FFh	
(2-2-2) Fast Read Number of Wait states	0 0000b: Not supported; 0 0100b: 4 0 0110b: 6; 0 1000b: 8	46h	20:16	0 0000b	00h	
(2-2-2) Fast Read Number of Mode Bits	Mode Bits: 000b: Not supported; 010b: 2 bits	4011	23:21	000b	OUII	
(2-2-2) Fast Read Opcode		47h	31:24	FFh	FFh	
Unused		49h:48h	15:00	FFh	FFh	
states	0 0000b: Not supported; 0 0100b: 4 0 0110b: 6; 0 1000b: 8	4Ah	20:16	0 0000b	00h	
(4-4-4) Fast Read Number of Mode Bits	Mode Bits: 000b: Not supported; 010b: 2 bits	4/11	23:21	000b	0011	
(4-4-4) Fast Read Opcode		4Bh	31:24	FFh	FFh	
Sector Type 1 Size	Sector/block size = 2^N bytes (Note5) 0Ch: 4KB; 0Fh: 32KB; 10h: 64KB	4Ch	07:00	0Ch	0Ch	
Sector Type 1 erase Opcode		4Dh	15:08	20h	20h	
Sector Type 2 Size	Sector/block size = 2^N bytes 00h: N/A; 0Fh: 32KB; 10h: 64KB	4Eh	23:16	0Fh	0Fh	
Sector Type 2 erase Opcode		4Fh	31:24	52h	52h	
Sector Type 3 Size	Sector/block size = 2^N bytes 00h: N/A; 0Fh: 32KB; 10h: 64KB	50h	07:00	10h	10h	
Sector Type 3 erase Opcode		51h	15:08	D8h	D8h	
Sector Type 4 Size	00h: N/A, This sector type doesn't exist	52h	23:16	00h	00h	
Sector Type 4 erase Opcode		53h	31:24	FFh	FFh	



## Table 13. Parameter Table (1): Macronix Flash Parameter Tables

SFDP Table below is for MX25L3273FM2I-08G and MX25L3273FM2I-08Q

Description	Comment	Add (h) (Byte)	DW Add (Bit)	Data (h/b) (Note1)	Data (h)
Vcc Supply Maximum Voltage	2000h=2.000V 2700h=2.700V 3600h=3.600V	61h:60h	07:00 15:08	00h 36h	00h 36h
Vcc Supply Minimum Voltage	1650h=1.650V, 1750h=1.750V 2250h=2.250V, 2300h=2.300V 2350h=2.350V, 2650h=2.650V 2700h=2.700V	63h:62h	23:16 31:24	50h 26h	50h 26h
H/W Reset# pin	0=not support 1=support		00	0b	
H/W Hold# pin	0=not support 1=support		01	0b	
Deep Power Down Mode	0=not support 1=support		02	1b	
S/W Reset	0=not support 1=support		03	1b	
S/W Reset Opcode	Reset Enable (66h) should be issued before Reset Opcode	65h:64h	11:04	1001 1001b (99h)	F99Ch
Program Suspend/Resume	0=not support 1=support		12	1b	
Erase Suspend/Resume	0=not support 1=support		13	1b	
Unused			14	1b	
Wrap-Around Read mode	0=not support 1=support		15	1b	
Wrap-Around Read mode Opcode		66h	23:16	77h	77h
Wrap-Around Read data length	08h:support 8B wrap-around read 16h:8B&16B 32h:8B&16B&32B 64h:8B&16B&32B&64B	67h	31:24	64h	64h
Individual block lock	0=not support 1=support		00	0b	
Individual block lock bit (Volatile/Nonvolatile)	0=Volatile 1=Nonvolatile		01	1b	
Individual block lock Opcode			09:02	1111 1111b (FFh)	
Individual block lock Volatile protect bit default protect status	0=protect 1=unprotect	001-001-	10	1b	CFFEh
Secured OTP	0=not support 1=support	6Bh:68h	11	1b	
Read Lock	0=not support 1=support		12	0b	
Permanent Lock	0=not support 1=support		13	0b	
Unused			15:14	11b	
Unused			31:16	FFh	FFh
Unused		6Fh:6Ch	31:00	FFh	FFh





#### Notes:

- 1: h/b is hexadecimal or binary.
- 2: (x-y-z) means I/O mode nomenclature used to indicate the number of active pins used for the opcode (x), address (y), and data (z). At the present time, the only valid Read SFDP instruction modes are: (1-1-1), (2-2-2), and (4-4-4)
- 3: Wait States is required dummy clock cycles after the address bits or optional mode bits.
- 4: Mode Bits is optional control bits that follow the address bits. These bits are driven by the system controller if they are specified. (eg,read performance enhance toggling bits)
- 5: 4KB=2^0Ch,32KB=2^0Fh,64KB=2^10h
- 6: All unused and undefined area data is blank FFh for SFDP Tables that are defined in Parameter Identification Header. All other areas beyond defined SFDP Table are reserved by Macronix.





#### 10. POWER-ON STATE

The device is at the following states after power-up:

- Standby mode
- Write Enable Latch (WEL) bit is reset

The device must not be selected during power-up and power-down stage until the VCC reaches the following levels:

- VCC minimum at power-up stage and then after a delay of tVSL
- GND at power-down

Please note that a pull-up resistor on CS# may ensure a safe and proper power-up/down level.

An internal Power-on Reset (POR) circuit may protect the device from data corruption and inadvertent data change during power up state.

For further protection on the device, if the VCC does not reach the VCC minimum level, the correct operation is not guaranteed. The read, write, erase, and program command should be sent after the time delay:

- tVSL after VCC reached VCC minimum level

The device can accept read command after VCC reached VCC minimum and a time delay of tVSL.

#### Note:

- To stabilize the VCC level, the VCC rail decoupled by a suitable capacitor close to package pins is recommended. (generally around 0.1uF)



## 11. Electrical Specifications

#### 11-1. Absolute Maximum Ratings

RATING		VALUE
Ambient Operating Temperature	Industrial grade	-40°C to 85°C
Storage Temperature		-65°C to 150°C
Applied Input Voltage	-0.5V to 4.6V	
Applied Output Voltage	-0.5V to 4.6V	
VCC to Ground Potential		-0.5V to 4.6V

#### NOTICE:

- 1. Stresses greater than those listed under ABSOLUTE MAXIMUM RATINGS may cause permanent damage to the device. This is stress rating only and functional operational sections of this specification is not implied. Exposure to absolute maximum rating conditions for extended period may affect reliability.
- 2. Specifications contained within the following tables are subject to change.
- 3. During voltage transitions, all pins may overshoot Vss to -2.0V and Vcc to +2.0V for periods up to 20ns, see the figures below.

Figure 36. Maximum Negative Overshoot Waveform





Figure 37. Maximum Positive Overshoot Waveform



#### 11-2. Capacitance $TA = 25^{\circ}C$ , f = 1.0 MHz

Symbol	Parameter	Min.	Тур.	Max.	Unit	Conditions
CIN	Input Capacitance			6	pF	VIN = 0V
COUT	Output Capacitance			8	pF	VOUT = 0V



Figure 38. Input Test Waveforms and Measurement Level





Figure 39. Output Loading



P/N: PM2163 REV. 1.2, October 21, 2016 63



## **Table 14. DC Characteristics**

Temperature = -40°C to 85°C for Industrial grade

Symbol	Parameter	Notes	Min.	Тур.	Max.	Units	Test Conditions					
ILI	Input Load Current	1			± 2	uA	VCC = VCC Max, VIN = VCC or GND					
ILO	Output Leakage Current	1			± 2	uA	VCC = VCC Max, VOUT = VCC or GND					
ISB1	VCC Standby Current	1		10	50	uA	VIN = VCC or GND, CS# = VCC					
ISB2	Deep Power-down Current			3	20	uA	VIN = VCC or GND, CS# = VCC					
ICC1	VCC Read	1		2.5	5	mA	f=50MHz, SCLK=0.1VCC/0.9VCC, SO=Open					
1001	VCC Reau	VCC Reau	VCC Read	CT VCC Read	VGC Neau	VCC Neau	<b>I</b>		10	17	mA	fQ=133MHz (4 x I/O read) SCLK=0.1VCC/0.9VCC, SO=Open
ICC2	VCC Program Current (PP)	1		10	15	mA	Program in Progress, CS# = VCC					
ICC3	VCC Write Status Register (WRSR) Current			10	15	mA	Program status register in progress, CS#=VCC					
ICC4	VCC Sector Erase Current (SE)	1		10	15	mA	Erase in Progress, CS#=VCC					
ICC5	VCC Chip Erase Current (CE)	1		10	15	mA	Erase in Progress, CS#=VCC					
VIL	Input Low Voltage		-0.5		0.8	V						
VIH	Input High Voltage		0.7VCC		VCC+0.4	V						
VOL	Output Low Voltage				0.4	V	IOL = 1.6mA					
VOH	Output High Voltage		VCC-0.2			V	IOH = -100uA					

#### Notes:

- 1. Typical values at VCC = 3.3V, T = 25°C. These currents are valid for all product versions (package and speeds).
- 2. Typical value is calculated by simulation.
- 3. The value guaranteed by characterization, not 100% tested in production.



## **Table 15. AC Characteristics**

Temperature = -40°C to 85°C for Industrial grade

Symbol	Alt.	Parameter		Min.	Тур.	Max.	Unit
fSCLK	fC	Clock Frequency for the following FAST_READ, PP, SE, BE, CE, RE RDID, RDSR, WRSR	S, WREN, WRDI,	D.C.			MHz
fRSCLK	fR	Clock Frequency for READ instruc				50	MHz
fTSCLK	fT	Clock Frequency for 2READ/DRE				133	MHz
	fQ	Clock Frequency for 4READ/QREA	D instructions			133	MHz
f4PP		Clock Frequency for 4PP (Quad page 1)	, <del></del>			133	MHz
tCH <sup>(1)</sup>	tCLH	Clock High Time	Normal Read (fRSCLK)				ns
	(OLI)	Oleok Flight Flillo	Others (fSCLK)	45% x (1/fSCLK)			ns
tCL <sup>(1)</sup>	tCLL	Clock Low Time	Normal Read (fRSCLK)				ns
	, CLL		Others (fSCLK)	45% x (1/fSCLK)			ns
tCLCH (2)		Clock Rise Time (peak to peak)		0.1			V/ns
tCHCL (2)		Clock Fall Time (peak to peak)		0.1			V/ns
tSLCH	tCSS	CS# Active Setup Time (relative to		4			ns
tCHSL		CS# Not Active Hold Time (relative	to SCLK)	4			ns
tDVCH	tDSU	Data In Setup Time		2			ns
tCHDX	tDH	Data In Hold Time	3			ns	
tCHSH		CS# Active Hold Time (relative to S	4			ns	
tSHCH		CS# Not Active Setup Time (relative	4			ns	
tSHSL tCSH	+C8H	CS# Deselect Time	Read	15			ns
	10311	CO# Desciect Time	Write/Erase/Program	50			ns
tSHQZ (2)	tDIS	S II ) Lithi it i ) isahia Tima	2.65V-3.6V			10	ns
ISTIQE IDIS	Output Disable Time	3.0V-3.6V			8	ns	
tCLQV	tV	Clock Low to Output Valid	Loading: 15pF			6	ns
ICLQV	10	VCC=2.65V~3.6V	Loading: 30pF			8	ns
tCLQX	tHO	Output Hold Time		1			ns
tESL <sup>(3)</sup>		Erase Suspend Latency				20	us
tPSL <sup>(3)</sup>		Program Suspend Latency				20	us
tPRS <sup>(4)</sup>		Latency between Program Resum	e and next Suspend	0.3	100		us
tERS <sup>(5)</sup>		Latency between Erase Resume a	ind next Suspend	0.3	200		us
tDP		CS# High to Deep Power-down Mo				10	us
tRES1		CS# High to Standby Mode without Ele				100	us
tRES2		CS# High to Standby Mode with E Read	lectronic Signature			100	us
tW		Write Status Register Cycle Time				40	ms
tBP		Byte-Program			10	50	us
tPP		Page Program Cycle Time		0.33	1.2	ms	
tSE		Sector Erase Cycle Time (4KB)			25	200	ms
tBE32K		Block Erase Cycle Time (32KB)			0.14	0.6	S
tBE		Block Erase Cycle Time (64KB)			0.25	1	s
tCE		Chip Erase Cycle Time			10	30	S
tWSR		Write Security Register Time				1	ms
tRCR	1	Recovery Time from Read		20			us
tRCP		Recovery Time from Program		20			us
tRCE		Recovery Time from Erase		12			ms





#### Notes:

- 1. tCH + tCL must be greater than or equal to 1/fC.
- 2. The value guaranteed by characterization, not 100% tested in production.
- 3. Latency time is required to complete Erase/Program Suspend operation until WIP bit is "0".
- 4. For tPRS, minimum timing must be observed before issuing the next program suspend command. However, a period equal to or longer than the typical timing is required in order for the program operation to make progress.
- 5. For tERS, minimum timing must be observed before issuing the next erase suspend command. However, a period equal to or longer than the typical timing is required in order for the erase operation to make progress.



## 12. TIMING ANALYSIS

## Figure 40. Serial Input Timing





Figure 41. Output Timing






#### 13. OPERATING CONDITIONS

#### At Device Power-Up and Power-Down

AC timing illustrated in "Figure 42. AC Timing at Device Power-Up" and "Figure 43. Power-Down Sequence" are for the supply voltages and the control signals at device power-up and power-down. If the timing in the figures is ignored, the device will not operate correctly.

During power-up and power-down, CS# needs to follow the voltage applied on VCC to keep the device not to be selected. The CS# can be driven low when VCC reach Vcc(min.) and wait a period of tVSL.

Figure 42. AC Timing at Device Power-Up



Symbol	Parameter	Notes	Min.	Max.	Unit
tVR	VCC Rise Time	1		500000	us/V

### Notes:

- 1. Sampled, not 100% tested.
- 2. For AC spec tCHSL, tSLCH, tDVCH, tCHDX, tSHSL, tCHSH, tSHCH, tCHCL, tCLCH in the figure, please refer to "Table 15. AC Characteristics".



## Figure 43. Power-Down Sequence

During power-down, CS# needs to follow the voltage drop on VCC to avoid mis-operation.





Figure 44. Power-up Timing





## Figure 45. Power Up/Down and Voltage Drop

For Power-down to Power-up operation, the VCC of flash device must below  $V_{PWD}$  for at least tPWD timing. Please check the table below for more detail.




Table 16. Power-Up/Down Voltage and Timing

Symbol	Parameter	Min.	Max.	Unit
tVSL	VCC(min.) to device operation	800		us
VWI	Write Inhibit Voltage	1.5	2.5	V
$V_{PWD}$	VCC voltage needed to below V <sub>PWD</sub> for ensuring initialization will occur		0.9	V
tPWD	The minimum duration for ensuring initialization will occur	300		us
VCC	VCC Power Supply	2.65	3.6	V

Note: These parameters are characterized only.

## 13-1. Initial Delivery State

The device is delivered with the memory array erased: all bits are set to 1 (each byte contains FFh). The Status Register contains 40h (all Status Register bits are 0 except QE bit: QE=1).



## 14. ERASE AND PROGRAMMING PERFORMANCE

Parameter	Typ. (1)	Max. (2)	Unit
Write Status Register Cycle Time		40	ms
Sector Erase Time (4KB)	25	200	ms
Block Erase Time (64KB)	0.25	1	s
Block Erase Time (32KB)	0.14	0.6	S
Chip Erase Time	10	30	S
Byte Program Time (via page program command)	10	50	us
Page Program Time	0.33	1.2	ms
Erase/Program Cycle	100,000		cycles

#### Notes:

- 1. Typical program and erase time assumes the following conditions: 25°C, 3.3V, and checkerboard pattern.
- 2. Under worst conditions of 85°C and 2.65V.
- 3. System-level overhead is the time required to execute the first-bus-cycle sequence for the programming command.

## **15. DATA RETENTION**

Parameter	Condition	Min.	Max.	Unit
Data retention	55°C	20		years

## 16. LATCH-UP CHARACTERISTICS

	Min.	Max.
Input Voltage with respect to GND on all power pins, SI, CS#	-1.0V	2 VCCmax
Input Voltage with respect to GND on SO	-1.0V	VCC + 1.0V
Current	-100mA	+100mA
Includes all pins except VCC. Test conditions: VCC = 3.0V, one pin at a time	•	






## 17. ORDERING INFORMATION

Please contact Macronix regional sales for the latest product selection and available form factors.

PART NO.	CLOCK (MHz)	TEMPERATURE	PACKAGE	Remark
MX25L3273FM2I-08G	133	-40°C to 85°C	8-SOP (200mil)	
MX25L3273FM2I-08Q	133	-40°C to 85°C	8-SOP (200mil)	




## 18. PART NAME DESCRIPTION





## 19. PACKAGE INFORMATION

Doc. Title: Package Outline for SOP 8L 200MIL (official name - 209MIL)



Dimensions (inch dimensions are derived from the original mm dimensions)

SY UNIT	MBOL	Α	<b>A</b> 1	A2	b	С	D	E	E1	е	L	L1	s	θ
	Min.	1.75	0.05	1.70	0.36	0.19	5.13	7.70	5.18	i	0.50	1.21	0.62	0°
mm	Nom.	1.95	0.15	1.80	0.41	0.20	5.23	7.90	5.28	1.27	0.65	1.31	0.74	5°
	Max.	2.16	0.20	1.91	0.51	0.25	5.33	8.10	5.38		0.80	1.41	0.88	8°
	Min.	0.069	0.002	0.067	0.014	0.007	0.202	0.303	0.204		0.020	0.048	0.024	0°
Inch	Nom.	0.077	0.006	0.071	0.016	0.008	0.206	0.311	0.208	0.050	0.026	0.052	0.029	5°
	Max.	0.085	0.008	0.075	0.020	0.010	0.210	0.319	0.212	_	0.031	0.056	0.035	8°

Dava No	Revision		Refe	erence	
Dwg. No.	Revision	JEDEC	EIAJ		
6110-1406	5				





## **20. REVISION HISTORY**

Revision No 0.01	<ul> <li>Description         <ul> <li>Changed document status from "ADVANCED INFORMATION"</li> <li>TOWNS TOWNS TOWNS</li> </ul> </li> </ul>	<b>Page</b> All	<b>Date</b> NOV/12/2014
	Updated suspend/resume descriptions.	P53-54, 67	
	Revised Key Features on cover page.     Modified tCH/tCL formula.	P1	
	Modified status register QE bit as OTP and Initial Delivery Stat	P67 eP22, 72	
1.0	Removed document status "PRELIMINARY"	All	NOV/24/2014
	2. Removed SRWD.	P22,24-26	
1.1	1. Updated Block diagram	P7	OCT/11/2016
	2. Removed Section 9-14. Performance Enhance Mode Reset	P35	
	<ol><li>Modified Deep Power-down (DP) descriptions.</li></ol>	P43	
	Modified REMS descriptions.	P46	
	<ol><li>Modified Table 9. Suspend Type for WREN command</li></ol>	P51	
	6. Updated tVR values.	P68,70	
	7. Updated part number list.	P72-73	
	8. Added a statement for product ordering information.	P72	
1.2	1. Updated "18. PART NAME DESCRIPTION".	P73	OCT/21/2016





Except for customized products which has been expressly identified in the applicable agreement, Macronix's products are designed, developed, and/or manufactured for ordinary business, industrial, personal, and/or household applications only, and not for use in any applications which may, directly or indirectly, cause death, personal injury, or severe property damages. In the event Macronix products are used in contradicted to their target usage above, the buyer shall take any and all actions to ensure said Macronix's product qualified for its actual use in accordance with the applicable laws and regulations; and Macronix as well as it's suppliers and/or distributors shall be released from any and all liability arisen therefrom.

Copyright© Macronix International Co., Ltd. 2014-2016. All rights reserved, including the trademarks and tradename thereof, such as Macronix, MXIC, MXIC Logo, MX Logo, Integrated Solutions Provider, NBit, NBit, NBit, Macronix NBit, eLiteFlash, HybridNVM, HybridFlash, XtraROM, Phines, KH Logo, BE-SONOS, KSMC, Kingtech, MXSMIO, Macronix vEE, Macronix MAP, Rich Audio, Rich Book, Rich TV, and FitCAM. The names and brands of third party referred thereto (if any) are for identification purposes only.

For the contact and order information, please visit Macronix's Web site at: http://www.macronix.com

# **Mouser Electronics**

**Authorized Distributor** 

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

# Macronix:

<u>MX25L3273FM2I-08G-T</u> <u>MX25L3273FM2I-08G-TB</u> <u>MX25L3273FM2I-08Q-TR</u> <u>MX25L3273FM2I-08Q-TB</u> MX25L3273FM2I-08Q-T MX25L3273FM2I-08G-TR