




REDLINE™

RAPID ENGINEERING DEVELOPMENT SYSTEMS

Modular Platforms Designed by Engineers for Engineers

AURIX™ TC214/224/234 MCU Platform Module



Overview

Designed for use with either REDline Carrier board, or as a standalone development platform, this Module can host a number of AURIX™ MCU derivatives.

The Module also supports easy integration into the customer's target platform as MCU pins are routed out to two 200 position pad arrays on the bottom.

All important standalone operations are made possible by incorporating essential power conversion, clock, system configuration, programming and debugging connections on the Module itself.

Separated Analog and Digital domains make full use of MCU's Analog-to-Digital Converters.

The supplied software (Board Support Package) has all necessary parts for MCU boot configuration, start-up, all written in C code.


Complete hardware development support: schematics, BOM, layout, Gerbers, PCB stack-up, and high-speed design rules.

Features

- Infineon AURIX™ SAK-TC2x4 MCU pin-compatible versions (214/224/234) in TQFP144 package
- Single core up to 200MHz, 2MB flash, 736kB SRAM with HSM, ADAS and Ethernet
- Default 20MHz crystal with optional socket for custom crystal
- Core voltage SMPS for 1.3V generation (optional LDO)
- Infineon DAP 10-position programming and debugging header (or alternative JTAG)
- Generic UART/CLI 4-pin header with USB cable
- SPI to I²C bridge for compatibility with other TC2xx devices
- MCU temperature sensor connected to on-board I²C bus
- System and MCU configuration 8-position DIP switch
- "No solder" headers to configure Module in standalone mode and external power
- Critical voltage rails' supervisor with LED
- User "Status" and "Reset" LEDs
- Very compact design for easy target integration, line-up compatible with remaining TC2xx series

Block Diagram

REDLINE
AND ASSOCIATED DEVELOPMENT SYSTEMS



Compatibility

The Module is designed to work with AURIX™ Base Carrier Development Platform

Part Number: **RDL-DEVCDP-00x**

Ordering Information

Module Part Number: **RDL-MCU2x4-SSxx-EVR13yy-zzz** (see datasheet for exact ordering options)

Supplier: Neutron Controls, 350 Palladium Drive, Suite 102 Ottawa, Ontario, Canada K2V 1A8

WWW.NEUTRONCONTROLS.COM

Mouser Electronics

Authorized Distributor

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

[Neutron Controls:](#)

[RDL-MCU234LA-001](#)